

Table 1
Summary of Anticipated Pipe Infrastructure and Adjacent Natural Resources
Woodridge Lake Sewer District (Prepared on March 15, 2017)

Pipe Segment #	Street Name	Total Length of Pipe (lf)	Community Location ⁸			Length of Proposed Pipeline (lf)									Adjacent to Mapped Wetlands ^{2,3,6}	Adjacent to Mapped Waterbodies ^{4,6}
			Goshen	Torrington	Litchfield	State Road	Non-State Road	New Force Main	Replacement Gravity Sewer ¹	Replacement Force Main ¹	In Sewer Service Area ⁵	Outside Sewer Service Area ⁵				
Alternative T1: Route 4 (Proposed Project)																
T1A	Brush Hill Road	2,800	2,800	-	-	-	2,800	2,800	-	-	-	2,800	30	30		
T1B	Route 63	7,500	7,500	-	-	7,500	-	7,500	-	-	-	7,500	30	30		
T1C	Ple Hill Road	7,500	7,500	-	-	-	7,500	7,500	-	-	-	7,500	240	240		
T1D	East Street	1,300	1,300	-	-	-	1,300	1,300	-	-	-	1,300	-	-		
T1E	Route 4	15,900	5,700	10,200	-	15,900	-	12,400	3,500	-	3,700	12,200	130	130		
Total (Alt. T1) =		35,000	24,800	10,200	-	23,400	11,800	31,500	3,500	-	3,700	31,300	430	430		
Alternative T2: Highland Avenue																
T2A	Brush Hill Road	2,800	2,800	-	-	-	2,800	2,800	-	-	-	2,800	30	30		
T2B	Route 63	5,300	5,100	-	200	5,300	-	5,300	-	-	-	5,300	30	30		
T2C	Deming Road	3,700	1,000	-	2,700	-	3,700	3,700	-	-	-	3,700	-	-		
T2D	Pumping Station Road	300	-	300	-	-	300	300	-	-	-	300	30	30		
T2E	Weed Road	4,500	-	4,500	-	-	4,500	4,500	-	-	-	4,500	70	70		
T2F	Highland Avenue	16,300	-	16,300	-	-	16,300	10,300	6,000	-	4,800	11,500	60	60		
Total (Alt. T2) =		32,900	8,900	21,100	2,900	6,300	27,600	28,900	6,000	-	4,800	28,100	220	220		
Alternative T3: Weed Road																
T3A	Brush Hill Road	2,800	2,800	-	-	-	2,800	2,800	-	-	-	2,800	30	30		
T3B	Route 63	5,300	5,100	-	200	5,300	-	5,300	-	-	-	5,300	30	30		
T3C	Deming Road	3,700	1,000	-	2,700	-	3,700	3,700	-	-	-	3,700	-	-		
T3D	Pumping Station Road	300	-	300	-	-	300	300	-	-	-	300	30	30		
T3E	Weed Road	14,400	-	14,400	-	-	14,400	14,400	-	-	-	14,400	-	-		
T3F	Route 4	10,100	-	10,100	-	10,100	-	6,600	3,500	-	3,700	6,400	490	490		
Total (Alt. T3) =		36,600	8,900	24,800	2,900	15,400	21,200	33,100	3,500	-	3,700	32,900	580	580		
Alternative L1: Via Litchfield																
L1A	Brush Hill Road	2,800	2,800	-	-	-	2,800	2,800	-	-	-	2,800	30	30		
L1B	Route 63	21,700	5,100	-	16,600	21,700	-	21,700	-	-	-	21,700	170	170		
L1C	Route 102	600	-	-	600	600	-	600	-	-	-	600	-	-		
L1D	Route 202	9,200	-	19,700	9,200	28,900	-	7,400	21,500	-	21,800	7,100	60	60		
Total (Alt. L1) =		34,300	7,900	19,700	26,400	51,200	2,800	32,500	21,500	-	21,800	32,200	290	290		

Notes:

- 1 Based on GIS mapping provided by City of Torrington on March 8, 2017 to WLSO.
- 2 State wetlands layer obtained from State GIS layers via US Fish and Wildlife Service.
- 3 Excludes field designated wetlands by soil scientist.
- 4 State waterbodies layer obtained from CT DEEP via State GIS layers.
- 5 Refer to Figure 1.
- 6 Refer to Figure 2.

RECEIVED FOR RECORD
TORRINGTON TOWN CLERK
FEB 20 PM 8:32

