

ALL SWALES SHALL BE LINED WITH NORTH AMERICAN GREEN S75 TEMPORARY NOTED, UNTIL PERMANENT VEGETATIVE COVER IS ESTABLISHED.





SWALE TREATMENT 1 N.A.G. S75 (TEMPORARY)
2 N.A.G. P300 (PERMANENT)

DRAINAGE SWALE TO BE PERMANENTLY SEEDED WITH NEW ENGLAND EROSION CONTROL MIX FOR MOIST SITES

SECTION 4.17

SCALE N.T.S.	CITY OF TORRINGTON Engineering Department
APPROVED	
RV. DATE AUG. 2011	ROADSIDE SWALE DETAIL