



NOTES:

1. BEDDING SHALL BE No.6 (3/4") CRUSHED STONE (CONNDOT FORM 816 ART M.01.01)
2. UNSUITABLE MATERIAL BELOW NORMAL GRADE SHALL BE REPLACED WITH No.6(3/4") CRUSHED STONE (CONNDOT FORM 816, M.01.01) AS DIRECTED BY THE CITY ENGINEER.
3. ALL WORK MUST BE CONDUCTED IN STRICT ACCORDANCE WITH THE LATEST REGULATIONS OF OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA) FOR EXCAVATIONS.

TYPICAL STORM DRAINAGE TRENCH RCP PAVED AREAS

NOT TO SCALE

SCALE N.T.S.	CITY OF TORRINGTON Engineering Department
APPROVED	
RV. DATE	TYPICAL STORM DRAINAGE TRENCH RCP PAVED AREAS
APR. 2009	
AUG. 2011	