



- DESIGN NOTES:**
1. CONCRETE, 4000 P.S.I., 28 DAYS.
 2. REINFORCEMENT, STEEL WIRE MESH, 6"x6" 10/10
 3. TONGUE & GROOVE JOINT SEALED WITH MASTIC SEALANT.
 4. CAST IRON TEES SUPPLIED BY OTHERS.
 5. H-20 LOADING WHEN INSTALLED IN PAVED AREAS.
 6. TANK SIZE REQUIRED MAY BE LARGER THAN MINIMUM 1,000 GALLON TANK. PUBLIC WORKS DIRECTOR TO DETERMINE SIZE BASED ON PROJECTED SEWAGE FLOW DATA TO BE SUBMITTED BY PERMIT APPLICANT.

SCALE N.T.S.		CITY OF TORRINGTON Engineering Department
Approved E.J.F.		
RV. DATE		
JAN. 2002		
JUL. 2010		
AUG. 2011		
		1000 GALLON GREASE TRAP

SECTION 5.22