



NOTES:

1. BEDDING TO BE 6" OF 3/4" CRUSHED STONE
2. UNSUITABLE MATERIAL BELOW NORMAL GRADE SHALL BE REPLACED WITH NO. 6 (3/4") CRUSHED STONE (DOT FORM 816, ART. M.01.01) AS DIRECTED BY THE CITY ENGINEER.
3. ALL WORK MUST BE CONDUCTED IN STRICT ACCORDANCE WITH THE LATEST REGULATIONS OF OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA) FOR EXCAVATIONS.

SANITARY SEWER TRENCH UNDER PAVEMENT

NOT TO SCALE

SECTION 5.8

SCALE N.T.S.	CITY OF TORRINGTON Engineering Department
APPROVED	
RV. DATE	SANITARY SEWER TRENCH UNDER PAVEMENT
OCT. 2002	
APR. 2009	
AUG. 2011	