

Stormwater Management Report

For the Proposed:

EdAdvance School Building

Located at:

95-104 Grove Street
Torrington, Connecticut

Prepared for Submission to:

City of Torrington, Connecticut

March 31, 2023

Revised April 14, 2023

Prepared for:

A. Secondino & Son, Inc.
PO Box 622 / 21 Acorn Road
Branford, CT 06405

Prepared by:



BL Companies
355 Research Parkway
Meriden, Connecticut 06450
Phone: (203) 630-1406

BL Project Number: 2202472



Contents

Executive Summary	1
Existing Site Conditions and Hydrologic Conditions	2
Developed Site Conditions and Hydrologic Conditions	4
Stormwater Management	8
Stormwater Quality	9
Summary	10

Appendix A: Location Maps

- Figure 1: Aerial Location Map
- Figure 2: USGS Location Map
- Figure 3: NRCS Soil Survey Report
- Figure 4: FEMA Federal Insurance Rate Map
- Figure 5: NOAA Atlas 14 Storm Data

Appendix B: Pre-development Hydrology (2-, 5-, 10-, 25-, 50-, and 100-year storms)

Appendix C: Post-development Hydrology (2-, 5-, 10-, 25-, 50-, and 100-year storms)

Appendix D: Water Quality Calculations

- CTDEEP Water Quality Volume Calculations
- CTDEEP Water Quality Flow Calculations
- CTDEEP Groundwater Recharge Calculations
- HydroCAD WQV Stage Volume Table
- CTDOT Hydrodynamic Separator Sizing
- Treatment Train Efficiency Worksheet

Appendix E: Drainage Maps

- ED-1 – Existing Drainage Map
- PD-1 – Proposed Drainage Map
- GD-1 – Grading and Drainage Plan

Appendix F: Stormwater System Operation and Maintenance Manual

Executive Summary

This report has been prepared in support of a Permit Application by A. Secondino & Son, Inc. to the City of Torrington for the proposed EdAdvance school building development and redevelopment of the existing Sacred Heart Church properties at 95 Grove Street (Lot 1) and 104 Grove Street (Lot 2). The existing Lot 1 is approximately 1.29 acres in size and is currently developed with an existing convent building and was the previous location of a school building demolished within the past decade. The existing Lot 2 is approximately 0.97 acres in size and is currently developed with the Sacred Heart Church building and rectory. The proposed EdAdvance school development is to be constructed on Lot 1, while work on Lot 2 consists of reconfiguration of existing parking areas. The properties are situated with Lot 1 on the western side of Grove Street and Lot 2 on the eastern side. Lot 2 is also bordered by Brook Street to the east. The parcels are bordered by residential properties on all sides. The East Branch Naugatuck River runs from north to south off of Lot 1's western boundary. A portion of the 75' wetland buffer area from alluvial wetland soils associated with the river exists on Lot 1. No existing stormwater management systems exist on either site, all stormwater runoff is discharged offsite, untreated, by overland surface flow.

The project parcels are located at a high point in elevation of Grove Street. In general, the existing topography Grove Street slopes from high point down to the north and south from approximately elevation 591' at the high point to 519' at the northern extent and 583' in the southern extent. Slopes on Lot 1 vary from approximately 2-3% along Grove Street to approximately 25% at the embankment drop-off to the west. Slopes on Lot 2 vary from 2-6% along Grove Street to approximately 67% at the embankment drop-off to Brook Street in the east. Several retaining walls exist on Lot 2 along the boundary with Brook Street supporting Lot 2 above Brook Street elevation.

Proposed site improvements will include a ±10,300 square foot school building with paved parking areas and driveways, landscaped areas, pedestrian sidewalks, site utilities and lighting, and stormwater management system upgrades. The proposed stormwater management system is designed to be in compliance with the 2002 State of Connecticut Guidelines for Soil Erosion and Sediment Control, and the 2004 State of Connecticut Stormwater Quality Manual.

A HydroCAD model, using TR-55 methodology, was developed to evaluate the existing and proposed drainage conditions of the property. The results of the analysis demonstrate that there will not be an increase in peak stormwater runoff rates for the 1" depth, 2-, 5-, 10-, 25-, 50-, and 100-year storm events. The proposed stormwater management system has been designed to attenuate the increased flows generated by the proposed development.

Stormwater quality is being addressed by a formalized street sweeping program, deep sump and hooded outlet catch basins, hydrodynamic separator, sediment isolator row, and an underground infiltration system. These features will provide the minimum required 80% TSS removal as required in the CT Stormwater Quality Manual.

Existing Site Conditions and Hydrologic Conditions

General Site Information

The site soil identified by the United States Department of Agriculture (USDA) Natural Resources Conservation Services (NRCS) is Hinckley-Urban Land Complex, 3 to 15 percent slopes. Per the USDA, the NRCS Hydrologic Soil Group rating for soil within the project area is A. A copy of the USDA NRCS Hydrologic Soil Group Map is included in Appendix A for reference.

Per the FEMA Flood Insurance Rate Map Number 0950810007B for the City of Torrington, Connecticut in Litchfield County, map revised date: April 4, 1983, the site resides in FEMA Flood Hazard Area C (unshaded). Zone C (unshaded) is defined as “areas determined to be outside the 500-year floodplain”. A copy of the FEMA Flood insurance rate Map is included in Appendix A for reference.

Existing Hydrologic Conditions

The existing site drainage area that was analyzed totals 2.81 acres and is approximately 58.2% impervious. The existing hydrologic model includes impervious areas associated with the previously constructed and recently demolished school building that was located on Lot 1. The hydrologic model analyzes peak flows to five main design points, DP-1 through DP-5. In the existing condition, the majority of stormwater runoff from Lot 1 sheet flows from west to east and eventually conveyed into the Grove Street gutter system untreated, which is then split between flow to the south gutter (DP-2) and the north gutter (DP-3) by the local roadway high point. A small portion of Lot 1 discharges stormwater to the west toward riverine wetland areas (DP-1). The majority of stormwater runoff from Lot 2 sheet flows from west to east and eventually conveyed into the Brook Street gutter system untreated, which is then also split between flow to the south gutter (DP-4) and flow to the north gutter (DP-5) by a local roadway high point. Water runoff currently flows over the retaining walls located on the boundary with Brook Street. The peak total offsite flow is also being analyzed (DP-6).

The following is a brief analysis of the existing design points as shown on the enclosed Existing Drainage Map (ED-1) Map, in Appendix E.

Existing Drainage Area 10 (EDA-10): This drainage area consists of the portions of Lot 1 from which stormwater runoff sheet flows directly to the riverine wetland systems to the west of Lot 1 (DP-1). It is 0.28 acres and is approximately 12.8% impervious. EDA-10 consists mainly of lawn areas with a smaller contributing areas of impervious roof and paved driveway ground cover.

Existing Drainage Area 20 (EDA-20): This drainage area consists of the portions of Lots 1 and 2 from which stormwater runoff sheet flows directly into the Grove Street gutter system flowing south (DP-2). It is 1.54 acres and is approximately 81.2% impervious. EDA-20 consists of impervious paved parking, drive aisle, roadway, and roof areas located on both sides of Grove Street and including impervious areas associated with the previously demolished school building. Lawn cover contributes runoff from smaller pervious areas.

Existing Drainage Area 30 (EDA-30): This drainage area consists of the portions of Lots 1 and 2 from which stormwater runoff sheet flows directly into the Grove Street gutter system flowing north (DP-3). It is 0.21 acres and is approximately 55.1% impervious. EDA-30 consists of impervious paved parking, drive aisle, roadway, and roof areas located west of Grove Street associated with the existing convent building and rectory. Lawn cover contributes runoff from smaller pervious areas.

Existing Drainage Area 40 (EDA-40): This drainage area consists of the portions of Lot 2 from which stormwater runoff sheet flows directly into the Brook Street gutter system flowing south (DP-4). It is 0.51 acres and is approximately 36.6% impervious. EDA-40 consists of impervious paved parking, drive aisle, roadway, and roof areas located east of Grove Street associated with the existing church and rectory building. Lawn cover contributes runoff from pervious areas.

Existing Drainage Area 50 (EDA-50): This drainage area consists of the portions of Lot 2 from which stormwater runoff sheet flows directly into the Brook Street gutter system flowing north (DP-5). It is 0.26 acres and is approximately 17.3% impervious. EDA-50 consists of impervious paved parking, drive aisle, roadway, and roof areas located east of Grove Street associated with the existing church and rectory building. Lawn cover contributes runoff from pervious areas.

Table 1 – Pre-Development Drainage Characteristics

Drainage Area	Area (square feet)	Composite Curve Number	Impervious Cover (%)	Time of Concentration (minutes)
EDA-10 (Area Draining Offsite West)	12,270	55	12.8	5.0
EDA-20 (Area to Grove Street South)	67,225	89	81.2	7.1
EDA-30 (Area to Grove Street North)	9,035	76	55.1	6.1
EDA-40 (Area to Brook Street South)	22,400	67	36.3	5.0
EDA-50 (Area to Brook Street North)	11,465	57	17.3	5.0

Table 2 – Pre-Development Conditions Peak Flows

Analysis Point	Peak Flow (cfs)						
	1”	2-yr	5-yr	10-yr	25-yr	50-yr	100-yr
Design Point 1 (Offsite Flow West)	0.00	0.04	0.23	0.42	0.71	0.95	1.21
Design Point 2 (Grove Street South)	0.46	4.59	6.29	7.68	9.52	10.91	12.34
Design Point 3 (Grove Street North)	0.00	0.37	0.60	0.79	1.06	1.26	1.47
Design Point 4 (Brook Street South)	0.00	0.54	1.05	1.51	2.16	2.67	3.21
Design Point 5 (Brook Street North)	0.00	0.07	0.26	0.45	0.74	0.96	1.22
Design Point 6 (Total Offsite Flow)	0.46	5.59	8.37	10.75	14.04	16.57	19.22

Developed Site Conditions and Hydrologic Conditions

In the proposed condition, stormwater collection and conveyance systems will be installed on site and will be supplemented with an underground stormwater detention system installed to mitigate the increase in peak flow from the site as a result of increased impervious cover in the water quality storm event. The underground detention system will also serve to detain and infiltrate the required water quality volume. The proposed stormwater system will also provide water quality improvements through the implementation of a formalized street sweeping program for the impervious surfaces and the installation of deep sump and hooded outlet catch basins, a sediment isolator row, and the underground infiltration system. These measures will treat the stormwater quality flow through structural means to provide water quality treatment in conformance with the State of Connecticut Water Quality Manual.

The proposed site drainage area totals 2.81 acres and is approximately 59.8% impervious. For the hydrologic analysis, the developed site retained the same Design Points as the existing model. The following sub-drainage areas were developed to model the proposed site improvements.

Proposed Drainage Area 100 (PDA-100): This drainage area consists of the portions of Lot 1 from which stormwater runoff will continue to sheet flow directly to the riverine wetland systems to the west of Lot 1 (DP-1), bypassing stormwater collection systems. It is 0.44 acres and is approximately 6.8% impervious. PDA-100 consists mainly of lawn areas with smaller contributing areas of impervious roof from the existing convent building and concrete pads.

Proposed Drainage Area 110 (PDA-110): This drainage area consists of the proposed paved parking area located south of the proposed school building on Lot 1. Stormwater runoff from this area is collected in catch basin inlets and conveyed through subsurface piping into the underground detention system (UDS). The UDS will be outfitted with a sediment isolator row for water quality treatment prior to discharge into the water quality volume and peak flow mitigation portion of the UDS. The UDS will discharge to a level spreader system for velocity dissipation prior to ultimately discharging to the riverine wetland systems to the west of Lot 1 (DP-1). It is 0.32 acres and is approximately 85.2% impervious. PDA-110 consists mainly of paved parking and drive aisle areas with smaller portions of lawn and landscaped surface cover.

Proposed Drainage Area 120 (PDA-120): This drainage area consists of the proposed EdAdvance school building roof. Stormwater runoff from the roof will be conveyed through subsurface piping into the underground detention system (UDS). The UDS will discharge to a level spreader system for velocity dissipation prior to ultimately discharging to the riverine wetland systems to the west of Lot 1 (DP-1). It is 0.24 acres and is entirely impervious.

Proposed Drainage Area 130 (PDA-130): This drainage area consists of the proposed paved parking area located south of the existing church building on Lot 2. Stormwater runoff from this area is collected in catch basin inlets and conveyed through subsurface piping into the underground detention system (UDS) on Lot 1. The UDS will be outfitted with a sediment isolator row for water quality treatment prior to discharge into the water quality volume and peak flow mitigation portion of the UDS. The UDS will discharge to a level spreader system for velocity dissipation prior to ultimately discharging to the riverine wetland systems to the west of Lot 1 (DP-1). It is 0.19 acres and is approximately 84.6% impervious. PDA-130 consists mainly of paved parking and drive aisle areas with smaller portions of lawn and landscaped surface cover.

Proposed Drainage Area 140 (PDA-140): This drainage area consists of the proposed paved parking area located to the north, east, and south of the existing rectory building on Lot 2. Stormwater runoff from this area is collected in catch basin inlets and conveyed through subsurface piping into the underground detention system (UDS) on Lot 1. The UDS will be outfitted with a sediment isolator row for water quality treatment prior to discharge into the water quality volume and peak flow mitigation portion of the UDS. The UDS will discharge to a level spreader system

for velocity dissipation prior to ultimately discharging to the riverine wetland systems to the west of Lot 1 (DP-1). It is 0.27 acres and is approximately 74.4% impervious. PDA-140 consists mainly of paved parking and drive aisle areas with smaller portions of lawn and landscaped surface cover. The rear half of the existing rectory building also drains to this area.

Proposed Drainage Area 200 (PDA-200): This drainage area consists of the portions of Lots 1 and 2 from which stormwater runoff will continue to sheet flow directly into the Grove Street gutter system flowing south (DP-2). It is 0.80 acres and is approximately 70.7% impervious. PDA-200 consists of impervious paved parking, drive aisle, and roadway areas located on both sides of Grove Street and including roof areas from the existing church and convent buildings on the east side of the street that will continue to drain as they do in existing condition. Lawn cover contributes runoff from smaller pervious areas.

Proposed Drainage Area 300 (PDA-300): This drainage area consists of the portions of Lots 1 and 2 from which stormwater runoff will continue to sheet flow directly into the Grove Street gutter system flowing north (DP-3). It is 0.20 acres and is approximately 57.5% impervious. PDA-300 consists of impervious paved parking, drive aisle, roadway, and roof areas located on both sides of Grove Street associated with the existing convent building and rectory. Lawn cover contributes runoff from smaller pervious areas.

Proposed Drainage Area 400 (PDA-400): This drainage area consists of the portions of Lot 2 from which stormwater runoff will continue to sheet flow directly into the Brook Street gutter system flowing south (DP-4). It is 0.25 acres and is approximately 36.3% impervious. PDA-400 consists of impervious paved parking, drive aisle, roadway, and roof areas located east of Grove Street associated with the existing church and rectory building. Lawn cover contributes runoff from pervious areas.

Proposed Drainage Area 500 (PDA-500): This drainage area consists of the portions of Lot 2 from which stormwater runoff will continue to sheet flow directly into the Brook Street gutter system flowing north (DP-5). It is 0.09 acres and is approximately 1.1% impervious. PDA-500 consists of impervious paved parking, drive aisle, roadway, and roof areas located east of Grove Street associated with the existing church and rectory building. Lawn cover contributes runoff from pervious areas.

Table 3 – Post-Development Drainage Characteristics

Drainage Area	Area (square feet)	Composite Curve Number	Impervious Cover (%)	Time of Concentration (minutes)
PDA-100 (Area Draining Offsite West)	19,320	43	6.8	5.00
PDA-110 (School Parking Area to UDS)	14,030	89	85.2	5.50
PDA-120 (School Roof Area to UDS)	10,425	98	100.0	5.00
PDA-130 (Church Parking Area to UDS)	8,295	89	84.6	5.00
PDA-140 (Rectory Parking Area to UDS)	11,585	83	74.4	5.00
PDA-200 (Area to Grove Street South)	34,990	81	70.7	7.60
PDA-300 (Area to Grove Street North)	8,855	73	57.5	6.10
PDA-400 (Area to Brook Street South)	10,875	60	36.3	5.00
PDA-500 (Area to Brook Street North)	4,020	40	1.1	5.00

Table 4 – Post-Development Conditions Peak Flows

Analysis Point	Peak Flow (cfs)						
	1"	2-yr	5-yr	10-yr	25-yr	50-yr	100-yr
Design Point 1 (Offsite Flow West)	0.00	0.06	0.70	2.75	6.77	8.09	9.41
Design Point 2 (Grove Street South)	0.04	1.68	2.54	3.25	4.21	4.94	5.69
Design Point 3 (Grove Street North)	0.00	0.30	0.52	0.70	0.96	1.16	1.36
Design Point 4 (Brook Street South)	0.00	0.12	0.33	0.52	0.80	1.03	1.28
Design Point 5 (Brook Street North)	0.00	0.00	0.00	0.01	0.05	0.10	0.16
Design Point 6 (Total Offsite Flow)	0.04	2.10	3.35	6.15	12.71	15.21	17.77

Table 5 – Existing vs Proposed Peak Rates of Runoff

Drainage Area	Peak Flow Rate in Cubic Feet per Second (cfs)						
	1”	2-yr	5-yr	10-yr	25-yr	50-yr	100-yr
Design Point 1							
Existing	0.00	0.04	0.23	0.42	0.71	0.95	1.21
Proposed	0.00	0.06	0.70	2.75	6.77	8.09	9.41
Change	0.00	+0.02	+0.47	+2.33	+6.06	+7.14	+8.20
Design Point 2							
Existing	0.46	4.59	6.29	7.68	9.52	10.91	12.34
Proposed	0.04	1.68	2.54	3.25	4.21	4.94	5.69
Change	-0.42	-2.91	-3.75	-4.43	-5.31	-5.97	-6.65
Design Point 3							
Existing	0.00	0.37	0.60	0.79	1.06	1.26	1.47
Proposed	0.00	0.30	0.52	0.70	0.96	1.16	1.36
Change	0.00	-0.07	-0.08	-0.09	-0.10	-0.10	-0.11
Design Point 4							
Existing	0.00	0.54	1.05	1.51	2.16	2.67	3.21
Proposed	0.00	0.12	0.33	0.52	0.80	1.03	1.28
Change	0.00	-0.42	-0.72	-0.99	-1.36	-1.64	-1.93
Design Point 5							
Existing	0.00	0.07	0.26	0.45	0.74	0.96	1.22
Proposed	0.00	0.00	0.00	0.01	0.05	0.10	0.16
Change	0.00	-0.07	-0.26	-0.44	-0.69	-0.86	-1.06
Design Point 6							
Existing	0.46	5.59	8.37	10.75	14.04	16.57	19.22
Proposed	0.04	2.10	3.35	6.15	12.71	15.21	17.77
Change	-0.42	-3.49	-5.02	-4.60	-1.33	-1.36	-1.45

Stormwater Management

Hydrologic Modeling of the Entire Site

The hydrologic analysis to determine peak stormwater discharge rates was performed using the HydroCAD stormwater modeling system computer program, version 10.00 developed by HydroCAD Software Solutions, LLC. Hydrographs for each watershed were developed using the SCS Synthetic Unit Hydrograph Method. Rainfall depths and distribution per the NOAA Atlas 14 for Torrington, CT were used for the calculation of peak flow rates and are listed in Table 6. The drainage areas, or subcatchments as labeled by the program, are depicted by hexagons on the

attached drainage diagrams. Pre-development HydroCAD output can be found in Appendix B and Post-development HydroCAD output can be found in Appendix C.

Table 6 – Rainfall Depths per NOAA Atlas 14

Return Period	24-hour Rainfall Depth
1” depth	1.00”
2-year	3.52”
5-year	4.72”
10-year	5.71”
25-year	7.07”
50-year	8.07”
100-year	9.18”

Stormwater Quality

Along with the reduction of the overall total peak stormwater discharge rate, an important element of the proposed drainage system is to improve the quality of stormwater leaving the property. Per the DEEP 2004 Stormwater Quality Manual “The pollutant reduction criterion is designed to improve the water quality of stormwater discharges by treating a prescribed water quality volume or associated peak flow, referred to as the water quality flow. Most treatment practices described in this Manual use a volume-based sizing criterion. The exceptions are grass drainage channels, proprietary stormwater treatment devices, and flow diversion structures, where a peak flow rate is utilized.” To adhere to the pollution reduction criteria of the manual, numerous Best Management Practices (BMPs) have been implemented in this design. The most basic preventive measure of the stormwater treatment train is to implement regular sweeping of the paved areas and annual cleaning of the catch basin sumps, underground detention system, and sediment isolator row, which allows continuous proper function of stormwater systems and prevents sediment from reaching outlet locations. The operation and maintenance manual for the application will have a standard required pavement sweeping schedule.

A variety of stormwater collection and treatment systems will be implemented in the proposed project. Water quality improvements will be installed through utilization of a sediment isolator row for removal of total suspended solids (TSS) as well as hydrocarbons including gasoline and oil. Regular maintenance, including removing the existing debris and sediment within each of the existing catch basins and proposed catch basins on site, shall be implemented to improve the overall removal of TSS and hydrocarbons within the existing system. Runoff from the proposed

development area will be piped to the sediment isolator row for treatment prior to discharge into underground stormwater detention systems for infiltration and ultimately conveyed offsite to the western wetland area. The underground detention system will also provide stormwater settling potential for further TSS and oil capture potential, to be removed offsite with proper maintenance. As a result of the various treatment systems, significant stormwater quality improvements are being provided for the site which currently operates with no treatment devices installed. The sediment isolator row works in conjunction with a flow splitter manhole to divert the 1" depth water quality flow into the isolation chambers.

All catch basins in new parking and/or paved areas will have a minimum of four-foot-deep sumps to collect sediment carried in the runoff. Catch basins in grassed areas will also have four-foot-deep sumps. The standard sump required by the CTDOT drainage manual is 2 feet. The additional 2 feet of sump depth will help to remove more sediment from the stormwater runoff. All catch basin outlets will be fitted with 'hoods' which remove floating debris and petroleum based contaminants as they float to the surface in the individual catch basin and are impounded in the structure so they can be properly removed during regular maintenance.

In addition to the WQF, the required sitewide water quality volume (WQV) will also be detained and infiltrated on site. The proposed underground detention system will detain and infiltrate the required water quality volume for the site per the DEEP 2004 Stormwater Quality Manual as shown in the Water Quality Volume Calculations found in Appendix D. Water Quality Flow calculations can also be found in Appendix D.

Summary

The post-development total peak discharge rate for the total developed site has been decreased for all storm events. The proposed underground stormwater detention system has been designed to attenuate peak flows for the 1" depth water quality storm event for flows directed toward the western wetland area. Stormwater quality is being addressed by a formalized street sweeping program, deep sump and hooded outlet catch basins, hydrodynamic separator, sediment isolator row, and an underground infiltration system. These features will provide the minimum required 80% TSS removal as required in the CT Stormwater Manual. The proposed stormwater management system will meet the stormwater quality requirements of the State of Connecticut.

APPENDIX A

LOCATION MAPS

Figure 1: Aerial Location Map


Figure 2: USGS Location Map

Figure 3: NRCS Soil Survey Report


Figure 4: FEMA Federal Insurance Rate Map

Figure 5: NOAA Atlas 14 Storm Data





































Hydrologic Soil Group—State of Connecticut
(95-104 Grove Street - Torrington, CT)



Soil Map may not be valid at this scale.



MAP LEGEND

Area of Interest (AOI)		 C
Area of Interest (AOI)		 C/D
		 D
		 Not rated or not available
Soils		
Soil Rating Polygons		
 A		
 A/D		
 B		
 B/D		
 C		
 C/D		
 D		
 Not rated or not available		
Soil Rating Lines		
 A		
 A/D		
 B		
 B/D		
 C		
 C/D		
 D		
 Not rated or not available		
Soil Rating Points		
 A		
 A/D		
 B		
 B/D		
Water Features		
 Streams and Canals		
Transportation		
 Rails		
 Interstate Highways		
 US Routes		
 Major Roads		
 Local Roads		
Background		
 Aerial Photography		

MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:12,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service
Web Soil Survey URL:
Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: State of Connecticut
Survey Area Data: Version 22, Sep 12, 2022

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Jun 12, 2020—Sep 15, 2020

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.

Hydrologic Soil Group

Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI
109	Fluvaquents-Udifulvents complex, frequently flooded	B/D	0.1	1.3%
238C	Hinckley-Urban land complex, 3 to 15 percent slopes	A	6.9	98.7%
Totals for Area of Interest			7.0	100.0%

Description

Hydrologic soil groups are based on estimates of runoff potential. Soils are assigned to one of four groups according to the rate of water infiltration when the soils are not protected by vegetation, are thoroughly wet, and receive precipitation from long-duration storms.

The soils in the United States are assigned to four groups (A, B, C, and D) and three dual classes (A/D, B/D, and C/D). The groups are defined as follows:

Group A. Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.

Group B. Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.

Group C. Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.

Group D. Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.



If a soil is assigned to a dual hydrologic group (A/D, B/D, or C/D), the first letter is for drained areas and the second is for undrained areas. Only the soils that in their natural condition are in group D are assigned to dual classes.

Rating Options

Aggregation Method: Dominant Condition

Component Percent Cutoff: None Specified

Tie-break Rule: Higher



NATIONAL FLOOD INSURANCE PROGRAM


FIRM
FLOOD INSURANCE RATE MAP

CITY OF
TORRINGTON,
CONNECTICUT
LITCHFIELD COUNTY

PANEL 7 OF 14
(SEE MAP INDEX FOR PANELS NOT PRINTED)

COMMUNITY-PANEL NUMBER
095081 0007 B

MAP REVISED:
APRIL 4, 1983



Federal Emergency Management Agency

This is an official FIRMette showing a portion of the above-referenced flood map created from the MSC FIRMette Web tool. This map does not reflect changes or amendments which may have been made subsequent to the date on the title block. For additional information about how to make sure the map is current, please see the Flood Hazard Mapping Updates Overview Fact Sheet available on the FEMA Flood Map Service Center home page at <https://msc.fema.gov>.



POINT PRECIPITATION FREQUENCY ESTIMATES

Sanja Perica, Sandra Pavlovic, Michael St. Laurent, Carl Trypaluk, Dale Unruh, Orlan Wilhite

NOAA, National Weather Service, Silver Spring, Maryland

[PF_tabular](#) | [PF_graphical](#) | [Maps & aerials](#)

PF tabular





PDS-based point precipitation frequency estimates with 90% confidence intervals (in inches)¹										
Duration	Average recurrence interval (years)									
	1	2	5	10	25	50	100	200	500	1000
5-min	0.358 (0.272-0.468)	0.427 (0.323-0.558)	0.539 (0.408-0.707)	0.632 (0.475-0.834)	0.759 (0.554-1.04)	0.856 (0.614-1.20)	0.955 (0.666-1.39)	1.06 (0.709-1.58)	1.20 (0.778-1.86)	1.32 (0.833-2.08)
10-min	0.508 (0.385-0.663)	0.605 (0.458-0.790)	0.763 (0.576-1.00)	0.895 (0.672-1.18)	1.08 (0.784-1.48)	1.21 (0.868-1.70)	1.35 (0.943-1.96)	1.50 (1.00-2.24)	1.71 (1.10-2.64)	1.87 (1.18-2.95)
15-min	0.597 (0.453-0.780)	0.711 (0.539-0.930)	0.897 (0.678-1.18)	1.05 (0.790-1.39)	1.26 (0.923-1.74)	1.43 (1.02-2.00)	1.59 (1.11-2.31)	1.77 (1.18-2.64)	2.01 (1.30-3.11)	2.19 (1.39-3.47)
30-min	0.814 (0.618-1.06)	0.970 (0.735-1.27)	1.22 (0.924-1.61)	1.43 (1.08-1.89)	1.72 (1.26-2.37)	1.95 (1.39-2.73)	2.17 (1.51-3.15)	2.41 (1.61-3.60)	2.74 (1.77-4.23)	2.99 (1.89-4.73)
60-min	1.03 (0.782-1.35)	1.23 (0.930-1.61)	1.55 (1.17-2.03)	1.82 (1.37-2.40)	2.18 (1.59-3.00)	2.46 (1.77-3.45)	2.75 (1.92-3.99)	3.05 (2.04-4.56)	3.47 (2.24-5.36)	3.79 (2.40-5.99)
2-hr	1.36 (1.04-1.77)	1.60 (1.22-2.07)	1.98 (1.50-2.58)	2.30 (1.74-3.01)	2.73 (2.01-3.74)	3.06 (2.21-4.28)	3.41 (2.40-4.94)	3.79 (2.54-5.64)	4.33 (2.81-6.68)	4.78 (3.03-7.52)
3-hr	1.58 (1.21-2.04)	1.85 (1.41-2.39)	2.29 (1.75-2.98)	2.66 (2.02-3.47)	3.16 (2.34-4.32)	3.54 (2.57-4.95)	3.94 (2.79-5.73)	4.40 (2.96-6.54)	5.08 (3.30-7.82)	5.64 (3.59-8.87)
6-hr	1.98 (1.53-2.55)	2.36 (1.81-3.03)	2.97 (2.28-3.84)	3.48 (2.66-4.52)	4.18 (3.11-5.71)	4.70 (3.44-6.58)	5.27 (3.77-7.70)	5.95 (4.01-8.82)	7.01 (4.56-10.8)	7.91 (5.05-12.4)
12-hr	2.40 (1.86-3.06)	2.95 (2.28-3.77)	3.84 (2.96-4.92)	4.58 (3.51-5.90)	5.60 (4.20-7.63)	6.34 (4.68-8.88)	7.17 (5.19-10.5)	8.21 (5.55-12.1)	9.86 (6.44-15.1)	11.3 (7.24-17.7)
24-hr	2.79 (2.17-3.53)	3.52 (2.74-4.46)	4.72 (3.66-6.00)	5.71 (4.40-7.31)	7.07 (5.34-9.63)	8.07 (6.00-11.3)	9.18 (6.73-13.5)	10.6 (7.21-15.7)	13.0 (8.52-19.9)	15.1 (9.71-23.6)
2-day	3.14 (2.46-3.95)	4.03 (3.15-5.08)	5.48 (4.28-6.94)	6.69 (5.19-8.52)	8.35 (6.35-11.3)	9.55 (7.17-13.4)	10.9 (8.09-16.2)	12.8 (8.68-18.7)	15.9 (10.4-24.2)	18.6 (12.0-29.0)
3-day	3.42 (2.69-4.29)	4.40 (3.46-5.52)	6.00 (4.70-7.56)	7.33 (5.70-9.29)	9.15 (6.99-12.4)	10.5 (7.89-14.6)	12.0 (8.91-17.7)	14.0 (9.56-20.6)	17.5 (11.5-26.6)	20.6 (13.3-32.0)
4-day	3.68 (2.90-4.60)	4.73 (3.72-5.91)	6.43 (5.05-8.08)	7.85 (6.13-9.93)	9.80 (7.50-13.3)	11.2 (8.46-15.6)	12.8 (9.55-18.9)	15.0 (10.2-21.9)	18.7 (12.3-28.4)	22.1 (14.3-34.2)
7-day	4.40 (3.48-5.47)	5.58 (4.41-6.94)	7.50 (5.92-9.38)	9.10 (7.14-11.4)	11.3 (8.68-15.2)	12.9 (9.76-17.9)	14.7 (11.0-21.5)	17.1 (11.7-25.0)	21.2 (14.0-32.1)	24.9 (16.1-38.4)
10-day	5.13 (4.07-6.35)	6.37 (5.06-7.90)	8.40 (6.65-10.5)	10.1 (7.94-12.6)	12.4 (9.54-16.6)	14.1 (10.7-19.4)	16.0 (11.9-23.3)	18.5 (12.7-26.9)	22.7 (15.0-34.3)	26.5 (17.2-40.8)
20-day	7.45 (5.95-9.16)	8.74 (6.97-10.8)	10.8 (8.62-13.4)	12.6 (9.96-15.7)	15.0 (11.6-19.8)	16.7 (12.7-22.7)	18.7 (13.9-26.7)	21.2 (14.6-30.6)	25.2 (16.8-37.9)	28.7 (18.7-44.2)
30-day	9.38 (7.52-11.5)	10.7 (8.56-13.1)	12.8 (10.2-15.8)	14.6 (11.6-18.1)	17.0 (13.1-22.2)	18.8 (14.2-25.2)	20.7 (15.3-29.2)	23.1 (16.0-33.2)	26.8 (17.8-40.1)	29.9 (19.5-45.9)
45-day	11.7 (9.45-14.3)	13.1 (10.5-16.0)	15.2 (12.2-18.7)	17.0 (13.6-21.1)	19.5 (15.1-25.3)	21.4 (16.2-28.4)	23.3 (17.1-32.4)	25.6 (17.8-36.6)	28.7 (19.2-42.9)	31.3 (20.4-47.9)
60-day	13.7 (11.0-16.6)	15.1 (12.1-18.3)	17.3 (13.9-21.2)	19.2 (15.3-23.6)	21.8 (16.8-28.0)	23.7 (17.9-31.3)	25.7 (18.7-35.2)	27.8 (19.4-39.6)	30.5 (20.5-45.4)	32.6 (21.3-49.8)

¹ Precipitation frequency (PF) estimates in this table are based on frequency analysis of partial duration series (PDS). Numbers in parenthesis are PF estimates at lower and upper bounds of the 90% confidence interval. The probability that precipitation frequency estimates (for a given duration and average recurrence interval) will be greater than the upper bound (or less than the lower bound) is 5%. Estimates at upper bounds are not checked against probable maximum precipitation (PMP) estimates and may be higher than currently valid PMP values. Please refer to NOAA Atlas 14 document for more information.

[Back to Top](#)

PF graphical


PDS-based depth-duration-frequency (DDF) curves
 Latitude: 41.8084°, Longitude: -73.1192°




[Back to Top](#)

Maps & aerials

Small scale terrain




Large scale terrain



Large scale map



Large scale aerial




[Back to Top](#)

[US Department of Commerce](#)
[National Oceanic and Atmospheric Administration](#)
[National Weather Service](#)
[National Water Center](#)
1325 East West Highway
Silver Spring, MD 20910
Questions?: HDSC.Questions@noaa.gov

[Disclaimer](#)

APPENDIX B
PRE-DEVELOPMENT HYDROLOGY



C-CALC-2202472-Existing Conditions

Type III 24-hr 1" Depth Rainfall=1.00"

Prepared by BL Companies

Printed 3/29/2023

HydroCAD® 10.00-25 s/n 01334 © 2019 HydroCAD Software Solutions LLC

Page 2

Time span=0.00-28.00 hrs, dt=0.01 hrs, 2801 points
 Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
 Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

SubcatchmentEDA-10: Area Draining Runoff Area=12,270 sf 12.84% Impervious Runoff Depth=0.00"
 Flow Length=50' Slope=0.0300 1' Tc=5.0 min CN=55 Runoff=0.00 cfs 0 cf

SubcatchmentEDA-20: Area Draining to Runoff Area=67,225 sf 81.17% Impervious Runoff Depth=0.28"
 Flow Length=436' Tc=7.1 min CN=89 Runoff=0.46 cfs 1,596 cf

SubcatchmentEDA-30: Area Draining to Runoff Area=9,035 sf 55.12% Impervious Runoff Depth=0.04"
 Flow Length=93' Tc=6.1 min CN=76 Runoff=0.00 cfs 29 cf

SubcatchmentEDA-40: Area Draining to Runoff Area=22,400 sf 36.29% Impervious Runoff Depth=0.00"
 Flow Length=96' Tc=5.0 min CN=67 Runoff=0.00 cfs 0 cf

SubcatchmentEDA-50: Area Draining to Runoff Area=11,465 sf 17.31% Impervious Runoff Depth=0.00"
 Flow Length=73' Tc=5.0 min CN=57 Runoff=0.00 cfs 0 cf

Link DP-1: Offsite West Inflow=0.00 cfs 0 cf
 Primary=0.00 cfs 0 cf

Link DP-2: Grove Street South Inflow=0.46 cfs 1,596 cf
 Primary=0.46 cfs 1,596 cf

Link DP-3: Grove Street North Inflow=0.00 cfs 29 cf
 Primary=0.00 cfs 29 cf

Link DP-4: Brook Street South Inflow=0.00 cfs 0 cf
 Primary=0.00 cfs 0 cf

Link DP-5: Brook Street North Inflow=0.00 cfs 0 cf
 Primary=0.00 cfs 0 cf

Link DP-6: Total Offsite Flow Inflow=0.46 cfs 1,625 cf
 Primary=0.46 cfs 1,625 cf

Total Runoff Area = 122,395 sf Runoff Volume = 1,625 cf Average Runoff Depth = 0.16"
41.80% Pervious = 51,160 sf 58.20% Impervious = 71,235 sf

C-CALC-2202472-Existing Conditions

Prepared by BL Companies

HydroCAD® 10.00-25 s/n 01334 © 2019 HydroCAD Software Solutions LLC

Type III 24-hr 1" Depth Rainfall=1.00"

Printed 3/29/2023

Page 3

Summary for Subcatchment EDA-10: Area Draining Offsite to the West


Runoff = 0.00 cfs @ 0.00 hrs, Volume= 0 cf, Depth= 0.00"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
Type III 24-hr 1" Depth Rainfall=1.00"

	Area (sf)	CN	Description
*	1,575	98	Impervious, HSG A
	10,695	49	50-75% Grass cover, Fair, HSG A
	12,270	55	Weighted Average
	10,695		87.16% Pervious Area
	1,575		12.84% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
4.6	50	0.0300	0.18		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
4.6	50	Total, Increased to minimum Tc = 5.0 min			

Subcatchment EDA-10: Area Draining Offsite to the West



C-CALC-2202472-Existing Conditions

Prepared by BL Companies

HydroCAD® 10.00-25 s/n 01334 © 2019 HydroCAD Software Solutions LLC

Type III 24-hr 1" Depth Rainfall=1.00"

Printed 3/29/2023

Page 4

Summary for Subcatchment EDA-20: Area Draining to Grove Street South

Runoff = 0.46 cfs @ 12.11 hrs, Volume= 1,596 cf, Depth= 0.28"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
Type III 24-hr 1" Depth Rainfall=1.00"

Area (sf)	CN	Description
* 54,565	98	Impervious, HSG A
12,660	49	50-75% Grass cover, Fair, HSG A
67,225	89	Weighted Average
12,660		18.83% Pervious Area
54,565		81.17% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
4.6	50	0.0300	0.18		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.4	25	0.0200	1.09		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
2.1	361	0.0200	2.87		Shallow Concentrated Flow, Paved Kv= 20.3 fps
7.1	436	Total			

Subcatchment EDA-20: Area Draining to Grove Street South

Hydrograph



C-CALC-2202472-Existing Conditions

Type III 24-hr 1" Depth Rainfall=1.00"

Prepared by BL Companies

Printed 3/29/2023

HydroCAD® 10.00-25 s/n 01334 © 2019 HydroCAD Software Solutions LLC

Page 6

Summary for Subcatchment EDA-40: Area Draining to Brook Street South

Runoff = 0.00 cfs @ 24.01 hrs, Volume= 0 cf, Depth= 0.00"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
Type III 24-hr 1" Depth Rainfall=1.00"

Area (sf)	CN	Description
8,130	98	Impervious, HSG A
14,270	49	50-75% Grass cover, Fair, HSG A
22,400	67	Weighted Average
14,270		63.71% Pervious Area
8,130		36.29% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
4.5	70	0.0600	0.26		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.1	26	0.4000	3.65		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
4.6	96	Total, Increased to minimum Tc = 5.0 min			

Subcatchment EDA-40: Area Draining to Brook Street South

Hydrograph



C-CALC-2202472-Existing Conditions

Type III 24-hr 1" Depth Rainfall=1.00"

Prepared by BL Companies

Printed 3/29/2023

HydroCAD® 10.00-25 s/n 01334 © 2019 HydroCAD Software Solutions LLC

Page 7

Summary for Subcatchment EDA-50: Area Draining to Brook Street North


Runoff = 0.00 cfs @ 0.00 hrs, Volume= 0 cf, Depth= 0.00"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
Type III 24-hr 1" Depth Rainfall=1.00"

Area (sf)	CN	Description
* 1,985	98	Impervious, HSG A
9,480	49	50-75% Grass cover, Fair, HSG A
11,465	57	Weighted Average
9,480		82.69% Pervious Area
1,985		17.31% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
4.0	55	0.0500	0.23		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.1	18	0.6000	3.99		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
4.1	73	Total, Increased to minimum Tc = 5.0 min			

Subcatchment EDA-50: Area Draining to Brook Street North




Summary for Link DP-1: Offsite West

Inflow Area = 12,270 sf, 12.84% Impervious, Inflow Depth = 0.00" for 1" Depth event
Inflow = 0.00 cfs @ 0.00 hrs, Volume= 0 cf
Primary = 0.00 cfs @ 0.00 hrs, Volume= 0 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-1: Offsite West




Summary for Link DP-2: Grove Street South

Inflow Area = 67,225 sf, 81.17% Impervious, Inflow Depth = 0.28" for 1" Depth event
Inflow = 0.46 cfs @ 12.11 hrs, Volume= 1,596 cf
Primary = 0.46 cfs @ 12.11 hrs, Volume= 1,596 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-2: Grove Street South




Summary for Link DP-3: Grove Street North

Inflow Area = 9,035 sf, 55.12% Impervious, Inflow Depth = 0.04" for 1" Depth event
Inflow = 0.00 cfs @ 12.49 hrs, Volume= 29 cf
Primary = 0.00 cfs @ 12.49 hrs, Volume= 29 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-3: Grove Street North

Hydrograph




Summary for Link DP-4: Brook Street South

Inflow Area = 22,400 sf, 36.29% Impervious, Inflow Depth = 0.00" for 1" Depth event
Inflow = 0.00 cfs @ 24.01 hrs, Volume= 0 cf
Primary = 0.00 cfs @ 24.01 hrs, Volume= 0 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-4: Brook Street South

Hydrograph




Summary for Link DP-5: Brook Street North

Inflow Area = 11,465 sf, 17.31% Impervious, Inflow Depth = 0.00" for 1" Depth event
Inflow = 0.00 cfs @ 0.00 hrs, Volume= 0 cf
Primary = 0.00 cfs @ 0.00 hrs, Volume= 0 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-5: Brook Street North




Summary for Link DP-6: Total Offsite Flow

Inflow Area = 122,395 sf, 58.20% Impervious, Inflow Depth = 0.16" for 1" Depth event
Inflow = 0.46 cfs @ 12.11 hrs, Volume= 1,625 cf
Primary = 0.46 cfs @ 12.11 hrs, Volume= 1,625 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-6: Total Offsite Flow



Time span=0.00-28.00 hrs, dt=0.01 hrs, 2801 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

SubcatchmentEDA-10: Area Draining Runoff Area=12,270 sf 12.84% Impervious Runoff Depth=0.35"
Flow Length=50' Slope=0.0300 '/ Tc=5.0 min CN=55 Runoff=0.04 cfs 360 cf

SubcatchmentEDA-20: Area Draining to Runoff Area=67,225 sf 81.17% Impervious Runoff Depth=2.38"
Flow Length=436' Tc=7.1 min CN=89 Runoff=4.59 cfs 13,309 cf

SubcatchmentEDA-30: Area Draining to Runoff Area=9,035 sf 55.12% Impervious Runoff Depth=1.38"
Flow Length=93' Tc=6.1 min CN=76 Runoff=0.37 cfs 1,039 cf

SubcatchmentEDA-40: Area Draining to Runoff Area=22,400 sf 36.29% Impervious Runoff Depth=0.86"
Flow Length=96' Tc=5.0 min CN=67 Runoff=0.54 cfs 1,608 cf

SubcatchmentEDA-50: Area Draining to Runoff Area=11,465 sf 17.31% Impervious Runoff Depth=0.42"
Flow Length=73' Tc=5.0 min CN=57 Runoff=0.07 cfs 404 cf

Link DP-1: Offsite West Inflow=0.04 cfs 360 cf
Primary=0.04 cfs 360 cf

Link DP-2: Grove Street South Inflow=4.59 cfs 13,309 cf
Primary=4.59 cfs 13,309 cf

Link DP-3: Grove Street North Inflow=0.37 cfs 1,039 cf
Primary=0.37 cfs 1,039 cf

Link DP-4: Brook Street South Inflow=0.54 cfs 1,608 cf
Primary=0.54 cfs 1,608 cf

Link DP-5: Brook Street North Inflow=0.07 cfs 404 cf
Primary=0.07 cfs 404 cf

Link DP-6: Total Offsite Flow Inflow=5.59 cfs 16,720 cf
Primary=5.59 cfs 16,720 cf

Total Runoff Area = 122,395 sf Runoff Volume = 16,720 cf Average Runoff Depth = 1.64"
41.80% Pervious = 51,160 sf 58.20% Impervious = 71,235 sf

Summary for Subcatchment EDA-10: Area Draining Offsite to the West


Runoff = 0.04 cfs @ 12.06 hrs, Volume= 360 cf, Depth= 0.35"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 2-yr Rainfall=3.52"

Area (sf)	CN	Description
* 1,575	98	Impervious, HSG A
10,695	49	50-75% Grass cover, Fair, HSG A
12,270	55	Weighted Average
10,695		87.16% Pervious Area
1,575		12.84% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
4.6	50	0.0300	0.18		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
4.6	50	Total, Increased to minimum Tc = 5.0 min			

Subcatchment EDA-10: Area Draining Offsite to the West



Summary for Subcatchment EDA-20: Area Draining to Grove Street South

Runoff = 4.59 cfs @ 12.05 hrs, Volume= 13,309 cf, Depth= 2.38"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 2-yr Rainfall=3.52"

Area (sf)	CN	Description
* 54,565	98	Impervious, HSG A
12,660	49	50-75% Grass cover, Fair, HSG A
67,225	89	Weighted Average
12,660		18.83% Pervious Area
54,565		81.17% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
4.6	50	0.0300	0.18		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.4	25	0.0200	1.09		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
2.1	361	0.0200	2.87		Shallow Concentrated Flow, Paved Kv= 20.3 fps
7.1	436	Total			

Subcatchment EDA-20: Area Draining to Grove Street South

Hydrograph



Summary for Subcatchment EDA-30: Area Draining to Grove Street North


Runoff = 0.37 cfs @ 12.04 hrs, Volume= 1,039 cf, Depth= 1.38"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 2-yr Rainfall=3.52"

Area (sf)	CN	Description
* 4,980	98	Impervious, HSG A
4,055	49	50-75% Grass cover, Fair, HSG A
9,035	76	Weighted Average
4,055		44.88% Pervious Area
4,980		55.12% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.7	66	0.0300	0.19		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.4	27	0.0200	1.11		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
6.1	93	Total			

Subcatchment EDA-30: Area Draining to Grove Street North



Summary for Subcatchment EDA-40: Area Draining to Brook Street South


Runoff = 0.54 cfs @ 12.03 hrs, Volume= 1,608 cf, Depth= 0.86"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 2-yr Rainfall=3.52"

Area (sf)	CN	Description
* 8,130	98	Impervious, HSG A
14,270	49	50-75% Grass cover, Fair, HSG A
22,400	67	Weighted Average
14,270		63.71% Pervious Area
8,130		36.29% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
4.5	70	0.0600	0.26		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.1	26	0.4000	3.65		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
4.6	96	Total, Increased to minimum Tc = 5.0 min			

Subcatchment EDA-40: Area Draining to Brook Street South



Summary for Subcatchment EDA-50: Area Draining to Brook Street North


Runoff = 0.07 cfs @ 12.05 hrs, Volume= 404 cf, Depth= 0.42"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 2-yr Rainfall=3.52"

Area (sf)	CN	Description
* 1,985	98	Impervious, HSG A
9,480	49	50-75% Grass cover, Fair, HSG A
11,465	57	Weighted Average
9,480		82.69% Pervious Area
1,985		17.31% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
4.0	55	0.0500	0.23		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.1	18	0.6000	3.99		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
4.1	73	Total, Increased to minimum Tc = 5.0 min			

Subcatchment EDA-50: Area Draining to Brook Street North




Summary for Link DP-1: Offsite West

Inflow Area = 12,270 sf, 12.84% Impervious, Inflow Depth = 0.35" for 2-yr event
 Inflow = 0.04 cfs @ 12.06 hrs, Volume= 360 cf
 Primary = 0.04 cfs @ 12.06 hrs, Volume= 360 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-1: Offsite West

Hydrograph




Summary for Link DP-2: Grove Street South

Inflow Area = 67,225 sf, 81.17% Impervious, Inflow Depth = 2.38" for 2-yr event
Inflow = 4.59 cfs @ 12.05 hrs, Volume= 13,309 cf
Primary = 4.59 cfs @ 12.05 hrs, Volume= 13,309 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-2: Grove Street South




Summary for Link DP-3: Grove Street North

Inflow Area = 9,035 sf, 55.12% Impervious, Inflow Depth = 1.38" for 2-yr event
Inflow = 0.37 cfs @ 12.04 hrs, Volume= 1,039 cf
Primary = 0.37 cfs @ 12.04 hrs, Volume= 1,039 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-3: Grove Street North




Summary for Link DP-4: Brook Street South

Inflow Area = 22,400 sf, 36.29% Impervious, Inflow Depth = 0.86" for 2-yr event
Inflow = 0.54 cfs @ 12.03 hrs, Volume= 1,608 cf
Primary = 0.54 cfs @ 12.03 hrs, Volume= 1,608 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-4: Brook Street South




Summary for Link DP-5: Brook Street North

Inflow Area = 11,465 sf, 17.31% Impervious, Inflow Depth = 0.42" for 2-yr event
Inflow = 0.07 cfs @ 12.05 hrs, Volume= 404 cf
Primary = 0.07 cfs @ 12.05 hrs, Volume= 404 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-5: Brook Street North




Summary for Link DP-6: Total Offsite Flow

Inflow Area = 122,395 sf, 58.20% Impervious, Inflow Depth = 1.64" for 2-yr event
Inflow = 5.59 cfs @ 12.05 hrs, Volume= 16,720 cf
Primary = 5.59 cfs @ 12.05 hrs, Volume= 16,720 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-6: Total Offsite Flow



Time span=0.00-28.00 hrs, dt=0.01 hrs, 2801 points
 Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
 Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

SubcatchmentEDA-10: Area Draining Runoff Area=12,270 sf 12.84% Impervious Runoff Depth=0.84"
 Flow Length=50' Slope=0.0300 '/ Tc=5.0 min CN=55 Runoff=0.23 cfs 863 cf

SubcatchmentEDA-20: Area Draining to Runoff Area=67,225 sf 81.17% Impervious Runoff Depth=3.50"
 Flow Length=436' Tc=7.1 min CN=89 Runoff=6.29 cfs 19,632 cf

SubcatchmentEDA-30: Area Draining to Runoff Area=9,035 sf 55.12% Impervious Runoff Depth=2.31"
 Flow Length=93' Tc=6.1 min CN=76 Runoff=0.60 cfs 1,737 cf

SubcatchmentEDA-40: Area Draining to Runoff Area=22,400 sf 36.29% Impervious Runoff Depth=1.61"
 Flow Length=96' Tc=5.0 min CN=67 Runoff=1.05 cfs 3,007 cf

SubcatchmentEDA-50: Area Draining to Runoff Area=11,465 sf 17.31% Impervious Runoff Depth=0.96"
 Flow Length=73' Tc=5.0 min CN=57 Runoff=0.26 cfs 916 cf

Link DP-1: Offsite West Inflow=0.23 cfs 863 cf
 Primary=0.23 cfs 863 cf

Link DP-2: Grove Street South Inflow=6.29 cfs 19,632 cf
 Primary=6.29 cfs 19,632 cf

Link DP-3: Grove Street North Inflow=0.60 cfs 1,737 cf
 Primary=0.60 cfs 1,737 cf

Link DP-4: Brook Street South Inflow=1.05 cfs 3,007 cf
 Primary=1.05 cfs 3,007 cf

Link DP-5: Brook Street North Inflow=0.26 cfs 916 cf
 Primary=0.26 cfs 916 cf

Link DP-6: Total Offsite Flow Inflow=8.37 cfs 26,155 cf
 Primary=8.37 cfs 26,155 cf

Total Runoff Area = 122,395 sf Runoff Volume = 26,155 cf Average Runoff Depth = 2.56"
41.80% Pervious = 51,160 sf 58.20% Impervious = 71,235 sf

Summary for Subcatchment EDA-10: Area Draining Offsite to the West

Runoff = 0.23 cfs @ 12.04 hrs, Volume= 863 cf, Depth= 0.84"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 5-yr Rainfall=4.72"

Area (sf)	CN	Description
* 1,575	98	Impervious, HSG A
10,695	49	50-75% Grass cover, Fair, HSG A
12,270	55	Weighted Average
10,695		87.16% Pervious Area
1,575		12.84% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
4.6	50	0.0300	0.18		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
4.6	50	Total, Increased to minimum Tc = 5.0 min			

Subcatchment EDA-10: Area Draining Offsite to the West

Hydrograph



Summary for Subcatchment EDA-20: Area Draining to Grove Street South


Runoff = 6.29 cfs @ 12.05 hrs, Volume= 19,632 cf, Depth= 3.50"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 5-yr Rainfall=4.72"

Area (sf)	CN	Description
* 54,565	98	Impervious, HSG A
12,660	49	50-75% Grass cover, Fair, HSG A
67,225	89	Weighted Average
12,660		18.83% Pervious Area
54,565		81.17% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
4.6	50	0.0300	0.18		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.4	25	0.0200	1.09		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
2.1	361	0.0200	2.87		Shallow Concentrated Flow, Paved Kv= 20.3 fps
7.1	436	Total			

Subcatchment EDA-20: Area Draining to Grove Street South



Summary for Subcatchment EDA-30: Area Draining to Grove Street North


Runoff = 0.60 cfs @ 12.04 hrs, Volume= 1,737 cf, Depth= 2.31"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 5-yr Rainfall=4.72"

Area (sf)	CN	Description
* 4,980	98	Impervious, HSG A
4,055	49	50-75% Grass cover, Fair, HSG A
9,035	76	Weighted Average
4,055		44.88% Pervious Area
4,980		55.12% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.7	66	0.0300	0.19		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.4	27	0.0200	1.11		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
6.1	93	Total			

Subcatchment EDA-30: Area Draining to Grove Street North



Summary for Subcatchment EDA-40: Area Draining to Brook Street South


Runoff = 1.05 cfs @ 12.03 hrs, Volume= 3,007 cf, Depth= 1.61"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 5-yr Rainfall=4.72"

Area (sf)	CN	Description
8,130	98	Impervious, HSG A
14,270	49	50-75% Grass cover, Fair, HSG A
22,400	67	Weighted Average
14,270		63.71% Pervious Area
8,130		36.29% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
4.5	70	0.0600	0.26		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.1	26	0.4000	3.65		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
4.6	96	Total, Increased to minimum Tc = 5.0 min			

Subcatchment EDA-40: Area Draining to Brook Street South



Summary for Subcatchment EDA-50: Area Draining to Brook Street North


Runoff = 0.26 cfs @ 12.04 hrs, Volume= 916 cf, Depth= 0.96"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 5-yr Rainfall=4.72"

Area (sf)	CN	Description
* 1,985	98	Impervious, HSG A
9,480	49	50-75% Grass cover, Fair, HSG A
11,465	57	Weighted Average
9,480		82.69% Pervious Area
1,985		17.31% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
4.0	55	0.0500	0.23		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.1	18	0.6000	3.99		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
4.1	73	Total, Increased to minimum Tc = 5.0 min			

Subcatchment EDA-50: Area Draining to Brook Street North




Summary for Link DP-1: Offsite West

Inflow Area = 12,270 sf, 12.84% Impervious, Inflow Depth = 0.84" for 5-yr event
Inflow = 0.23 cfs @ 12.04 hrs, Volume= 863 cf
Primary = 0.23 cfs @ 12.04 hrs, Volume= 863 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-1: Offsite West




Summary for Link DP-2: Grove Street South

Inflow Area = 67,225 sf, 81.17% Impervious, Inflow Depth = 3.50" for 5-yr event
Inflow = 6.29 cfs @ 12.05 hrs, Volume= 19,632 cf
Primary = 6.29 cfs @ 12.05 hrs, Volume= 19,632 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-2: Grove Street South




Summary for Link DP-3: Grove Street North

Inflow Area = 9,035 sf, 55.12% Impervious, Inflow Depth = 2.31" for 5-yr event
Inflow = 0.60 cfs @ 12.04 hrs, Volume= 1,737 cf
Primary = 0.60 cfs @ 12.04 hrs, Volume= 1,737 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-3: Grove Street North




Summary for Link DP-4: Brook Street South

Inflow Area = 22,400 sf, 36.29% Impervious, Inflow Depth = 1.61" for 5-yr event
Inflow = 1.05 cfs @ 12.03 hrs, Volume= 3,007 cf
Primary = 1.05 cfs @ 12.03 hrs, Volume= 3,007 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-4: Brook Street South




Summary for Link DP-5: Brook Street North

Inflow Area = 11,465 sf, 17.31% Impervious, Inflow Depth = 0.96" for 5-yr event
Inflow = 0.26 cfs @ 12.04 hrs, Volume= 916 cf
Primary = 0.26 cfs @ 12.04 hrs, Volume= 916 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-5: Brook Street North




Summary for Link DP-6: Total Offsite Flow

Inflow Area = 122,395 sf, 58.20% Impervious, Inflow Depth = 2.56" for 5-yr event
Inflow = 8.37 cfs @ 12.04 hrs, Volume= 26,155 cf
Primary = 8.37 cfs @ 12.04 hrs, Volume= 26,155 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-6: Total Offsite Flow



Time span=0.00-28.00 hrs, dt=0.01 hrs, 2801 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

SubcatchmentEDA-10: Area Draining Runoff Area=12,270 sf 12.84% Impervious Runoff Depth=1.35"
Flow Length=50' Slope=0.0300 '/' Tc=5.0 min CN=55 Runoff=0.42 cfs 1,385 cf

SubcatchmentEDA-20: Area Draining to Runoff Area=67,225 sf 81.17% Impervious Runoff Depth=4.45"
Flow Length=436' Tc=7.1 min CN=89 Runoff=7.68 cfs 24,957 cf

SubcatchmentEDA-30: Area Draining to Runoff Area=9,035 sf 55.12% Impervious Runoff Depth=3.13"
Flow Length=93' Tc=6.1 min CN=76 Runoff=0.79 cfs 2,358 cf

SubcatchmentEDA-40: Area Draining to Runoff Area=22,400 sf 36.29% Impervious Runoff Depth=2.31"
Flow Length=96' Tc=5.0 min CN=67 Runoff=1.51 cfs 4,318 cf

SubcatchmentEDA-50: Area Draining to Runoff Area=11,465 sf 17.31% Impervious Runoff Depth=1.50"
Flow Length=73' Tc=5.0 min CN=57 Runoff=0.45 cfs 1,436 cf

Link DP-1: Offsite West Inflow=0.42 cfs 1,385 cf
Primary=0.42 cfs 1,385 cf

Link DP-2: Grove Street South Inflow=7.68 cfs 24,957 cf
Primary=7.68 cfs 24,957 cf

Link DP-3: Grove Street North Inflow=0.79 cfs 2,358 cf
Primary=0.79 cfs 2,358 cf

Link DP-4: Brook Street South Inflow=1.51 cfs 4,318 cf
Primary=1.51 cfs 4,318 cf

Link DP-5: Brook Street North Inflow=0.45 cfs 1,436 cf
Primary=0.45 cfs 1,436 cf

Link DP-6: Total Offsite Flow Inflow=10.75 cfs 34,453 cf
Primary=10.75 cfs 34,453 cf

Total Runoff Area = 122,395 sf Runoff Volume = 34,453 cf Average Runoff Depth = 3.38"
41.80% Pervious = 51,160 sf 58.20% Impervious = 71,235 sf

Summary for Subcatchment EDA-10: Area Draining Offsite to the West

Runoff = 0.42 cfs @ 12.03 hrs, Volume= 1,385 cf, Depth= 1.35"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 10-yr Rainfall=5.71"

	Area (sf)	CN	Description
*	1,575	98	Impervious, HSG A
	10,695	49	50-75% Grass cover, Fair, HSG A
	12,270	55	Weighted Average
	10,695		87.16% Pervious Area
	1,575		12.84% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
4.6	50	0.0300	0.18		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
4.6	50	Total, Increased to minimum Tc = 5.0 min			

Subcatchment EDA-10: Area Draining Offsite to the West

Hydrograph



Summary for Subcatchment EDA-20: Area Draining to Grove Street South

Runoff = 7.68 cfs @ 12.05 hrs, Volume= 24,957 cf, Depth= 4.45"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 10-yr Rainfall=5.71"

Area (sf)	CN	Description
* 54,565	98	Impervious, HSG A
12,660	49	50-75% Grass cover, Fair, HSG A
67,225	89	Weighted Average
12,660		18.83% Pervious Area
54,565		81.17% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
4.6	50	0.0300	0.18		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.4	25	0.0200	1.09		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
2.1	361	0.0200	2.87		Shallow Concentrated Flow, Paved Kv= 20.3 fps
7.1	436	Total			

Subcatchment EDA-20: Area Draining to Grove Street South

Hydrograph



Summary for Subcatchment EDA-30: Area Draining to Grove Street North


Runoff = 0.79 cfs @ 12.04 hrs, Volume= 2,358 cf, Depth= 3.13"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 10-yr Rainfall=5.71"

Area (sf)	CN	Description
* 4,980	98	Impervious, HSG A
4,055	49	50-75% Grass cover, Fair, HSG A
9,035	76	Weighted Average
4,055		44.88% Pervious Area
4,980		55.12% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.7	66	0.0300	0.19		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.4	27	0.0200	1.11		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
6.1	93	Total			

Subcatchment EDA-30: Area Draining to Grove Street North



Summary for Subcatchment EDA-40: Area Draining to Brook Street South


Runoff = 1.51 cfs @ 12.03 hrs, Volume= 4,318 cf, Depth= 2.31"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 10-yr Rainfall=5.71"

Area (sf)	CN	Description
8,130	98	Impervious, HSG A
14,270	49	50-75% Grass cover, Fair, HSG A
22,400	67	Weighted Average
14,270		63.71% Pervious Area
8,130		36.29% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
4.5	70	0.0600	0.26		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.1	26	0.4000	3.65		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
4.6	96	Total, Increased to minimum Tc = 5.0 min			

Subcatchment EDA-40: Area Draining to Brook Street South



Summary for Subcatchment EDA-50: Area Draining to Brook Street North


Runoff = 0.45 cfs @ 12.03 hrs, Volume= 1,436 cf, Depth= 1.50"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 10-yr Rainfall=5.71"

Area (sf)	CN	Description
* 1,985	98	Impervious, HSG A
9,480	49	50-75% Grass cover, Fair, HSG A
11,465	57	Weighted Average
9,480		82.69% Pervious Area
1,985		17.31% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
4.0	55	0.0500	0.23		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.1	18	0.6000	3.99		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
4.1	73	Total, Increased to minimum Tc = 5.0 min			

Subcatchment EDA-50: Area Draining to Brook Street North




Summary for Link DP-1: Offsite West

Inflow Area = 12,270 sf, 12.84% Impervious, Inflow Depth = 1.35" for 10-yr event
Inflow = 0.42 cfs @ 12.03 hrs, Volume= 1,385 cf
Primary = 0.42 cfs @ 12.03 hrs, Volume= 1,385 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-1: Offsite West




Summary for Link DP-2: Grove Street South

Inflow Area = 67,225 sf, 81.17% Impervious, Inflow Depth = 4.45" for 10-yr event
Inflow = 7.68 cfs @ 12.05 hrs, Volume= 24,957 cf
Primary = 7.68 cfs @ 12.05 hrs, Volume= 24,957 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-2: Grove Street South




Summary for Link DP-3: Grove Street North

Inflow Area = 9,035 sf, 55.12% Impervious, Inflow Depth = 3.13" for 10-yr event
 Inflow = 0.79 cfs @ 12.04 hrs, Volume= 2,358 cf
 Primary = 0.79 cfs @ 12.04 hrs, Volume= 2,358 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-3: Grove Street North




Summary for Link DP-4: Brook Street South

Inflow Area = 22,400 sf, 36.29% Impervious, Inflow Depth = 2.31" for 10-yr event
Inflow = 1.51 cfs @ 12.03 hrs, Volume= 4,318 cf
Primary = 1.51 cfs @ 12.03 hrs, Volume= 4,318 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-4: Brook Street South




Summary for Link DP-5: Brook Street North

Inflow Area = 11,465 sf, 17.31% Impervious, Inflow Depth = 1.50" for 10-yr event
 Inflow = 0.45 cfs @ 12.03 hrs, Volume= 1,436 cf
 Primary = 0.45 cfs @ 12.03 hrs, Volume= 1,436 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-5: Brook Street North




Summary for Link DP-6: Total Offsite Flow

Inflow Area = 122,395 sf, 58.20% Impervious, Inflow Depth = 3.38" for 10-yr event
Inflow = 10.75 cfs @ 12.04 hrs, Volume= 34,453 cf
Primary = 10.75 cfs @ 12.04 hrs, Volume= 34,453 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-6: Total Offsite Flow



Time span=0.00-28.00 hrs, dt=0.01 hrs, 2801 points
 Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
 Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

Subcatchment EDA-10: Area Draining	Runoff Area=12,270 sf 12.84% Impervious Runoff Depth=2.17" Flow Length=50' Slope=0.0300 '/' Tc=5.0 min CN=55 Runoff=0.71 cfs 2,217 cf
Subcatchment EDA-20: Area Draining to	Runoff Area=67,225 sf 81.17% Impervious Runoff Depth=5.78" Flow Length=436' Tc=7.1 min CN=89 Runoff=9.52 cfs 32,360 cf
Subcatchment EDA-30: Area Draining to	Runoff Area=9,035 sf 55.12% Impervious Runoff Depth=4.32" Flow Length=93' Tc=6.1 min CN=76 Runoff=1.06 cfs 3,252 cf
Subcatchment EDA-40: Area Draining to	Runoff Area=22,400 sf 36.29% Impervious Runoff Depth=3.36" Flow Length=96' Tc=5.0 min CN=67 Runoff=2.16 cfs 6,277 cf
Subcatchment EDA-50: Area Draining to	Runoff Area=11,465 sf 17.31% Impervious Runoff Depth=2.36" Flow Length=73' Tc=5.0 min CN=57 Runoff=0.74 cfs 2,255 cf
Link DP-1: Offsite West	Inflow=0.71 cfs 2,217 cf Primary=0.71 cfs 2,217 cf
Link DP-2: Grove Street South	Inflow=9.52 cfs 32,360 cf Primary=9.52 cfs 32,360 cf
Link DP-3: Grove Street North	Inflow=1.06 cfs 3,252 cf Primary=1.06 cfs 3,252 cf
Link DP-4: Brook Street South	Inflow=2.16 cfs 6,277 cf Primary=2.16 cfs 6,277 cf
Link DP-5: Brook Street North	Inflow=0.74 cfs 2,255 cf Primary=0.74 cfs 2,255 cf
Link DP-6: Total Offsite Flow	Inflow=14.04 cfs 46,362 cf Primary=14.04 cfs 46,362 cf

Total Runoff Area = 122,395 sf Runoff Volume = 46,362 cf Average Runoff Depth = 4.55"
41.80% Pervious = 51,160 sf 58.20% Impervious = 71,235 sf

Summary for Subcatchment EDA-10: Area Draining Offsite to the West


Runoff = 0.71 cfs @ 12.03 hrs, Volume= 2,217 cf, Depth= 2.17"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 25-yr Rainfall=7.07"

Area (sf)	CN	Description
* 1,575	98	Impervious, HSG A
10,695	49	50-75% Grass cover, Fair, HSG A
12,270	55	Weighted Average
10,695		87.16% Pervious Area
1,575		12.84% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
4.6	50	0.0300	0.18		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
4.6	50	Total, Increased to minimum Tc = 5.0 min			

Subcatchment EDA-10: Area Draining Offsite to the West



Summary for Subcatchment EDA-20: Area Draining to Grove Street South

Runoff = 9.52 cfs @ 12.05 hrs, Volume= 32,360 cf, Depth= 5.78"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 25-yr Rainfall=7.07"

Area (sf)	CN	Description
* 54,565	98	Impervious, HSG A
12,660	49	50-75% Grass cover, Fair, HSG A
67,225	89	Weighted Average
12,660		18.83% Pervious Area
54,565		81.17% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
4.6	50	0.0300	0.18		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.4	25	0.0200	1.09		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
2.1	361	0.0200	2.87		Shallow Concentrated Flow, Paved Kv= 20.3 fps
7.1	436	Total			

Subcatchment EDA-20: Area Draining to Grove Street South

Hydrograph



Summary for Subcatchment EDA-30: Area Draining to Grove Street North


Runoff = 1.06 cfs @ 12.04 hrs, Volume= 3,252 cf, Depth= 4.32"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 25-yr Rainfall=7.07"

Area (sf)	CN	Description
* 4,980	98	Impervious, HSG A
4,055	49	50-75% Grass cover, Fair, HSG A
9,035	76	Weighted Average
4,055		44.88% Pervious Area
4,980		55.12% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.7	66	0.0300	0.19		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.4	27	0.0200	1.11		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
6.1	93	Total			

Subcatchment EDA-30: Area Draining to Grove Street North



Summary for Subcatchment EDA-40: Area Draining to Brook Street South


Runoff = 2.16 cfs @ 12.03 hrs, Volume= 6,277 cf, Depth= 3.36"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 25-yr Rainfall=7.07"

Area (sf)	CN	Description
8,130	98	Impervious, HSG A
14,270	49	50-75% Grass cover, Fair, HSG A
22,400	67	Weighted Average
14,270		63.71% Pervious Area
8,130		36.29% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
4.5	70	0.0600	0.26		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.1	26	0.4000	3.65		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
4.6	96	Total, Increased to minimum Tc = 5.0 min			

Subcatchment EDA-40: Area Draining to Brook Street South



Summary for Subcatchment EDA-50: Area Draining to Brook Street North


Runoff = 0.74 cfs @ 12.03 hrs, Volume= 2,255 cf, Depth= 2.36"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 25-yr Rainfall=7.07"

Area (sf)	CN	Description
* 1,985	98	Impervious, HSG A
9,480	49	50-75% Grass cover, Fair, HSG A
11,465	57	Weighted Average
9,480		82.69% Pervious Area
1,985		17.31% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
4.0	55	0.0500	0.23		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.1	18	0.6000	3.99		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
4.1	73	Total, Increased to minimum Tc = 5.0 min			

Subcatchment EDA-50: Area Draining to Brook Street North




Summary for Link DP-1: Offsite West

Inflow Area = 12,270 sf, 12.84% Impervious, Inflow Depth = 2.17" for 25-yr event
Inflow = 0.71 cfs @ 12.03 hrs, Volume= 2,217 cf
Primary = 0.71 cfs @ 12.03 hrs, Volume= 2,217 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-1: Offsite West




Summary for Link DP-2: Grove Street South

Inflow Area = 67,225 sf, 81.17% Impervious, Inflow Depth = 5.78" for 25-yr event
Inflow = 9.52 cfs @ 12.05 hrs, Volume= 32,360 cf
Primary = 9.52 cfs @ 12.05 hrs, Volume= 32,360 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-2: Grove Street South




Summary for Link DP-3: Grove Street North

Inflow Area = 9,035 sf, 55.12% Impervious, Inflow Depth = 4.32" for 25-yr event
Inflow = 1.06 cfs @ 12.04 hrs, Volume= 3,252 cf
Primary = 1.06 cfs @ 12.04 hrs, Volume= 3,252 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-3: Grove Street North




Summary for Link DP-4: Brook Street South

Inflow Area = 22,400 sf, 36.29% Impervious, Inflow Depth = 3.36" for 25-yr event
Inflow = 2.16 cfs @ 12.03 hrs, Volume= 6,277 cf
Primary = 2.16 cfs @ 12.03 hrs, Volume= 6,277 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-4: Brook Street South




Summary for Link DP-5: Brook Street North

Inflow Area = 11,465 sf, 17.31% Impervious, Inflow Depth = 2.36" for 25-yr event
 Inflow = 0.74 cfs @ 12.03 hrs, Volume= 2,255 cf
 Primary = 0.74 cfs @ 12.03 hrs, Volume= 2,255 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-5: Brook Street North

Hydrograph




Summary for Link DP-6: Total Offsite Flow

Inflow Area = 122,395 sf, 58.20% Impervious, Inflow Depth = 4.55" for 25-yr event
Inflow = 14.04 cfs @ 12.04 hrs, Volume= 46,362 cf
Primary = 14.04 cfs @ 12.04 hrs, Volume= 46,362 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-6: Total Offsite Flow



Time span=0.00-28.00 hrs, dt=0.01 hrs, 2801 points
 Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
 Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

SubcatchmentEDA-10: Area Draining Runoff Area=12,270 sf 12.84% Impervious Runoff Depth=2.83"
 Flow Length=50' Slope=0.0300 '/' Tc=5.0 min CN=55 Runoff=0.95 cfs 2,896 cf

SubcatchmentEDA-20: Area Draining to Runoff Area=67,225 sf 81.17% Impervious Runoff Depth=6.76"
 Flow Length=436' Tc=7.1 min CN=89 Runoff=10.91 cfs 37,845 cf

SubcatchmentEDA-30: Area Draining to Runoff Area=9,035 sf 55.12% Impervious Runoff Depth=5.22"
 Flow Length=93' Tc=6.1 min CN=76 Runoff=1.26 cfs 3,931 cf

SubcatchmentEDA-40: Area Draining to Runoff Area=22,400 sf 36.29% Impervious Runoff Depth=4.18"
 Flow Length=96' Tc=5.0 min CN=67 Runoff=2.67 cfs 7,802 cf

SubcatchmentEDA-50: Area Draining to Runoff Area=11,465 sf 17.31% Impervious Runoff Depth=3.05"
 Flow Length=73' Tc=5.0 min CN=57 Runoff=0.96 cfs 2,916 cf

Link DP-1: Offsite West Inflow=0.95 cfs 2,896 cf
 Primary=0.95 cfs 2,896 cf

Link DP-2: Grove Street South Inflow=10.91 cfs 37,845 cf
 Primary=10.91 cfs 37,845 cf

Link DP-3: Grove Street North Inflow=1.26 cfs 3,931 cf
 Primary=1.26 cfs 3,931 cf

Link DP-4: Brook Street South Inflow=2.67 cfs 7,802 cf
 Primary=2.67 cfs 7,802 cf

Link DP-5: Brook Street North Inflow=0.96 cfs 2,916 cf
 Primary=0.96 cfs 2,916 cf

Link DP-6: Total Offsite Flow Inflow=16.57 cfs 55,390 cf
 Primary=16.57 cfs 55,390 cf

Total Runoff Area = 122,395 sf Runoff Volume = 55,390 cf Average Runoff Depth = 5.43"
41.80% Pervious = 51,160 sf 58.20% Impervious = 71,235 sf

Summary for Subcatchment EDA-10: Area Draining Offsite to the West


Runoff = 0.95 cfs @ 12.03 hrs, Volume= 2,896 cf, Depth= 2.83"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 50-yr Rainfall=8.07"

Area (sf)	CN	Description
* 1,575	98	Impervious, HSG A
10,695	49	50-75% Grass cover, Fair, HSG A
12,270	55	Weighted Average
10,695		87.16% Pervious Area
1,575		12.84% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
4.6	50	0.0300	0.18		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
4.6	50	Total, Increased to minimum Tc = 5.0 min			

Subcatchment EDA-10: Area Draining Offsite to the West



Summary for Subcatchment EDA-20: Area Draining to Grove Street South

Runoff = 10.91 cfs @ 12.05 hrs, Volume= 37,845 cf, Depth= 6.76"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 50-yr Rainfall=8.07"

Area (sf)	CN	Description
* 54,565	98	Impervious, HSG A
12,660	49	50-75% Grass cover, Fair, HSG A
67,225	89	Weighted Average
12,660		18.83% Pervious Area
54,565		81.17% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
4.6	50	0.0300	0.18		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.4	25	0.0200	1.09		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
2.1	361	0.0200	2.87		Shallow Concentrated Flow, Paved Kv= 20.3 fps
7.1	436	Total			

Subcatchment EDA-20: Area Draining to Grove Street South

Hydrograph



Summary for Subcatchment EDA-30: Area Draining to Grove Street North


Runoff = 1.26 cfs @ 12.04 hrs, Volume= 3,931 cf, Depth= 5.22"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 50-yr Rainfall=8.07"

Area (sf)	CN	Description
4,980	98	Impervious, HSG A
4,055	49	50-75% Grass cover, Fair, HSG A
9,035	76	Weighted Average
4,055		44.88% Pervious Area
4,980		55.12% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.7	66	0.0300	0.19		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.4	27	0.0200	1.11		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
6.1	93	Total			

Subcatchment EDA-30: Area Draining to Grove Street North



Summary for Subcatchment EDA-40: Area Draining to Brook Street South


Runoff = 2.67 cfs @ 12.03 hrs, Volume= 7,802 cf, Depth= 4.18"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 50-yr Rainfall=8.07"

Area (sf)	CN	Description
8,130	98	Impervious, HSG A
14,270	49	50-75% Grass cover, Fair, HSG A
22,400	67	Weighted Average
14,270		63.71% Pervious Area
8,130		36.29% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
4.5	70	0.0600	0.26		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.1	26	0.4000	3.65		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
4.6	96	Total, Increased to minimum Tc = 5.0 min			

Subcatchment EDA-40: Area Draining to Brook Street South



Summary for Subcatchment EDA-50: Area Draining to Brook Street North


Runoff = 0.96 cfs @ 12.03 hrs, Volume= 2,916 cf, Depth= 3.05"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 50-yr Rainfall=8.07"

Area (sf)	CN	Description
1,985	98	Impervious, HSG A
9,480	49	50-75% Grass cover, Fair, HSG A
11,465	57	Weighted Average
9,480		82.69% Pervious Area
1,985		17.31% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
4.0	55	0.0500	0.23		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.1	18	0.6000	3.99		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
4.1	73	Total, Increased to minimum Tc = 5.0 min			

Subcatchment EDA-50: Area Draining to Brook Street North




Summary for Link DP-1: Offsite West

Inflow Area = 12,270 sf, 12.84% Impervious, Inflow Depth = 2.83" for 50-yr event
Inflow = 0.95 cfs @ 12.03 hrs, Volume= 2,896 cf
Primary = 0.95 cfs @ 12.03 hrs, Volume= 2,896 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-1: Offsite West




Summary for Link DP-2: Grove Street South

Inflow Area = 67,225 sf, 81.17% Impervious, Inflow Depth = 6.76" for 50-yr event
Inflow = 10.91 cfs @ 12.05 hrs, Volume= 37,845 cf
Primary = 10.91 cfs @ 12.05 hrs, Volume= 37,845 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-2: Grove Street South

Hydrograph




Summary for Link DP-3: Grove Street North

Inflow Area = 9,035 sf, 55.12% Impervious, Inflow Depth = 5.22" for 50-yr event
Inflow = 1.26 cfs @ 12.04 hrs, Volume= 3,931 cf
Primary = 1.26 cfs @ 12.04 hrs, Volume= 3,931 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-3: Grove Street North




Summary for Link DP-4: Brook Street South

Inflow Area = 22,400 sf, 36.29% Impervious, Inflow Depth = 4.18" for 50-yr event
Inflow = 2.67 cfs @ 12.03 hrs, Volume= 7,802 cf
Primary = 2.67 cfs @ 12.03 hrs, Volume= 7,802 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-4: Brook Street South




Summary for Link DP-5: Brook Street North

Inflow Area = 11,465 sf, 17.31% Impervious, Inflow Depth = 3.05" for 50-yr event
Inflow = 0.96 cfs @ 12.03 hrs, Volume= 2,916 cf
Primary = 0.96 cfs @ 12.03 hrs, Volume= 2,916 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-5: Brook Street North




Summary for Link DP-6: Total Offsite Flow

Inflow Area = 122,395 sf, 58.20% Impervious, Inflow Depth = 5.43" for 50-yr event
 Inflow = 16.57 cfs @ 12.04 hrs, Volume= 55,390 cf
 Primary = 16.57 cfs @ 12.04 hrs, Volume= 55,390 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-6: Total Offsite Flow



Time span=0.00-28.00 hrs, dt=0.01 hrs, 2801 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

SubcatchmentEDA-10: Area Draining Runoff Area=12,270 sf 12.84% Impervious Runoff Depth=3.62"
Flow Length=50' Slope=0.0300 '/' Tc=5.0 min CN=55 Runoff=1.21 cfs 3,700 cf

SubcatchmentEDA-20: Area Draining to Runoff Area=67,225 sf 81.17% Impervious Runoff Depth=7.85"
Flow Length=436' Tc=7.1 min CN=89 Runoff=12.34 cfs 43,960 cf

SubcatchmentEDA-30: Area Draining to Runoff Area=9,035 sf 55.12% Impervious Runoff Depth=6.24"
Flow Length=93' Tc=6.1 min CN=76 Runoff=1.47 cfs 4,700 cf

SubcatchmentEDA-40: Area Draining to Runoff Area=22,400 sf 36.29% Impervious Runoff Depth=5.12"
Flow Length=96' Tc=5.0 min CN=67 Runoff=3.21 cfs 9,555 cf

SubcatchmentEDA-50: Area Draining to Runoff Area=11,465 sf 17.31% Impervious Runoff Depth=3.87"
Flow Length=73' Tc=5.0 min CN=57 Runoff=1.22 cfs 3,695 cf

Link DP-1: Offsite West Inflow=1.21 cfs 3,700 cf
Primary=1.21 cfs 3,700 cf

Link DP-2: Grove Street South Inflow=12.34 cfs 43,960 cf
Primary=12.34 cfs 43,960 cf

Link DP-3: Grove Street North Inflow=1.47 cfs 4,700 cf
Primary=1.47 cfs 4,700 cf

Link DP-4: Brook Street South Inflow=3.21 cfs 9,555 cf
Primary=3.21 cfs 9,555 cf

Link DP-5: Brook Street North Inflow=1.22 cfs 3,695 cf
Primary=1.22 cfs 3,695 cf

Link DP-6: Total Offsite Flow Inflow=19.22 cfs 65,610 cf
Primary=19.22 cfs 65,610 cf

Total Runoff Area = 122,395 sf Runoff Volume = 65,610 cf Average Runoff Depth = 6.43"
41.80% Pervious = 51,160 sf 58.20% Impervious = 71,235 sf

Summary for Subcatchment EDA-10: Area Draining Offsite to the West


Runoff = 1.21 cfs @ 12.03 hrs, Volume= 3,700 cf, Depth= 3.62"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 100-yr Rainfall=9.18"

Area (sf)	CN	Description
* 1,575	98	Impervious, HSG A
10,695	49	50-75% Grass cover, Fair, HSG A
12,270	55	Weighted Average
10,695		87.16% Pervious Area
1,575		12.84% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
4.6	50	0.0300	0.18		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
4.6	50	Total, Increased to minimum Tc = 5.0 min			

Subcatchment EDA-10: Area Draining Offsite to the West



Summary for Subcatchment EDA-20: Area Draining to Grove Street South

Runoff = 12.34 cfs @ 12.05 hrs, Volume= 43,960 cf, Depth= 7.85"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 100-yr Rainfall=9.18"

Area (sf)	CN	Description
* 54,565	98	Impervious, HSG A
12,660	49	50-75% Grass cover, Fair, HSG A
67,225	89	Weighted Average
12,660		18.83% Pervious Area
54,565		81.17% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
4.6	50	0.0300	0.18		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.4	25	0.0200	1.09		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
2.1	361	0.0200	2.87		Shallow Concentrated Flow, Paved Kv= 20.3 fps
7.1	436	Total			

Subcatchment EDA-20: Area Draining to Grove Street South

Hydrograph



Summary for Subcatchment EDA-30: Area Draining to Grove Street North


Runoff = 1.47 cfs @ 12.04 hrs, Volume= 4,700 cf, Depth= 6.24"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 100-yr Rainfall=9.18"

Area (sf)	CN	Description
* 4,980	98	Impervious, HSG A
4,055	49	50-75% Grass cover, Fair, HSG A
9,035	76	Weighted Average
4,055		44.88% Pervious Area
4,980		55.12% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.7	66	0.0300	0.19		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.4	27	0.0200	1.11		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
6.1	93	Total			

Subcatchment EDA-30: Area Draining to Grove Street North



Summary for Subcatchment EDA-40: Area Draining to Brook Street South


Runoff = 3.21 cfs @ 12.03 hrs, Volume= 9,555 cf, Depth= 5.12"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 100-yr Rainfall=9.18"

Area (sf)	CN	Description
* 8,130	98	Impervious, HSG A
14,270	49	50-75% Grass cover, Fair, HSG A
22,400	67	Weighted Average
14,270		63.71% Pervious Area
8,130		36.29% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
4.5	70	0.0600	0.26		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.1	26	0.4000	3.65		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
4.6	96	Total, Increased to minimum Tc = 5.0 min			

Subcatchment EDA-40: Area Draining to Brook Street South



Summary for Subcatchment EDA-50: Area Draining to Brook Street North


Runoff = 1.22 cfs @ 12.03 hrs, Volume= 3,695 cf, Depth= 3.87"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 100-yr Rainfall=9.18"

Area (sf)	CN	Description
1,985	98	Impervious, HSG A
9,480	49	50-75% Grass cover, Fair, HSG A
11,465	57	Weighted Average
9,480		82.69% Pervious Area
1,985		17.31% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
4.0	55	0.0500	0.23		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.1	18	0.6000	3.99		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
4.1	73	Total, Increased to minimum Tc = 5.0 min			

Subcatchment EDA-50: Area Draining to Brook Street North




Summary for Link DP-1: Offsite West

Inflow Area = 12,270 sf, 12.84% Impervious, Inflow Depth = 3.62" for 100-yr event
Inflow = 1.21 cfs @ 12.03 hrs, Volume= 3,700 cf
Primary = 1.21 cfs @ 12.03 hrs, Volume= 3,700 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-1: Offsite West




Summary for Link DP-2: Grove Street South

Inflow Area = 67,225 sf, 81.17% Impervious, Inflow Depth = 7.85" for 100-yr event
Inflow = 12.34 cfs @ 12.05 hrs, Volume= 43,960 cf
Primary = 12.34 cfs @ 12.05 hrs, Volume= 43,960 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-2: Grove Street South




Summary for Link DP-3: Grove Street North

Inflow Area = 9,035 sf, 55.12% Impervious, Inflow Depth = 6.24" for 100-yr event
Inflow = 1.47 cfs @ 12.04 hrs, Volume= 4,700 cf
Primary = 1.47 cfs @ 12.04 hrs, Volume= 4,700 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-3: Grove Street North




Summary for Link DP-4: Brook Street South

Inflow Area = 22,400 sf, 36.29% Impervious, Inflow Depth = 5.12" for 100-yr event
Inflow = 3.21 cfs @ 12.03 hrs, Volume= 9,555 cf
Primary = 3.21 cfs @ 12.03 hrs, Volume= 9,555 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-4: Brook Street South




Summary for Link DP-5: Brook Street North

Inflow Area = 11,465 sf, 17.31% Impervious, Inflow Depth = 3.87" for 100-yr event
Inflow = 1.22 cfs @ 12.03 hrs, Volume= 3,695 cf
Primary = 1.22 cfs @ 12.03 hrs, Volume= 3,695 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-5: Brook Street North




Summary for Link DP-6: Total Offsite Flow

Inflow Area = 122,395 sf, 58.20% Impervious, Inflow Depth = 6.43" for 100-yr event
Inflow = 19.22 cfs @ 12.04 hrs, Volume= 65,610 cf
Primary = 19.22 cfs @ 12.04 hrs, Volume= 65,610 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-6: Total Offsite Flow






An Employee-Owned Company
Stormwater Management Report

APPENDIX C

POST-DEVELOPMENT HYDROLOGY



C-CALC-2202472-Proposed Conditions

Type III 24-hr 1" Depth Rainfall=1.00"

Prepared by BL Companies

Printed 4/14/2023

HydroCAD® 10.00-25 s/n 01334 © 2019 HydroCAD Software Solutions LLC

Page 2

Time span=0.00-28.00 hrs, dt=0.01 hrs, 2801 points
 Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
 Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

SubcatchmentPDA-100: Area Draining Runoff Area=19,320 sf 6.83% Impervious Runoff Depth=0.00"
 Flow Length=50' Slope=0.0300 1/100 Tc=5.0 min CN=43 Runoff=0.00 cfs 0 cf

SubcatchmentPDA-110: School Parking Runoff Area=14,030 sf 85.25% Impervious Runoff Depth=0.28"
 Flow Length=181' Slope=0.0200 1/100 Tc=5.5 min CN=89 Runoff=0.10 cfs 333 cf

SubcatchmentPDA-120: School Roof Runoff Area=10,425 sf 100.00% Impervious Runoff Depth=0.79"
 Tc=5.0 min CN=98 Runoff=0.22 cfs 687 cf

SubcatchmentPDA-130: Church Parking Runoff Area=8,295 sf 84.63% Impervious Runoff Depth=0.28"
 Flow Length=151' Tc=5.0 min CN=89 Runoff=0.06 cfs 197 cf

SubcatchmentPDA-140: Rectory Parking Runoff Area=11,585 sf 74.36% Impervious Runoff Depth=0.13"
 Flow Length=64' Slope=0.0300 1/100 Tc=5.0 min CN=83 Runoff=0.03 cfs 128 cf

SubcatchmentPDA-200: Area Draining to Runoff Area=34,990 sf 70.66% Impervious Runoff Depth=0.10"
 Flow Length=447' Tc=7.6 min CN=81 Runoff=0.04 cfs 286 cf

SubcatchmentPDA-300: Area Draining to Runoff Area=8,855 sf 57.48% Impervious Runoff Depth=0.02"
 Flow Length=93' Tc=6.1 min CN=73 Runoff=0.00 cfs 13 cf

SubcatchmentPDA-400: Area Draining to Runoff Area=10,875 sf 36.28% Impervious Runoff Depth=0.00"
 Flow Length=62' Tc=5.0 min CN=60 Runoff=0.00 cfs 0 cf

SubcatchmentPDA-500: Area Draining to Runoff Area=4,020 sf 1.12% Impervious Runoff Depth=0.00"
 Flow Length=53' Tc=5.0 min CN=40 Runoff=0.00 cfs 0 cf

Pond 1P: Underground Detention System Peak Elev=97.44' Storage=569 cf Inflow=0.40 cfs 1,345 cf
 Discarded=0.03 cfs 1,345 cf Primary=0.00 cfs 0 cf Outflow=0.03 cfs 1,345 cf

Link DP-1: Offsite West Inflow=0.00 cfs 0 cf
 Primary=0.00 cfs 0 cf

Link DP-2: Grove Street South Inflow=0.04 cfs 286 cf
 Primary=0.04 cfs 286 cf

Link DP-3: Grove Street North Inflow=0.00 cfs 13 cf
 Primary=0.00 cfs 13 cf

Link DP-4: Brook Street South Inflow=0.00 cfs 0 cf
 Primary=0.00 cfs 0 cf

Link DP-5: Brook Street North Inflow=0.00 cfs 0 cf
 Primary=0.00 cfs 0 cf

Link DP-6: Total Offsite Flow Inflow=0.04 cfs 298 cf
 Primary=0.04 cfs 298 cf

C-CALC-2202472-Proposed Conditions

Type III 24-hr 1" Depth Rainfall=1.00"

Prepared by BL Companies

Printed 4/14/2023

HydroCAD® 10.00-25 s/n 01334 © 2019 HydroCAD Software Solutions LLC

Page 3

Total Runoff Area = 122,395 sf Runoff Volume = 1,643 cf Average Runoff Depth = 0.16"
40.24% Pervious = 49,250 sf 59.76% Impervious = 73,145 sf

C-CALC-2202472-Proposed Conditions

Type III 24-hr 1" Depth Rainfall=1.00"

Prepared by BL Companies

Printed 4/14/2023

HydroCAD® 10.00-25 s/n 01334 © 2019 HydroCAD Software Solutions LLC

Page 4

Summary for Subcatchment PDA-100: Area Draining Offsite to the West


Runoff = 0.00 cfs @ 0.00 hrs, Volume= 0 cf, Depth= 0.00"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
Type III 24-hr 1" Depth Rainfall=1.00"

	Area (sf)	CN	Description
*	1,320	98	Impervious, HSG A
	18,000	39	>75% Grass cover, Good, HSG A
	19,320	43	Weighted Average
	18,000		93.17% Pervious Area
	1,320		6.83% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
4.6	50	0.0300	0.18		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
4.6	50	Total, Increased to minimum Tc = 5.0 min			

Subcatchment PDA-100: Area Draining Offsite to the West



C-CALC-2202472-Proposed Conditions

Type III 24-hr 1" Depth Rainfall=1.00"

Prepared by BL Companies

Printed 4/14/2023

HydroCAD® 10.00-25 s/n 01334 © 2019 HydroCAD Software Solutions LLC

Page 5

Summary for Subcatchment PDA-110: School Parking Area to UDS

Runoff = 0.10 cfs @ 12.09 hrs, Volume= 333 cf, Depth= 0.28"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
Type III 24-hr 1" Depth Rainfall=1.00"

Area (sf)	CN	Description
* 11,960	98	Impervious, HSG A
2,070	39	>75% Grass cover, Good, HSG A
14,030	89	Weighted Average
2,070		14.75% Pervious Area
11,960		85.25% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
4.2	37	0.0200	0.15		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.8	63	0.0200	1.32		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
0.5	81	0.0200	2.87		Shallow Concentrated Flow, Paved Kv= 20.3 fps
5.5	181	Total			

Subcatchment PDA-110: School Parking Area to UDS

Hydrograph



C-CALC-2202472-Proposed Conditions

Prepared by BL Companies

HydroCAD® 10.00-25 s/n 01334 © 2019 HydroCAD Software Solutions LLC

Type III 24-hr 1" Depth Rainfall=1.00"

Printed 4/14/2023

Page 6

Summary for Subcatchment PDA-120: School Roof Area to UDS

Runoff = 0.22 cfs @ 12.07 hrs, Volume= 687 cf, Depth= 0.79"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
Type III 24-hr 1" Depth Rainfall=1.00"

Area (sf)	CN	Description
* 10,425	98	Impervious, HSG A
10,425		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

Subcatchment PDA-120: School Roof Area to UDS

Hydrograph



C-CALC-2202472-Proposed Conditions

Type III 24-hr 1" Depth Rainfall=1.00"

Prepared by BL Companies

Printed 4/14/2023

HydroCAD® 10.00-25 s/n 01334 © 2019 HydroCAD Software Solutions LLC

Page 7

Summary for Subcatchment PDA-130: Church Parking Area to UDS

Runoff = 0.06 cfs @ 12.08 hrs, Volume= 197 cf, Depth= 0.28"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
Type III 24-hr 1" Depth Rainfall=1.00"

Area (sf)	CN	Description
* 7,020	98	Impervious, HSG A
1,275	39	>75% Grass cover, Good, HSG A
8,295	89	Weighted Average
1,275		15.37% Pervious Area
7,020		84.63% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.7	22	0.0100	0.10		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.8	78	0.0350	1.72		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
0.2	51	0.0350	3.80		Shallow Concentrated Flow, Paved Kv= 20.3 fps
4.7	151	Total, Increased to minimum Tc = 5.0 min			

Subcatchment PDA-130: Church Parking Area to UDS

Hydrograph



C-CALC-2202472-Proposed Conditions

Type III 24-hr 1" Depth Rainfall=1.00"

Prepared by BL Companies

Printed 4/14/2023

HydroCAD® 10.00-25 s/n 01334 © 2019 HydroCAD Software Solutions LLC

Page 8

Summary for Subcatchment PDA-140: Rectory Parking Area to UDS


Runoff = 0.03 cfs @ 12.11 hrs, Volume= 128 cf, Depth= 0.13"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
Type III 24-hr 1" Depth Rainfall=1.00"

Area (sf)	CN	Description
* 8,615	98	Impervious, HSG A
2,970	39	>75% Grass cover, Good, HSG A
11,585	83	Weighted Average
2,970		25.64% Pervious Area
8,615		74.36% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.8	16	0.0300	0.15		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.5	48	0.0300	1.47		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
2.3	64	Total, Increased to minimum Tc = 5.0 min			

Subcatchment PDA-140: Rectory Parking Area to UDS



C-CALC-2202472-Proposed Conditions

Type III 24-hr 1" Depth Rainfall=1.00"

Prepared by BL Companies

Printed 4/14/2023

HydroCAD® 10.00-25 s/n 01334 © 2019 HydroCAD Software Solutions LLC

Page 9

Summary for Subcatchment PDA-200: Area Draining to Grove Street South

Runoff = 0.04 cfs @ 12.30 hrs, Volume= 286 cf, Depth= 0.10"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
Type III 24-hr 1" Depth Rainfall=1.00"

	Area (sf)	CN	Description
*	24,725	98	Impervious, HSG A
	10,265	39	>75% Grass cover, Good, HSG A
	34,990	81	Weighted Average
	10,265		29.34% Pervious Area
	24,725		70.66% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
4.7	30	0.0100	0.11		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.9	70	0.0200	1.34		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
2.0	347	0.0200	2.87		Shallow Concentrated Flow, Paved Kv= 20.3 fps
7.6	447	Total			

Subcatchment PDA-200: Area Draining to Grove Street South

Hydrograph



C-CALC-2202472-Proposed Conditions

Type III 24-hr 1" Depth Rainfall=1.00"

Prepared by BL Companies

Printed 4/14/2023

HydroCAD® 10.00-25 s/n 01334 © 2019 HydroCAD Software Solutions LLC

Page 11

Summary for Subcatchment PDA-400: Area Draining to Brook Street South


Runoff = 0.00 cfs @ 0.00 hrs, Volume= 0 cf, Depth= 0.00"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 Type III 24-hr 1" Depth Rainfall=1.00"

Area (sf)	CN	Description
* 3,945	98	Impervious, HSG A
6,930	39	>75% Grass cover, Good, HSG A
10,875	60	Weighted Average
6,930		63.72% Pervious Area
3,945		36.28% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.6	37	0.0300	0.17		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.1	25	0.4000	3.62		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
3.7	62	Total, Increased to minimum Tc = 5.0 min			

Subcatchment PDA-400: Area Draining to Brook Street South



C-CALC-2202472-Proposed Conditions

Type III 24-hr 1" Depth Rainfall=1.00"

Prepared by BL Companies

Printed 4/14/2023

HydroCAD® 10.00-25 s/n 01334 © 2019 HydroCAD Software Solutions LLC

Page 12

Summary for Subcatchment PDA-500: Area Draining to Brook Street North


Runoff = 0.00 cfs @ 0.00 hrs, Volume= 0 cf, Depth= 0.00"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 Type III 24-hr 1" Depth Rainfall=1.00"

Area (sf)	CN	Description
* 45	98	Impervious, HSG A
3,975	39	>75% Grass cover, Good, HSG A
4,020	40	Weighted Average
3,975		98.88% Pervious Area
45		1.12% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.4	35	0.0300	0.17		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.1	18	0.6000	3.99		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
3.5	53	Total, Increased to minimum Tc = 5.0 min			

Subcatchment PDA-500: Area Draining to Brook Street North



C-CALC-2202472-Proposed Conditions

Type III 24-hr 1" Depth Rainfall=1.00"

Prepared by BL Companies

Printed 4/14/2023

HydroCAD® 10.00-25 s/n 01334 © 2019 HydroCAD Software Solutions LLC

Page 13

Summary for Pond 1P: Underground Detention System

Inflow Area = 44,335 sf, 85.76% Impervious, Inflow Depth = 0.36" for 1" Depth event
 Inflow = 0.40 cfs @ 12.08 hrs, Volume= 1,345 cf
 Outflow = 0.03 cfs @ 11.77 hrs, Volume= 1,345 cf, Atten= 93%, Lag= 0.0 min
 Discarded = 0.03 cfs @ 11.77 hrs, Volume= 1,345 cf
 Primary = 0.00 cfs @ 0.00 hrs, Volume= 0 cf

Routing by Stor-Ind method, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 Peak Elev= 97.44' @ 14.09 hrs Surf.Area= 3,095 sf Storage= 569 cf

Plug-Flow detention time= 195.1 min calculated for 1,345 cf (100% of inflow)
 Center-of-Mass det. time= 195.1 min (1,026.9 - 831.7)

Volume	Invert	Avail.Storage	Storage Description
#1A	96.98'	3,408 cf	34.75"W x 89.06"L x 4.00"H Field A 12,379 cf Overall - 3,859 cf Embedded = 8,520 cf x 40.0% Voids
#2A	97.98'	3,859 cf	ADS_StormTech SC-740 +Cap x 84 Inside #1 Effective Size= 44.6"W x 30.0"H => 6.45 sf x 7.12'L = 45.9 cf Overall Size= 51.0"W x 30.0"H x 7.56'L with 0.44' Overlap 84 Chambers in 7 Rows
		7,267 cf	Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	98.40'	18.0" Round Culvert L= 20.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 98.40' / 98.30' S= 0.0050 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 1.77 sf
#2	Device 1	100.05'	4.0' long Sharp-Crested Rectangular Weir 2 End Contraction(s)
#3	Discarded	96.98'	0.400 in/hr Exfiltration over Surface area

Discarded OutFlow Max=0.03 cfs @ 11.77 hrs HW=97.02' (Free Discharge)
 ↑**3=Exfiltration** (Exfiltration Controls 0.03 cfs)

Primary OutFlow Max=0.00 cfs @ 0.00 hrs HW=96.98' (Free Discharge)
 ↑**1=Culvert** (Controls 0.00 cfs)
 ↑**2=Sharp-Crested Rectangular Weir**(Controls 0.00 cfs)

C-CALC-2202472-Proposed Conditions

Type III 24-hr 1" Depth Rainfall=1.00"

Prepared by BL Companies

Printed 4/14/2023

HydroCAD® 10.00-25 s/n 01334 © 2019 HydroCAD Software Solutions LLC

Page 14

Pond 1P: Underground Detention System - Chamber Wizard Field A

Chamber Model = ADS_StormTechSC-740 +Cap (ADS StormTech®SC-740 with cap length)

Effective Size= 44.6"W x 30.0"H => 6.45 sf x 7.12'L = 45.9 cf

Overall Size= 51.0"W x 30.0"H x 7.56'L with 0.44' Overlap

51.0" Wide + 6.0" Spacing = 57.0" C-C Row Spacing

12 Chambers/Row x 7.12' Long +0.81' Cap Length x 2 = 87.06' Row Length +12.0" End Stone x 2 = 89.06' Base Length

7 Rows x 51.0" Wide + 6.0" Spacing x 6 + 12.0" Side Stone x 2 = 34.75' Base Width

12.0" Base + 30.0" Chamber Height + 6.0" Cover = 4.00' Field Height

84 Chambers x 45.9 cf = 3,859.0 cf Chamber Storage

12,378.9 cf Field - 3,859.0 cf Chambers = 8,519.9 cf Stone x 40.0% Voids = 3,408.0 cf Stone Storage

Chamber Storage + Stone Storage = 7,266.9 cf = 0.167 af


Overall Storage Efficiency = 58.7%

Overall System Size = 89.06' x 34.75' x 4.00'


84 Chambers

458.5 cy Field

315.6 cy Stone



Pond 1P: Underground Detention System




Summary for Link DP-1: Offsite West

Inflow Area = 63,655 sf, 61.80% Impervious, Inflow Depth = 0.00" for 1" Depth event
Inflow = 0.00 cfs @ 0.00 hrs, Volume= 0 cf
Primary = 0.00 cfs @ 0.00 hrs, Volume= 0 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-1: Offsite West




Summary for Link DP-2: Grove Street South

Inflow Area = 34,990 sf, 70.66% Impervious, Inflow Depth = 0.10" for 1" Depth event
Inflow = 0.04 cfs @ 12.30 hrs, Volume= 286 cf
Primary = 0.04 cfs @ 12.30 hrs, Volume= 286 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-2: Grove Street South

Hydrograph




Summary for Link DP-3: Grove Street North

Inflow Area = 8,855 sf, 57.48% Impervious, Inflow Depth = 0.02" for 1" Depth event
Inflow = 0.00 cfs @ 15.12 hrs, Volume= 13 cf
Primary = 0.00 cfs @ 15.12 hrs, Volume= 13 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-3: Grove Street North

Hydrograph



C-CALC-2202472-Proposed Conditions

Type III 24-hr 1" Depth Rainfall=1.00"

Prepared by BL Companies

Printed 4/14/2023

HydroCAD® 10.00-25 s/n 01334 © 2019 HydroCAD Software Solutions LLC


Page 19

Summary for Link DP-4: Brook Street South

Inflow Area = 10,875 sf, 36.28% Impervious, Inflow Depth = 0.00" for 1" Depth event
Inflow = 0.00 cfs @ 0.00 hrs, Volume= 0 cf
Primary = 0.00 cfs @ 0.00 hrs, Volume= 0 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-4: Brook Street South




Summary for Link DP-5: Brook Street North

Inflow Area = 4,020 sf, 1.12% Impervious, Inflow Depth = 0.00" for 1" Depth event
Inflow = 0.00 cfs @ 0.00 hrs, Volume= 0 cf
Primary = 0.00 cfs @ 0.00 hrs, Volume= 0 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-5: Brook Street North




Summary for Link DP-6: Total Offsite Flow

Inflow Area = 122,395 sf, 59.76% Impervious, Inflow Depth = 0.03" for 1" Depth event
Inflow = 0.04 cfs @ 12.30 hrs, Volume= 298 cf
Primary = 0.04 cfs @ 12.30 hrs, Volume= 298 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-6: Total Offsite Flow

Hydrograph



Time span=0.00-28.00 hrs, dt=0.01 hrs, 2801 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

SubcatchmentPDA-100: Area Draining Runoff Area=19,320 sf 6.83% Impervious Runoff Depth=0.05"
Flow Length=50' Slope=0.0300 '/' Tc=5.0 min CN=43 Runoff=0.00 cfs 86 cf

SubcatchmentPDA-110: School Parking Runoff Area=14,030 sf 85.25% Impervious Runoff Depth=2.38"
Flow Length=181' Slope=0.0200 '/' Tc=5.5 min CN=89 Runoff=1.05 cfs 2,778 cf

SubcatchmentPDA-120: School Roof Runoff Area=10,425 sf 100.00% Impervious Runoff Depth=3.29"
Tc=5.0 min CN=98 Runoff=1.00 cfs 2,855 cf

SubcatchmentPDA-130: Church Parking Runoff Area=8,295 sf 84.63% Impervious Runoff Depth=2.38"
Flow Length=151' Tc=5.0 min CN=89 Runoff=0.64 cfs 1,642 cf

SubcatchmentPDA-140: Rectory Parking Runoff Area=11,585 sf 74.36% Impervious Runoff Depth=1.88"
Flow Length=64' Slope=0.0300 '/' Tc=5.0 min CN=83 Runoff=0.71 cfs 1,811 cf

SubcatchmentPDA-200: Area Draining to Runoff Area=34,990 sf 70.66% Impervious Runoff Depth=1.72"
Flow Length=447' Tc=7.6 min CN=81 Runoff=1.68 cfs 5,029 cf

SubcatchmentPDA-300: Area Draining to Runoff Area=8,855 sf 57.48% Impervious Runoff Depth=1.19"
Flow Length=93' Tc=6.1 min CN=73 Runoff=0.30 cfs 880 cf

SubcatchmentPDA-400: Area Draining to Runoff Area=10,875 sf 36.28% Impervious Runoff Depth=0.54"
Flow Length=62' Tc=5.0 min CN=60 Runoff=0.12 cfs 489 cf

SubcatchmentPDA-500: Area Draining to Runoff Area=4,020 sf 1.12% Impervious Runoff Depth=0.02"
Flow Length=53' Tc=5.0 min CN=40 Runoff=0.00 cfs 6 cf

Pond 1P: Underground Detention System Peak Elev=100.08' Storage=6,057 cf Inflow=3.39 cfs 9,085 cf
Discarded=0.03 cfs 2,395 cf Primary=0.06 cfs 1,067 cf Outflow=0.09 cfs 3,461 cf

Link DP-1: Offsite West Inflow=0.06 cfs 1,153 cf
Primary=0.06 cfs 1,153 cf

Link DP-2: Grove Street South Inflow=1.68 cfs 5,029 cf
Primary=1.68 cfs 5,029 cf

Link DP-3: Grove Street North Inflow=0.30 cfs 880 cf
Primary=0.30 cfs 880 cf

Link DP-4: Brook Street South Inflow=0.12 cfs 489 cf
Primary=0.12 cfs 489 cf

Link DP-5: Brook Street North Inflow=0.00 cfs 6 cf
Primary=0.00 cfs 6 cf

Link DP-6: Total Offsite Flow Inflow=2.10 cfs 7,557 cf
Primary=2.10 cfs 7,557 cf

Total Runoff Area = 122,395 sf Runoff Volume = 15,576 cf Average Runoff Depth = 1.53"
40.24% Pervious = 49,250 sf 59.76% Impervious = 73,145 sf

Summary for Subcatchment PDA-100: Area Draining Offsite to the West

Runoff = 0.00 cfs @ 21.74 hrs, Volume= 86 cf, Depth= 0.05"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 2-yr Rainfall=3.52"

Area (sf)	CN	Description
* 1,320	98	Impervious, HSG A
18,000	39	>75% Grass cover, Good, HSG A
19,320	43	Weighted Average
18,000		93.17% Pervious Area
1,320		6.83% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
4.6	50	0.0300	0.18		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
4.6	50	Total, Increased to minimum Tc = 5.0 min			

Subcatchment PDA-100: Area Draining Offsite to the West

Hydrograph



Summary for Subcatchment PDA-110: School Parking Area to UDS

Runoff = 1.05 cfs @ 12.03 hrs, Volume= 2,778 cf, Depth= 2.38"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 2-yr Rainfall=3.52"

Area (sf)	CN	Description
* 11,960	98	Impervious, HSG A
2,070	39	>75% Grass cover, Good, HSG A
14,030	89	Weighted Average
2,070		14.75% Pervious Area
11,960		85.25% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
4.2	37	0.0200	0.15		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.8	63	0.0200	1.32		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
0.5	81	0.0200	2.87		Shallow Concentrated Flow, Paved Kv= 20.3 fps
5.5	181	Total			

Subcatchment PDA-110: School Parking Area to UDS

Hydrograph



Summary for Subcatchment PDA-120: School Roof Area to UDS


Runoff = 1.00 cfs @ 12.03 hrs, Volume= 2,855 cf, Depth= 3.29"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 2-yr Rainfall=3.52"

Area (sf)	CN	Description
* 10,425	98	Impervious, HSG A
10,425		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

Subcatchment PDA-120: School Roof Area to UDS



Summary for Subcatchment PDA-130: Church Parking Area to UDS

Runoff = 0.64 cfs @ 12.03 hrs, Volume= 1,642 cf, Depth= 2.38"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 2-yr Rainfall=3.52"

Area (sf)	CN	Description
* 7,020	98	Impervious, HSG A
1,275	39	>75% Grass cover, Good, HSG A
8,295	89	Weighted Average
1,275		15.37% Pervious Area
7,020		84.63% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.7	22	0.0100	0.10		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.8	78	0.0350	1.72		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
0.2	51	0.0350	3.80		Shallow Concentrated Flow, Paved Kv= 20.3 fps
4.7	151	Total, Increased to minimum Tc = 5.0 min			

Subcatchment PDA-130: Church Parking Area to UDS

Hydrograph



Summary for Subcatchment PDA-140: Rectory Parking Area to UDS


Runoff = 0.71 cfs @ 12.03 hrs, Volume= 1,811 cf, Depth= 1.88"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 2-yr Rainfall=3.52"

Area (sf)	CN	Description
* 8,615	98	Impervious, HSG A
2,970	39	>75% Grass cover, Good, HSG A
11,585	83	Weighted Average
2,970		25.64% Pervious Area
8,615		74.36% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.8	16	0.0300	0.15		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.5	48	0.0300	1.47		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
2.3	64	Total, Increased to minimum Tc = 5.0 min			

Subcatchment PDA-140: Rectory Parking Area to UDS



Summary for Subcatchment PDA-200: Area Draining to Grove Street South


Runoff = 1.68 cfs @ 12.06 hrs, Volume= 5,029 cf, Depth= 1.72"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 2-yr Rainfall=3.52"

Area (sf)	CN	Description
24,725	98	Impervious, HSG A
10,265	39	>75% Grass cover, Good, HSG A
34,990	81	Weighted Average
10,265		29.34% Pervious Area
24,725		70.66% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
4.7	30	0.0100	0.11		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.9	70	0.0200	1.34		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
2.0	347	0.0200	2.87		Shallow Concentrated Flow, Paved Kv= 20.3 fps
7.6	447	Total			

Subcatchment PDA-200: Area Draining to Grove Street South



Summary for Subcatchment PDA-300: Area Draining to Grove Street North


Runoff = 0.30 cfs @ 12.04 hrs, Volume= 880 cf, Depth= 1.19"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 2-yr Rainfall=3.52"

Area (sf)	CN	Description
* 5,090	98	Impervious, HSG A
3,765	39	>75% Grass cover, Good, HSG A
8,855	73	Weighted Average
3,765		42.52% Pervious Area
5,090		57.48% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.7	66	0.0300	0.19		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.4	27	0.0200	1.11		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
6.1	93	Total			

Subcatchment PDA-300: Area Draining to Grove Street North



Summary for Subcatchment PDA-400: Area Draining to Brook Street South


Runoff = 0.12 cfs @ 12.04 hrs, Volume= 489 cf, Depth= 0.54"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 2-yr Rainfall=3.52"

Area (sf)	CN	Description
* 3,945	98	Impervious, HSG A
6,930	39	>75% Grass cover, Good, HSG A
10,875	60	Weighted Average
6,930		63.72% Pervious Area
3,945		36.28% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.6	37	0.0300	0.17		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.1	25	0.4000	3.62		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
3.7	62	Total, Increased to minimum Tc = 5.0 min			

Subcatchment PDA-400: Area Draining to Brook Street South



Summary for Pond 1P: Underground Detention System

Inflow Area = 44,335 sf, 85.76% Impervious, Inflow Depth = 2.46" for 2-yr event
 Inflow = 3.39 cfs @ 12.03 hrs, Volume= 9,085 cf
 Outflow = 0.09 cfs @ 16.18 hrs, Volume= 3,461 cf, Atten= 97%, Lag= 249.3 min
 Discarded = 0.03 cfs @ 7.30 hrs, Volume= 2,395 cf
 Primary = 0.06 cfs @ 16.18 hrs, Volume= 1,067 cf

Routing by Stor-Ind method, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 Peak Elev= 100.08' @ 16.18 hrs Surf.Area= 3,095 sf Storage= 6,057 cf

Plug-Flow detention time= 394.0 min calculated for 3,461 cf (38% of inflow)
 Center-of-Mass det. time= 223.0 min (1,029.7 - 806.7)

Volume	Invert	Avail.Storage	Storage Description
#1A	96.98'	3,408 cf	34.75"W x 89.06'L x 4.00'H Field A 12,379 cf Overall - 3,859 cf Embedded = 8,520 cf x 40.0% Voids
#2A	97.98'	3,859 cf	ADS_StormTech SC-740 +Cap x 84 Inside #1 Effective Size= 44.6"W x 30.0"H => 6.45 sf x 7.12'L = 45.9 cf Overall Size= 51.0"W x 30.0"H x 7.56'L with 0.44' Overlap 84 Chambers in 7 Rows
		7,267 cf	Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	98.40'	18.0" Round Culvert L= 20.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 98.40' / 98.30' S= 0.0050 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 1.77 sf
#2	Device 1	100.05'	4.0' long Sharp-Crested Rectangular Weir 2 End Contraction(s)
#3	Discarded	96.98'	0.400 in/hr Exfiltration over Surface area

Discarded OutFlow Max=0.03 cfs @ 7.30 hrs HW=97.02' (Free Discharge)
 ↑ **3=Exfiltration** (Exfiltration Controls 0.03 cfs)

Primary OutFlow Max=0.05 cfs @ 16.18 hrs HW=100.08' (Free Discharge)
 ↑ **1=Culvert** (Passes 0.05 cfs of 6.85 cfs potential flow)
 ↑ **2=Sharp-Crested Rectangular Weir**(Weir Controls 0.05 cfs @ 0.52 fps)

Pond 1P: Underground Detention System - Chamber Wizard Field A

Chamber Model = ADS_StormTechSC-740 +Cap (ADS StormTech®SC-740 with cap length)

Effective Size= 44.6"W x 30.0"H => 6.45 sf x 7.12'L = 45.9 cf

Overall Size= 51.0"W x 30.0"H x 7.56'L with 0.44' Overlap

51.0" Wide + 6.0" Spacing = 57.0" C-C Row Spacing

12 Chambers/Row x 7.12' Long +0.81' Cap Length x 2 = 87.06' Row Length +12.0" End Stone x 2 = 89.06' Base Length

7 Rows x 51.0" Wide + 6.0" Spacing x 6 + 12.0" Side Stone x 2 = 34.75' Base Width

12.0" Base + 30.0" Chamber Height + 6.0" Cover = 4.00' Field Height

84 Chambers x 45.9 cf = 3,859.0 cf Chamber Storage


12,378.9 cf Field - 3,859.0 cf Chambers = 8,519.9 cf Stone x 40.0% Voids = 3,408.0 cf Stone Storage

Chamber Storage + Stone Storage = 7,266.9 cf = 0.167 af


Overall Storage Efficiency = 58.7%

Overall System Size = 89.06' x 34.75' x 4.00'

84 Chambers
 458.5 cy Field
 315.6 cy Stone



Pond 1P: Underground Detention System




Summary for Link DP-1: Offsite West

Inflow Area = 63,655 sf, 61.80% Impervious, Inflow Depth = 0.22" for 2-yr event
 Inflow = 0.06 cfs @ 16.18 hrs, Volume= 1,153 cf
 Primary = 0.06 cfs @ 16.18 hrs, Volume= 1,153 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-1: Offsite West

Hydrograph




Summary for Link DP-2: Grove Street South

Inflow Area = 34,990 sf, 70.66% Impervious, Inflow Depth = 1.72" for 2-yr event
Inflow = 1.68 cfs @ 12.06 hrs, Volume= 5,029 cf
Primary = 1.68 cfs @ 12.06 hrs, Volume= 5,029 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-2: Grove Street South




Summary for Link DP-3: Grove Street North

Inflow Area = 8,855 sf, 57.48% Impervious, Inflow Depth = 1.19" for 2-yr event
 Inflow = 0.30 cfs @ 12.04 hrs, Volume= 880 cf
 Primary = 0.30 cfs @ 12.04 hrs, Volume= 880 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-3: Grove Street North




Summary for Link DP-4: Brook Street South

Inflow Area = 10,875 sf, 36.28% Impervious, Inflow Depth = 0.54" for 2-yr event
 Inflow = 0.12 cfs @ 12.04 hrs, Volume= 489 cf
 Primary = 0.12 cfs @ 12.04 hrs, Volume= 489 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-4: Brook Street South




Summary for Link DP-5: Brook Street North

Inflow Area = 4,020 sf, 1.12% Impervious, Inflow Depth = 0.02" for 2-yr event
 Inflow = 0.00 cfs @ 24.00 hrs, Volume= 6 cf
 Primary = 0.00 cfs @ 24.00 hrs, Volume= 6 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-5: Brook Street North

Hydrograph




Summary for Link DP-6: Total Offsite Flow

Inflow Area = 122,395 sf, 59.76% Impervious, Inflow Depth = 0.74" for 2-yr event
 Inflow = 2.10 cfs @ 12.05 hrs, Volume= 7,557 cf
 Primary = 2.10 cfs @ 12.05 hrs, Volume= 7,557 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-6: Total Offsite Flow



Time span=0.00-28.00 hrs, dt=0.01 hrs, 2801 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

SubcatchmentPDA-100: Area Draining Runoff Area=19,320 sf 6.83% Impervious Runoff Depth=0.28"
Flow Length=50' Slope=0.0300 '/' Tc=5.0 min CN=43 Runoff=0.02 cfs 450 cf

SubcatchmentPDA-110: School Parking Runoff Area=14,030 sf 85.25% Impervious Runoff Depth=3.50"
Flow Length=181' Slope=0.0200 '/' Tc=5.5 min CN=89 Runoff=1.43 cfs 4,097 cf

SubcatchmentPDA-120: School Roof Runoff Area=10,425 sf 100.00% Impervious Runoff Depth=4.48"
Tc=5.0 min CN=98 Runoff=1.27 cfs 3,895 cf

SubcatchmentPDA-130: Church Parking Runoff Area=8,295 sf 84.63% Impervious Runoff Depth=3.50"
Flow Length=151' Tc=5.0 min CN=89 Runoff=0.87 cfs 2,422 cf

SubcatchmentPDA-140: Rectory Parking Runoff Area=11,585 sf 74.36% Impervious Runoff Depth=2.92"
Flow Length=64' Slope=0.0300 '/' Tc=5.0 min CN=83 Runoff=1.04 cfs 2,821 cf

SubcatchmentPDA-200: Area Draining to Runoff Area=34,990 sf 70.66% Impervious Runoff Depth=2.74"
Flow Length=447' Tc=7.6 min CN=81 Runoff=2.54 cfs 7,987 cf

SubcatchmentPDA-300: Area Draining to Runoff Area=8,855 sf 57.48% Impervious Runoff Depth=2.06"
Flow Length=93' Tc=6.1 min CN=73 Runoff=0.52 cfs 1,522 cf

SubcatchmentPDA-400: Area Draining to Runoff Area=10,875 sf 36.28% Impervious Runoff Depth=1.14"
Flow Length=62' Tc=5.0 min CN=60 Runoff=0.33 cfs 1,034 cf

SubcatchmentPDA-500: Area Draining to Runoff Area=4,020 sf 1.12% Impervious Runoff Depth=0.18"
Flow Length=53' Tc=5.0 min CN=40 Runoff=0.00 cfs 59 cf

Pond 1P: Underground Detention System Peak Elev=100.19' Storage=6,249 cf Inflow=4.61 cfs 13,236 cf
Discarded=0.03 cfs 2,556 cf Primary=0.68 cfs 5,050 cf Outflow=0.71 cfs 7,606 cf

Link DP-1: Offsite West Inflow=0.70 cfs 5,499 cf
Primary=0.70 cfs 5,499 cf

Link DP-2: Grove Street South Inflow=2.54 cfs 7,987 cf
Primary=2.54 cfs 7,987 cf

Link DP-3: Grove Street North Inflow=0.52 cfs 1,522 cf
Primary=0.52 cfs 1,522 cf

Link DP-4: Brook Street South Inflow=0.33 cfs 1,034 cf
Primary=0.33 cfs 1,034 cf

Link DP-5: Brook Street North Inflow=0.00 cfs 59 cf
Primary=0.00 cfs 59 cf

Link DP-6: Total Offsite Flow Inflow=3.35 cfs 16,102 cf
Primary=3.35 cfs 16,102 cf

Total Runoff Area = 122,395 sf Runoff Volume = 24,288 cf Average Runoff Depth = 2.38"
40.24% Pervious = 49,250 sf 59.76% Impervious = 73,145 sf

Summary for Subcatchment PDA-100: Area Draining Offsite to the West


Runoff = 0.02 cfs @ 12.53 hrs, Volume= 450 cf, Depth= 0.28"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 5-yr Rainfall=4.72"

Area (sf)	CN	Description
* 1,320	98	Impervious, HSG A
18,000	39	>75% Grass cover, Good, HSG A
19,320	43	Weighted Average
18,000		93.17% Pervious Area
1,320		6.83% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
4.6	50	0.0300	0.18		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
4.6	50	Total, Increased to minimum Tc = 5.0 min			

Subcatchment PDA-100: Area Draining Offsite to the West



Summary for Subcatchment PDA-110: School Parking Area to UDS


Runoff = 1.43 cfs @ 12.03 hrs, Volume= 4,097 cf, Depth= 3.50"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 5-yr Rainfall=4.72"

Area (sf)	CN	Description
* 11,960	98	Impervious, HSG A
2,070	39	>75% Grass cover, Good, HSG A
14,030	89	Weighted Average
2,070		14.75% Pervious Area
11,960		85.25% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
4.2	37	0.0200	0.15		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.8	63	0.0200	1.32		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
0.5	81	0.0200	2.87		Shallow Concentrated Flow, Paved Kv= 20.3 fps
5.5	181	Total			

Subcatchment PDA-110: School Parking Area to UDS



Summary for Subcatchment PDA-120: School Roof Area to UDS


Runoff = 1.27 cfs @ 12.03 hrs, Volume= 3,895 cf, Depth= 4.48"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 5-yr Rainfall=4.72"

Area (sf)	CN	Description
* 10,425	98	Impervious, HSG A
10,425		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

Subcatchment PDA-120: School Roof Area to UDS



Summary for Subcatchment PDA-130: Church Parking Area to UDS

Runoff = 0.87 cfs @ 12.03 hrs, Volume= 2,422 cf, Depth= 3.50"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 5-yr Rainfall=4.72"

Area (sf)	CN	Description
* 7,020	98	Impervious, HSG A
1,275	39	>75% Grass cover, Good, HSG A
8,295	89	Weighted Average
1,275		15.37% Pervious Area
7,020		84.63% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.7	22	0.0100	0.10		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.8	78	0.0350	1.72		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
0.2	51	0.0350	3.80		Shallow Concentrated Flow, Paved Kv= 20.3 fps
4.7	151	Total, Increased to minimum Tc = 5.0 min			

Subcatchment PDA-130: Church Parking Area to UDS

Hydrograph



Summary for Subcatchment PDA-140: Rectory Parking Area to UDS


Runoff = 1.04 cfs @ 12.03 hrs, Volume= 2,821 cf, Depth= 2.92"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 5-yr Rainfall=4.72"

Area (sf)	CN	Description
* 8,615	98	Impervious, HSG A
2,970	39	>75% Grass cover, Good, HSG A
11,585	83	Weighted Average
2,970		25.64% Pervious Area
8,615		74.36% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.8	16	0.0300	0.15		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.5	48	0.0300	1.47		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
2.3	64	Total, Increased to minimum Tc = 5.0 min			

Subcatchment PDA-140: Rectory Parking Area to UDS



Summary for Subcatchment PDA-200: Area Draining to Grove Street South


Runoff = 2.54 cfs @ 12.06 hrs, Volume= 7,987 cf, Depth= 2.74"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 5-yr Rainfall=4.72"

Area (sf)	CN	Description
* 24,725	98	Impervious, HSG A
10,265	39	>75% Grass cover, Good, HSG A
34,990	81	Weighted Average
10,265		29.34% Pervious Area
24,725		70.66% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
4.7	30	0.0100	0.11		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.9	70	0.0200	1.34		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
2.0	347	0.0200	2.87		Shallow Concentrated Flow, Paved Kv= 20.3 fps
7.6	447	Total			

Subcatchment PDA-200: Area Draining to Grove Street South



Summary for Subcatchment PDA-300: Area Draining to Grove Street North


Runoff = 0.52 cfs @ 12.04 hrs, Volume= 1,522 cf, Depth= 2.06"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 5-yr Rainfall=4.72"

Area (sf)	CN	Description
* 5,090	98	Impervious, HSG A
3,765	39	>75% Grass cover, Good, HSG A
8,855	73	Weighted Average
3,765		42.52% Pervious Area
5,090		57.48% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.7	66	0.0300	0.19		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.4	27	0.0200	1.11		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
6.1	93	Total			

Subcatchment PDA-300: Area Draining to Grove Street North



Summary for Subcatchment PDA-400: Area Draining to Brook Street South


Runoff = 0.33 cfs @ 12.03 hrs, Volume= 1,034 cf, Depth= 1.14"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 5-yr Rainfall=4.72"

Area (sf)	CN	Description
3,945	98	Impervious, HSG A
6,930	39	>75% Grass cover, Good, HSG A
10,875	60	Weighted Average
6,930		63.72% Pervious Area
3,945		36.28% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.6	37	0.0300	0.17		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.1	25	0.4000	3.62		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
3.7	62	Total, Increased to minimum Tc = 5.0 min			

Subcatchment PDA-400: Area Draining to Brook Street South



Summary for Pond 1P: Underground Detention System

Inflow Area = 44,335 sf, 85.76% Impervious, Inflow Depth = 3.58" for 5-yr event
 Inflow = 4.61 cfs @ 12.03 hrs, Volume= 13,236 cf
 Outflow = 0.71 cfs @ 12.45 hrs, Volume= 7,606 cf, Atten= 85%, Lag= 25.2 min
 Discarded = 0.03 cfs @ 5.24 hrs, Volume= 2,556 cf
 Primary = 0.68 cfs @ 12.45 hrs, Volume= 5,050 cf

Routing by Stor-Ind method, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 Peak Elev= 100.19' @ 12.45 hrs Surf.Area= 3,095 sf Storage= 6,249 cf

Plug-Flow detention time= 286.5 min calculated for 7,603 cf (57% of inflow)
 Center-of-Mass det. time= 142.6 min (940.8 - 798.2)

Volume	Invert	Avail.Storage	Storage Description
#1A	96.98'	3,408 cf	34.75'W x 89.06'L x 4.00'H Field A 12,379 cf Overall - 3,859 cf Embedded = 8,520 cf x 40.0% Voids
#2A	97.98'	3,859 cf	ADS_StormTech SC-740 +Cap x 84 Inside #1 Effective Size= 44.6"W x 30.0"H => 6.45 sf x 7.12'L = 45.9 cf Overall Size= 51.0"W x 30.0"H x 7.56'L with 0.44' Overlap 84 Chambers in 7 Rows
		7,267 cf	Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	98.40'	18.0" Round Culvert L= 20.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 98.40' / 98.30' S= 0.0050 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 1.77 sf
#2	Device 1	100.05'	4.0' long Sharp-Crested Rectangular Weir 2 End Contraction(s)
#3	Discarded	96.98'	0.400 in/hr Exfiltration over Surface area

Discarded OutFlow Max=0.03 cfs @ 5.24 hrs HW=97.02' (Free Discharge)
 ↑ **3=Exfiltration** (Exfiltration Controls 0.03 cfs)

Primary OutFlow Max=0.68 cfs @ 12.45 hrs HW=100.19' (Free Discharge)
 ↑ **1=Culvert** (Passes 0.68 cfs of 7.41 cfs potential flow)
 ↑ **2=Sharp-Crested Rectangular Weir**(Weir Controls 0.68 cfs @ 1.22 fps)

Pond 1P: Underground Detention System - Chamber Wizard Field A

Chamber Model = ADS_StormTechSC-740 +Cap (ADS StormTech®SC-740 with cap length)

Effective Size= 44.6"W x 30.0"H => 6.45 sf x 7.12'L = 45.9 cf

Overall Size= 51.0"W x 30.0"H x 7.56'L with 0.44' Overlap

51.0" Wide + 6.0" Spacing = 57.0" C-C Row Spacing

12 Chambers/Row x 7.12' Long +0.81' Cap Length x 2 = 87.06' Row Length +12.0" End Stone x 2 = 89.06' Base Length

7 Rows x 51.0" Wide + 6.0" Spacing x 6 + 12.0" Side Stone x 2 = 34.75' Base Width

12.0" Base + 30.0" Chamber Height + 6.0" Cover = 4.00' Field Height

84 Chambers x 45.9 cf = 3,859.0 cf Chamber Storage

12,378.9 cf Field - 3,859.0 cf Chambers = 8,519.9 cf Stone x 40.0% Voids = 3,408.0 cf Stone Storage

Chamber Storage + Stone Storage = 7,266.9 cf = 0.167 af


Overall Storage Efficiency = 58.7%

Overall System Size = 89.06' x 34.75' x 4.00'


84 Chambers

458.5 cy Field

315.6 cy Stone



Pond 1P: Underground Detention System




Summary for Link DP-1: Offsite West

Inflow Area = 63,655 sf, 61.80% Impervious, Inflow Depth = 1.04" for 5-yr event
Inflow = 0.70 cfs @ 12.45 hrs, Volume= 5,499 cf
Primary = 0.70 cfs @ 12.45 hrs, Volume= 5,499 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-1: Offsite West




Summary for Link DP-2: Grove Street South

Inflow Area = 34,990 sf, 70.66% Impervious, Inflow Depth = 2.74" for 5-yr event
Inflow = 2.54 cfs @ 12.06 hrs, Volume= 7,987 cf
Primary = 2.54 cfs @ 12.06 hrs, Volume= 7,987 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-2: Grove Street South




Summary for Link DP-3: Grove Street North

Inflow Area = 8,855 sf, 57.48% Impervious, Inflow Depth = 2.06" for 5-yr event
Inflow = 0.52 cfs @ 12.04 hrs, Volume= 1,522 cf
Primary = 0.52 cfs @ 12.04 hrs, Volume= 1,522 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-3: Grove Street North




Summary for Link DP-4: Brook Street South

Inflow Area = 10,875 sf, 36.28% Impervious, Inflow Depth = 1.14" for 5-yr event
 Inflow = 0.33 cfs @ 12.03 hrs, Volume= 1,034 cf
 Primary = 0.33 cfs @ 12.03 hrs, Volume= 1,034 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-4: Brook Street South




Summary for Link DP-5: Brook Street North

Inflow Area = 4,020 sf, 1.12% Impervious, Inflow Depth = 0.18" for 5-yr event
 Inflow = 0.00 cfs @ 14.24 hrs, Volume= 59 cf
 Primary = 0.00 cfs @ 14.24 hrs, Volume= 59 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-5: Brook Street North

Hydrograph




Summary for Link DP-6: Total Offsite Flow

Inflow Area = 122,395 sf, 59.76% Impervious, Inflow Depth = 1.58" for 5-yr event
 Inflow = 3.35 cfs @ 12.05 hrs, Volume= 16,102 cf
 Primary = 3.35 cfs @ 12.05 hrs, Volume= 16,102 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-6: Total Offsite Flow



Time span=0.00-28.00 hrs, dt=0.01 hrs, 2801 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

SubcatchmentPDA-100: Area Draining Runoff Area=19,320 sf 6.83% Impervious Runoff Depth=0.57"
Flow Length=50' Slope=0.0300 '/' Tc=5.0 min CN=43 Runoff=0.10 cfs 923 cf

SubcatchmentPDA-110: School Parking Runoff Area=14,030 sf 85.25% Impervious Runoff Depth=4.45"
Flow Length=181' Slope=0.0200 '/' Tc=5.5 min CN=89 Runoff=1.75 cfs 5,209 cf

SubcatchmentPDA-120: School Roof Runoff Area=10,425 sf 100.00% Impervious Runoff Depth=5.47"
Tc=5.0 min CN=98 Runoff=1.49 cfs 4,754 cf

SubcatchmentPDA-130: Church Parking Runoff Area=8,295 sf 84.63% Impervious Runoff Depth=4.45"
Flow Length=151' Tc=5.0 min CN=89 Runoff=1.06 cfs 3,079 cf

SubcatchmentPDA-140: Rectory Parking Runoff Area=11,585 sf 74.36% Impervious Runoff Depth=3.82"
Flow Length=64' Slope=0.0300 '/' Tc=5.0 min CN=83 Runoff=1.31 cfs 3,691 cf

SubcatchmentPDA-200: Area Draining to Runoff Area=34,990 sf 70.66% Impervious Runoff Depth=3.62"
Flow Length=447' Tc=7.6 min CN=81 Runoff=3.25 cfs 10,557 cf

SubcatchmentPDA-300: Area Draining to Runoff Area=8,855 sf 57.48% Impervious Runoff Depth=2.85"
Flow Length=93' Tc=6.1 min CN=73 Runoff=0.70 cfs 2,103 cf

SubcatchmentPDA-400: Area Draining to Runoff Area=10,875 sf 36.28% Impervious Runoff Depth=1.73"
Flow Length=62' Tc=5.0 min CN=60 Runoff=0.52 cfs 1,572 cf

SubcatchmentPDA-500: Area Draining to Runoff Area=4,020 sf 1.12% Impervious Runoff Depth=0.41"
Flow Length=53' Tc=5.0 min CN=40 Runoff=0.01 cfs 139 cf

Pond 1P: Underground Detention System Peak Elev=100.40' Storage=6,546 cf Inflow=5.61 cfs 16,733 cf
Discarded=0.03 cfs 2,635 cf Primary=2.66 cfs 8,464 cf Outflow=2.69 cfs 11,099 cf

Link DP-1: Offsite West Inflow=2.75 cfs 9,387 cf
Primary=2.75 cfs 9,387 cf

Link DP-2: Grove Street South Inflow=3.25 cfs 10,557 cf
Primary=3.25 cfs 10,557 cf

Link DP-3: Grove Street North Inflow=0.70 cfs 2,103 cf
Primary=0.70 cfs 2,103 cf

Link DP-4: Brook Street South Inflow=0.52 cfs 1,572 cf
Primary=0.52 cfs 1,572 cf

Link DP-5: Brook Street North Inflow=0.01 cfs 139 cf
Primary=0.01 cfs 139 cf

Link DP-6: Total Offsite Flow Inflow=6.15 cfs 23,757 cf
Primary=6.15 cfs 23,757 cf

Total Runoff Area = 122,395 sf Runoff Volume = 32,026 cf Average Runoff Depth = 3.14"
40.24% Pervious = 49,250 sf 59.76% Impervious = 73,145 sf

Summary for Subcatchment PDA-100: Area Draining Offsite to the West


Runoff = 0.10 cfs @ 12.06 hrs, Volume= 923 cf, Depth= 0.57"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 10-yr Rainfall=5.71"

Area (sf)	CN	Description
* 1,320	98	Impervious, HSG A
18,000	39	>75% Grass cover, Good, HSG A
19,320	43	Weighted Average
18,000		93.17% Pervious Area
1,320		6.83% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
4.6	50	0.0300	0.18		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
4.6	50	Total, Increased to minimum Tc = 5.0 min			

Subcatchment PDA-100: Area Draining Offsite to the West



Summary for Subcatchment PDA-110: School Parking Area to UDS

Runoff = 1.75 cfs @ 12.03 hrs, Volume= 5,209 cf, Depth= 4.45"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 10-yr Rainfall=5.71"

Area (sf)	CN	Description
* 11,960	98	Impervious, HSG A
2,070	39	>75% Grass cover, Good, HSG A
14,030	89	Weighted Average
2,070		14.75% Pervious Area
11,960		85.25% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
4.2	37	0.0200	0.15		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.8	63	0.0200	1.32		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
0.5	81	0.0200	2.87		Shallow Concentrated Flow, Paved Kv= 20.3 fps
5.5	181	Total			

Subcatchment PDA-110: School Parking Area to UDS

Hydrograph



Summary for Subcatchment PDA-120: School Roof Area to UDS


Runoff = 1.49 cfs @ 12.03 hrs, Volume= 4,754 cf, Depth= 5.47"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 10-yr Rainfall=5.71"

Area (sf)	CN	Description
* 10,425	98	Impervious, HSG A
10,425		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

Subcatchment PDA-120: School Roof Area to UDS



Summary for Subcatchment PDA-130: Church Parking Area to UDS

Runoff = 1.06 cfs @ 12.03 hrs, Volume= 3,079 cf, Depth= 4.45"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 10-yr Rainfall=5.71"

Area (sf)	CN	Description
* 7,020	98	Impervious, HSG A
1,275	39	>75% Grass cover, Good, HSG A
8,295	89	Weighted Average
1,275		15.37% Pervious Area
7,020		84.63% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.7	22	0.0100	0.10		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.8	78	0.0350	1.72		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
0.2	51	0.0350	3.80		Shallow Concentrated Flow, Paved Kv= 20.3 fps
4.7	151	Total, Increased to minimum Tc = 5.0 min			

Subcatchment PDA-130: Church Parking Area to UDS

Hydrograph



Summary for Subcatchment PDA-140: Rectory Parking Area to UDS


Runoff = 1.31 cfs @ 12.03 hrs, Volume= 3,691 cf, Depth= 3.82"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 10-yr Rainfall=5.71"

Area (sf)	CN	Description
* 8,615	98	Impervious, HSG A
2,970	39	>75% Grass cover, Good, HSG A
11,585	83	Weighted Average
2,970		25.64% Pervious Area
8,615		74.36% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.8	16	0.0300	0.15		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.5	48	0.0300	1.47		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
2.3	64	Total, Increased to minimum Tc = 5.0 min			

Subcatchment PDA-140: Rectory Parking Area to UDS



Summary for Subcatchment PDA-200: Area Draining to Grove Street South


Runoff = 3.25 cfs @ 12.06 hrs, Volume= 10,557 cf, Depth= 3.62"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 10-yr Rainfall=5.71"

Area (sf)	CN	Description
* 24,725	98	Impervious, HSG A
10,265	39	>75% Grass cover, Good, HSG A
34,990	81	Weighted Average
10,265		29.34% Pervious Area
24,725		70.66% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
4.7	30	0.0100	0.11		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.9	70	0.0200	1.34		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
2.0	347	0.0200	2.87		Shallow Concentrated Flow, Paved Kv= 20.3 fps
7.6	447	Total			

Subcatchment PDA-200: Area Draining to Grove Street South



Summary for Subcatchment PDA-300: Area Draining to Grove Street North


Runoff = 0.70 cfs @ 12.04 hrs, Volume= 2,103 cf, Depth= 2.85"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 10-yr Rainfall=5.71"

Area (sf)	CN	Description
* 5,090	98	Impervious, HSG A
3,765	39	>75% Grass cover, Good, HSG A
8,855	73	Weighted Average
3,765		42.52% Pervious Area
5,090		57.48% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.7	66	0.0300	0.19		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.4	27	0.0200	1.11		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
6.1	93	Total			

Subcatchment PDA-300: Area Draining to Grove Street North



Summary for Subcatchment PDA-400: Area Draining to Brook Street South


Runoff = 0.52 cfs @ 12.03 hrs, Volume= 1,572 cf, Depth= 1.73"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 10-yr Rainfall=5.71"

Area (sf)	CN	Description
* 3,945	98	Impervious, HSG A
6,930	39	>75% Grass cover, Good, HSG A
10,875	60	Weighted Average
6,930		63.72% Pervious Area
3,945		36.28% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.6	37	0.0300	0.17		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.1	25	0.4000	3.62		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
3.7	62	Total, Increased to minimum Tc = 5.0 min			

Subcatchment PDA-400: Area Draining to Brook Street South



Summary for Subcatchment PDA-500: Area Draining to Brook Street North


Runoff = 0.01 cfs @ 12.24 hrs, Volume= 139 cf, Depth= 0.41"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 10-yr Rainfall=5.71"

Area (sf)	CN	Description
* 45	98	Impervious, HSG A
3,975	39	>75% Grass cover, Good, HSG A
4,020	40	Weighted Average
3,975		98.88% Pervious Area
45		1.12% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.4	35	0.0300	0.17		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.1	18	0.6000	3.99		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
3.5	53	Total, Increased to minimum Tc = 5.0 min			

Subcatchment PDA-500: Area Draining to Brook Street North



Summary for Pond 1P: Underground Detention System

Inflow Area = 44,335 sf, 85.76% Impervious, Inflow Depth = 4.53" for 10-yr event
 Inflow = 5.61 cfs @ 12.03 hrs, Volume= 16,733 cf
 Outflow = 2.69 cfs @ 12.12 hrs, Volume= 11,099 cf, Atten= 52%, Lag= 5.6 min
 Discarded = 0.03 cfs @ 4.07 hrs, Volume= 2,635 cf
 Primary = 2.66 cfs @ 12.12 hrs, Volume= 8,464 cf

Routing by Stor-Ind method, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 Peak Elev= 100.40' @ 12.12 hrs Surf.Area= 3,095 sf Storage= 6,546 cf

Plug-Flow detention time= 244.3 min calculated for 11,099 cf (66% of inflow)
 Center-of-Mass det. time= 113.5 min (905.7 - 792.2)

Volume	Invert	Avail.Storage	Storage Description
#1A	96.98'	3,408 cf	34.75'W x 89.06'L x 4.00'H Field A 12,379 cf Overall - 3,859 cf Embedded = 8,520 cf x 40.0% Voids
#2A	97.98'	3,859 cf	ADS_StormTech SC-740 +Cap x 84 Inside #1 Effective Size= 44.6"W x 30.0"H => 6.45 sf x 7.12'L = 45.9 cf Overall Size= 51.0"W x 30.0"H x 7.56'L with 0.44' Overlap 84 Chambers in 7 Rows
		7,267 cf	Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	98.40'	18.0" Round Culvert L= 20.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 98.40' / 98.30' S= 0.0050 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 1.77 sf
#2	Device 1	100.05'	4.0' long Sharp-Crested Rectangular Weir 2 End Contraction(s)
#3	Discarded	96.98'	0.400 in/hr Exfiltration over Surface area

Discarded OutFlow Max=0.03 cfs @ 4.07 hrs HW=97.02' (Free Discharge)
 ↑**3=Exfiltration** (Exfiltration Controls 0.03 cfs)

Primary OutFlow Max=2.65 cfs @ 12.12 hrs HW=100.40' (Free Discharge)
 ↑**1=Culvert** (Passes 2.65 cfs of 8.05 cfs potential flow)
 ↑**2=Sharp-Crested Rectangular Weir**(Weir Controls 2.65 cfs @ 1.93 fps)

Pond 1P: Underground Detention System - Chamber Wizard Field A

Chamber Model = ADS_StormTechSC-740 +Cap (ADS StormTech®SC-740 with cap length)

Effective Size= 44.6"W x 30.0"H => 6.45 sf x 7.12'L = 45.9 cf

Overall Size= 51.0"W x 30.0"H x 7.56'L with 0.44' Overlap

51.0" Wide + 6.0" Spacing = 57.0" C-C Row Spacing

12 Chambers/Row x 7.12' Long +0.81' Cap Length x 2 = 87.06' Row Length +12.0" End Stone x 2 = 89.06' Base Length

7 Rows x 51.0" Wide + 6.0" Spacing x 6 + 12.0" Side Stone x 2 = 34.75' Base Width

12.0" Base + 30.0" Chamber Height + 6.0" Cover = 4.00' Field Height

84 Chambers x 45.9 cf = 3,859.0 cf Chamber Storage

12,378.9 cf Field - 3,859.0 cf Chambers = 8,519.9 cf Stone x 40.0% Voids = 3,408.0 cf Stone Storage

Chamber Storage + Stone Storage = 7,266.9 cf = 0.167 af


Overall Storage Efficiency = 58.7%

Overall System Size = 89.06' x 34.75' x 4.00'


84 Chambers

458.5 cy Field

315.6 cy Stone



Pond 1P: Underground Detention System




Summary for Link DP-1: Offsite West

Inflow Area = 63,655 sf, 61.80% Impervious, Inflow Depth = 1.77" for 10-yr event
Inflow = 2.75 cfs @ 12.12 hrs, Volume= 9,387 cf
Primary = 2.75 cfs @ 12.12 hrs, Volume= 9,387 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-1: Offsite West




Summary for Link DP-2: Grove Street South

Inflow Area = 34,990 sf, 70.66% Impervious, Inflow Depth = 3.62" for 10-yr event
Inflow = 3.25 cfs @ 12.06 hrs, Volume= 10,557 cf
Primary = 3.25 cfs @ 12.06 hrs, Volume= 10,557 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-2: Grove Street South




Summary for Link DP-3: Grove Street North

Inflow Area = 8,855 sf, 57.48% Impervious, Inflow Depth = 2.85" for 10-yr event
Inflow = 0.70 cfs @ 12.04 hrs, Volume= 2,103 cf
Primary = 0.70 cfs @ 12.04 hrs, Volume= 2,103 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-3: Grove Street North




Summary for Link DP-4: Brook Street South

Inflow Area = 10,875 sf, 36.28% Impervious, Inflow Depth = 1.73" for 10-yr event
Inflow = 0.52 cfs @ 12.03 hrs, Volume= 1,572 cf
Primary = 0.52 cfs @ 12.03 hrs, Volume= 1,572 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-4: Brook Street South




Summary for Link DP-5: Brook Street North

Inflow Area = 4,020 sf, 1.12% Impervious, Inflow Depth = 0.41" for 10-yr event
Inflow = 0.01 cfs @ 12.24 hrs, Volume= 139 cf
Primary = 0.01 cfs @ 12.24 hrs, Volume= 139 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-5: Brook Street North

Hydrograph




Summary for Link DP-6: Total Offsite Flow

Inflow Area = 122,395 sf, 59.76% Impervious, Inflow Depth = 2.33" for 10-yr event
 Inflow = 6.15 cfs @ 12.09 hrs, Volume= 23,757 cf
 Primary = 6.15 cfs @ 12.09 hrs, Volume= 23,757 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-6: Total Offsite Flow



Time span=0.00-28.00 hrs, dt=0.01 hrs, 2801 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

SubcatchmentPDA-100: Area Draining Runoff Area=19,320 sf 6.83% Impervious Runoff Depth=1.10"
Flow Length=50' Slope=0.0300 '/' Tc=5.0 min CN=43 Runoff=0.40 cfs 1,779 cf

SubcatchmentPDA-110: School Parking Runoff Area=14,030 sf 85.25% Impervious Runoff Depth=5.78"
Flow Length=181' Slope=0.0200 '/' Tc=5.5 min CN=89 Runoff=2.17 cfs 6,754 cf

SubcatchmentPDA-120: School Roof Runoff Area=10,425 sf 100.00% Impervious Runoff Depth=6.83"
Tc=5.0 min CN=98 Runoff=1.79 cfs 5,934 cf

SubcatchmentPDA-130: Church Parking Runoff Area=8,295 sf 84.63% Impervious Runoff Depth=5.78"
Flow Length=151' Tc=5.0 min CN=89 Runoff=1.32 cfs 3,993 cf

SubcatchmentPDA-140: Rectory Parking Runoff Area=11,585 sf 74.36% Impervious Runoff Depth=5.09"
Flow Length=64' Slope=0.0300 '/' Tc=5.0 min CN=83 Runoff=1.68 cfs 4,918 cf

SubcatchmentPDA-200: Area Draining to Runoff Area=34,990 sf 70.66% Impervious Runoff Depth=4.87"
Flow Length=447' Tc=7.6 min CN=81 Runoff=4.21 cfs 14,201 cf

SubcatchmentPDA-300: Area Draining to Runoff Area=8,855 sf 57.48% Impervious Runoff Depth=4.00"
Flow Length=93' Tc=6.1 min CN=73 Runoff=0.96 cfs 2,948 cf

SubcatchmentPDA-400: Area Draining to Runoff Area=10,875 sf 36.28% Impervious Runoff Depth=2.65"
Flow Length=62' Tc=5.0 min CN=60 Runoff=0.80 cfs 2,405 cf

SubcatchmentPDA-500: Area Draining to Runoff Area=4,020 sf 1.12% Impervious Runoff Depth=0.87"
Flow Length=53' Tc=5.0 min CN=40 Runoff=0.05 cfs 291 cf

Pond 1P: Underground Detention System Peak Elev=100.68' Storage=6,899 cf Inflow=6.95 cfs 21,599 cf
Discarded=0.03 cfs 2,704 cf Primary=6.38 cfs 13,258 cf Outflow=6.41 cfs 15,961 cf

Link DP-1: Offsite West Inflow=6.77 cfs 15,036 cf
Primary=6.77 cfs 15,036 cf

Link DP-2: Grove Street South Inflow=4.21 cfs 14,201 cf
Primary=4.21 cfs 14,201 cf

Link DP-3: Grove Street North Inflow=0.96 cfs 2,948 cf
Primary=0.96 cfs 2,948 cf

Link DP-4: Brook Street South Inflow=0.80 cfs 2,405 cf
Primary=0.80 cfs 2,405 cf

Link DP-5: Brook Street North Inflow=0.05 cfs 291 cf
Primary=0.05 cfs 291 cf

Link DP-6: Total Offsite Flow Inflow=12.71 cfs 34,881 cf
Primary=12.71 cfs 34,881 cf

Total Runoff Area = 122,395 sf Runoff Volume = 43,222 cf Average Runoff Depth = 4.24"
40.24% Pervious = 49,250 sf 59.76% Impervious = 73,145 sf

Summary for Subcatchment PDA-100: Area Draining Offsite to the West


Runoff = 0.40 cfs @ 12.04 hrs, Volume= 1,779 cf, Depth= 1.10"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 25-yr Rainfall=7.07"

Area (sf)	CN	Description
* 1,320	98	Impervious, HSG A
18,000	39	>75% Grass cover, Good, HSG A
19,320	43	Weighted Average
18,000		93.17% Pervious Area
1,320		6.83% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
4.6	50	0.0300	0.18		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
4.6	50	Total, Increased to minimum Tc = 5.0 min			

Subcatchment PDA-100: Area Draining Offsite to the West



Summary for Subcatchment PDA-110: School Parking Area to UDS

Runoff = 2.17 cfs @ 12.03 hrs, Volume= 6,754 cf, Depth= 5.78"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 25-yr Rainfall=7.07"

Area (sf)	CN	Description
* 11,960	98	Impervious, HSG A
2,070	39	>75% Grass cover, Good, HSG A
14,030	89	Weighted Average
2,070		14.75% Pervious Area
11,960		85.25% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
4.2	37	0.0200	0.15		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.8	63	0.0200	1.32		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
0.5	81	0.0200	2.87		Shallow Concentrated Flow, Paved Kv= 20.3 fps
5.5	181	Total			

Subcatchment PDA-110: School Parking Area to UDS

Hydrograph



Summary for Subcatchment PDA-120: School Roof Area to UDS


Runoff = 1.79 cfs @ 12.03 hrs, Volume= 5,934 cf, Depth= 6.83"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 25-yr Rainfall=7.07"

Area (sf)	CN	Description
* 10,425	98	Impervious, HSG A
10,425		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

Subcatchment PDA-120: School Roof Area to UDS



Summary for Subcatchment PDA-130: Church Parking Area to UDS

Runoff = 1.32 cfs @ 12.03 hrs, Volume= 3,993 cf, Depth= 5.78"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 25-yr Rainfall=7.07"

Area (sf)	CN	Description
* 7,020	98	Impervious, HSG A
1,275	39	>75% Grass cover, Good, HSG A
8,295	89	Weighted Average
1,275		15.37% Pervious Area
7,020		84.63% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.7	22	0.0100	0.10		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.8	78	0.0350	1.72		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
0.2	51	0.0350	3.80		Shallow Concentrated Flow, Paved Kv= 20.3 fps
4.7	151	Total, Increased to minimum Tc = 5.0 min			

Subcatchment PDA-130: Church Parking Area to UDS

Hydrograph



Summary for Subcatchment PDA-140: Rectory Parking Area to UDS


Runoff = 1.68 cfs @ 12.03 hrs, Volume= 4,918 cf, Depth= 5.09"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 25-yr Rainfall=7.07"

Area (sf)	CN	Description
* 8,615	98	Impervious, HSG A
2,970	39	>75% Grass cover, Good, HSG A
11,585	83	Weighted Average
2,970		25.64% Pervious Area
8,615		74.36% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.8	16	0.0300	0.15		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.5	48	0.0300	1.47		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
2.3	64	Total, Increased to minimum Tc = 5.0 min			

Subcatchment PDA-140: Rectory Parking Area to UDS



Summary for Subcatchment PDA-200: Area Draining to Grove Street South


Runoff = 4.21 cfs @ 12.05 hrs, Volume= 14,201 cf, Depth= 4.87"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 25-yr Rainfall=7.07"

Area (sf)	CN	Description
* 24,725	98	Impervious, HSG A
10,265	39	>75% Grass cover, Good, HSG A
34,990	81	Weighted Average
10,265		29.34% Pervious Area
24,725		70.66% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
4.7	30	0.0100	0.11		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.9	70	0.0200	1.34		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
2.0	347	0.0200	2.87		Shallow Concentrated Flow, Paved Kv= 20.3 fps
7.6	447	Total			

Subcatchment PDA-200: Area Draining to Grove Street South



Summary for Subcatchment PDA-300: Area Draining to Grove Street North


Runoff = 0.96 cfs @ 12.04 hrs, Volume= 2,948 cf, Depth= 4.00"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 25-yr Rainfall=7.07"

Area (sf)	CN	Description
* 5,090	98	Impervious, HSG A
3,765	39	>75% Grass cover, Good, HSG A
8,855	73	Weighted Average
3,765		42.52% Pervious Area
5,090		57.48% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.7	66	0.0300	0.19		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.4	27	0.0200	1.11		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
6.1	93	Total			

Subcatchment PDA-300: Area Draining to Grove Street North



Summary for Subcatchment PDA-400: Area Draining to Brook Street South


Runoff = 0.80 cfs @ 12.03 hrs, Volume= 2,405 cf, Depth= 2.65"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 25-yr Rainfall=7.07"

Area (sf)	CN	Description
3,945	98	Impervious, HSG A
6,930	39	>75% Grass cover, Good, HSG A
10,875	60	Weighted Average
6,930		63.72% Pervious Area
3,945		36.28% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.6	37	0.0300	0.17		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.1	25	0.4000	3.62		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
3.7	62	Total, Increased to minimum Tc = 5.0 min			

Subcatchment PDA-400: Area Draining to Brook Street South



Summary for Subcatchment PDA-500: Area Draining to Brook Street North


Runoff = 0.05 cfs @ 12.05 hrs, Volume= 291 cf, Depth= 0.87"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 25-yr Rainfall=7.07"

Area (sf)	CN	Description
* 45	98	Impervious, HSG A
3,975	39	>75% Grass cover, Good, HSG A
4,020	40	Weighted Average
3,975		98.88% Pervious Area
45		1.12% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.4	35	0.0300	0.17		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.1	18	0.6000	3.99		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
3.5	53	Total, Increased to minimum Tc = 5.0 min			

Subcatchment PDA-500: Area Draining to Brook Street North



Summary for Pond 1P: Underground Detention System

Inflow Area = 44,335 sf, 85.76% Impervious, Inflow Depth = 5.85" for 25-yr event
 Inflow = 6.95 cfs @ 12.03 hrs, Volume= 21,599 cf
 Outflow = 6.41 cfs @ 12.05 hrs, Volume= 15,961 cf, Atten= 8%, Lag= 1.3 min
 Discarded = 0.03 cfs @ 3.00 hrs, Volume= 2,704 cf
 Primary = 6.38 cfs @ 12.05 hrs, Volume= 13,258 cf

Routing by Stor-Ind method, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 Peak Elev= 100.68' @ 12.05 hrs Surf.Area= 3,095 sf Storage= 6,899 cf

Plug-Flow detention time= 212.1 min calculated for 15,961 cf (74% of inflow)
 Center-of-Mass det. time= 96.8 min (882.2 - 785.4)

Volume	Invert	Avail.Storage	Storage Description
#1A	96.98'	3,408 cf	34.75'W x 89.06'L x 4.00'H Field A 12,379 cf Overall - 3,859 cf Embedded = 8,520 cf x 40.0% Voids
#2A	97.98'	3,859 cf	ADS_StormTech SC-740 +Cap x 84 Inside #1 Effective Size= 44.6"W x 30.0"H => 6.45 sf x 7.12'L = 45.9 cf Overall Size= 51.0"W x 30.0"H x 7.56'L with 0.44' Overlap 84 Chambers in 7 Rows
		7,267 cf	Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	98.40'	18.0" Round Culvert L= 20.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 98.40' / 98.30' S= 0.0050 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 1.77 sf
#2	Device 1	100.05'	4.0' long Sharp-Crested Rectangular Weir 2 End Contraction(s)
#3	Discarded	96.98'	0.400 in/hr Exfiltration over Surface area

Discarded OutFlow Max=0.03 cfs @ 3.00 hrs HW=97.02' (Free Discharge)
 ↑**3=Exfiltration** (Exfiltration Controls 0.03 cfs)

Primary OutFlow Max=6.37 cfs @ 12.05 hrs HW=100.68' (Free Discharge)
 ↑**1=Culvert** (Passes 6.37 cfs of 9.75 cfs potential flow)
 ↑**2=Sharp-Crested Rectangular Weir**(Weir Controls 6.37 cfs @ 2.60 fps)

Pond 1P: Underground Detention System - Chamber Wizard Field A

Chamber Model = ADS_StormTechSC-740 +Cap (ADS StormTech®SC-740 with cap length)

Effective Size= 44.6"W x 30.0"H => 6.45 sf x 7.12'L = 45.9 cf

Overall Size= 51.0"W x 30.0"H x 7.56'L with 0.44' Overlap

51.0" Wide + 6.0" Spacing = 57.0" C-C Row Spacing

12 Chambers/Row x 7.12' Long +0.81' Cap Length x 2 = 87.06' Row Length +12.0" End Stone x 2 = 89.06' Base Length

7 Rows x 51.0" Wide + 6.0" Spacing x 6 + 12.0" Side Stone x 2 = 34.75' Base Width

12.0" Base + 30.0" Chamber Height + 6.0" Cover = 4.00' Field Height

84 Chambers x 45.9 cf = 3,859.0 cf Chamber Storage

12,378.9 cf Field - 3,859.0 cf Chambers = 8,519.9 cf Stone x 40.0% Voids = 3,408.0 cf Stone Storage

Chamber Storage + Stone Storage = 7,266.9 cf = 0.167 af


Overall Storage Efficiency = 58.7%

Overall System Size = 89.06' x 34.75' x 4.00'


84 Chambers

458.5 cy Field

315.6 cy Stone



Pond 1P: Underground Detention System




Summary for Link DP-1: Offsite West

Inflow Area = 63,655 sf, 61.80% Impervious, Inflow Depth = 2.83" for 25-yr event
Inflow = 6.77 cfs @ 12.05 hrs, Volume= 15,036 cf
Primary = 6.77 cfs @ 12.05 hrs, Volume= 15,036 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-1: Offsite West




Summary for Link DP-2: Grove Street South

Inflow Area = 34,990 sf, 70.66% Impervious, Inflow Depth = 4.87" for 25-yr event
Inflow = 4.21 cfs @ 12.05 hrs, Volume= 14,201 cf
Primary = 4.21 cfs @ 12.05 hrs, Volume= 14,201 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-2: Grove Street South




Summary for Link DP-3: Grove Street North

Inflow Area = 8,855 sf, 57.48% Impervious, Inflow Depth = 4.00" for 25-yr event
Inflow = 0.96 cfs @ 12.04 hrs, Volume= 2,948 cf
Primary = 0.96 cfs @ 12.04 hrs, Volume= 2,948 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-3: Grove Street North




Summary for Link DP-4: Brook Street South

Inflow Area = 10,875 sf, 36.28% Impervious, Inflow Depth = 2.65" for 25-yr event
Inflow = 0.80 cfs @ 12.03 hrs, Volume= 2,405 cf
Primary = 0.80 cfs @ 12.03 hrs, Volume= 2,405 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-4: Brook Street South




Summary for Link DP-5: Brook Street North

Inflow Area = 4,020 sf, 1.12% Impervious, Inflow Depth = 0.87" for 25-yr event
 Inflow = 0.05 cfs @ 12.05 hrs, Volume= 291 cf
 Primary = 0.05 cfs @ 12.05 hrs, Volume= 291 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-5: Brook Street North

Hydrograph




Summary for Link DP-6: Total Offsite Flow

Inflow Area = 122,395 sf, 59.76% Impervious, Inflow Depth = 3.42" for 25-yr event
Inflow = 12.71 cfs @ 12.05 hrs, Volume= 34,881 cf
Primary = 12.71 cfs @ 12.05 hrs, Volume= 34,881 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-6: Total Offsite Flow



Time span=0.00-28.00 hrs, dt=0.01 hrs, 2801 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

SubcatchmentPDA-100: Area Draining Runoff Area=19,320 sf 6.83% Impervious Runoff Depth=1.57"
Flow Length=50' Slope=0.0300 '/' Tc=5.0 min CN=43 Runoff=0.66 cfs 2,532 cf

SubcatchmentPDA-110: School Parking Runoff Area=14,030 sf 85.25% Impervious Runoff Depth=6.76"
Flow Length=181' Slope=0.0200 '/' Tc=5.5 min CN=89 Runoff=2.48 cfs 7,898 cf

SubcatchmentPDA-120: School Roof Runoff Area=10,425 sf 100.00% Impervious Runoff Depth=7.83"
Tc=5.0 min CN=98 Runoff=2.02 cfs 6,802 cf

SubcatchmentPDA-130: Church Parking Runoff Area=8,295 sf 84.63% Impervious Runoff Depth=6.76"
Flow Length=151' Tc=5.0 min CN=89 Runoff=1.51 cfs 4,670 cf

SubcatchmentPDA-140: Rectory Parking Runoff Area=11,585 sf 74.36% Impervious Runoff Depth=6.04"
Flow Length=64' Slope=0.0300 '/' Tc=5.0 min CN=83 Runoff=1.95 cfs 5,835 cf

SubcatchmentPDA-200: Area Draining to Runoff Area=34,990 sf 70.66% Impervious Runoff Depth=5.81"
Flow Length=447' Tc=7.6 min CN=81 Runoff=4.94 cfs 16,936 cf

SubcatchmentPDA-300: Area Draining to Runoff Area=8,855 sf 57.48% Impervious Runoff Depth=4.87"
Flow Length=93' Tc=6.1 min CN=73 Runoff=1.16 cfs 3,595 cf

SubcatchmentPDA-400: Area Draining to Runoff Area=10,875 sf 36.28% Impervious Runoff Depth=3.39"
Flow Length=62' Tc=5.0 min CN=60 Runoff=1.03 cfs 3,068 cf

SubcatchmentPDA-500: Area Draining to Runoff Area=4,020 sf 1.12% Impervious Runoff Depth=1.28"
Flow Length=53' Tc=5.0 min CN=40 Runoff=0.10 cfs 429 cf

Pond 1P: Underground Detention System Peak Elev=100.75' Storage=6,986 cf Inflow=7.96 cfs 25,206 cf
Discarded=0.03 cfs 2,735 cf Primary=7.45 cfs 16,831 cf Outflow=7.47 cfs 19,566 cf

Link DP-1: Offsite West Inflow=8.09 cfs 19,363 cf
Primary=8.09 cfs 19,363 cf

Link DP-2: Grove Street South Inflow=4.94 cfs 16,936 cf
Primary=4.94 cfs 16,936 cf

Link DP-3: Grove Street North Inflow=1.16 cfs 3,595 cf
Primary=1.16 cfs 3,595 cf

Link DP-4: Brook Street South Inflow=1.03 cfs 3,068 cf
Primary=1.03 cfs 3,068 cf

Link DP-5: Brook Street North Inflow=0.10 cfs 429 cf
Primary=0.10 cfs 429 cf

Link DP-6: Total Offsite Flow Inflow=15.21 cfs 43,392 cf
Primary=15.21 cfs 43,392 cf

Total Runoff Area = 122,395 sf Runoff Volume = 51,766 cf Average Runoff Depth = 5.08"
40.24% Pervious = 49,250 sf 59.76% Impervious = 73,145 sf

Summary for Subcatchment PDA-100: Area Draining Offsite to the West


Runoff = 0.66 cfs @ 12.04 hrs, Volume= 2,532 cf, Depth= 1.57"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 50-yr Rainfall=8.07"

Area (sf)	CN	Description
* 1,320	98	Impervious, HSG A
18,000	39	>75% Grass cover, Good, HSG A
19,320	43	Weighted Average
18,000		93.17% Pervious Area
1,320		6.83% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
4.6	50	0.0300	0.18		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
4.6	50	Total, Increased to minimum Tc = 5.0 min			

Subcatchment PDA-100: Area Draining Offsite to the West



Summary for Subcatchment PDA-110: School Parking Area to UDS


Runoff = 2.48 cfs @ 12.03 hrs, Volume= 7,898 cf, Depth= 6.76"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 50-yr Rainfall=8.07"

Area (sf)	CN	Description
* 11,960	98	Impervious, HSG A
2,070	39	>75% Grass cover, Good, HSG A
14,030	89	Weighted Average
2,070		14.75% Pervious Area
11,960		85.25% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
4.2	37	0.0200	0.15		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.8	63	0.0200	1.32		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
0.5	81	0.0200	2.87		Shallow Concentrated Flow, Paved Kv= 20.3 fps
5.5	181	Total			

Subcatchment PDA-110: School Parking Area to UDS



Summary for Subcatchment PDA-120: School Roof Area to UDS


Runoff = 2.02 cfs @ 12.03 hrs, Volume= 6,802 cf, Depth= 7.83"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 50-yr Rainfall=8.07"

Area (sf)	CN	Description
* 10,425	98	Impervious, HSG A
10,425		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

Subcatchment PDA-120: School Roof Area to UDS



Summary for Subcatchment PDA-130: Church Parking Area to UDS

Runoff = 1.51 cfs @ 12.03 hrs, Volume= 4,670 cf, Depth= 6.76"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 50-yr Rainfall=8.07"

Area (sf)	CN	Description
7,020	98	Impervious, HSG A
1,275	39	>75% Grass cover, Good, HSG A
8,295	89	Weighted Average
1,275		15.37% Pervious Area
7,020		84.63% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.7	22	0.0100	0.10		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.8	78	0.0350	1.72		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
0.2	51	0.0350	3.80		Shallow Concentrated Flow, Paved Kv= 20.3 fps
4.7	151	Total, Increased to minimum Tc = 5.0 min			

Subcatchment PDA-130: Church Parking Area to UDS

Hydrograph



Summary for Subcatchment PDA-140: Rectory Parking Area to UDS


Runoff = 1.95 cfs @ 12.03 hrs, Volume= 5,835 cf, Depth= 6.04"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 50-yr Rainfall=8.07"

Area (sf)	CN	Description
* 8,615	98	Impervious, HSG A
2,970	39	>75% Grass cover, Good, HSG A
11,585	83	Weighted Average
2,970		25.64% Pervious Area
8,615		74.36% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.8	16	0.0300	0.15		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.5	48	0.0300	1.47		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
2.3	64	Total, Increased to minimum Tc = 5.0 min			

Subcatchment PDA-140: Rectory Parking Area to UDS



Summary for Subcatchment PDA-200: Area Draining to Grove Street South


Runoff = 4.94 cfs @ 12.05 hrs, Volume= 16,936 cf, Depth= 5.81"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 50-yr Rainfall=8.07"

Area (sf)	CN	Description
24,725	98	Impervious, HSG A
10,265	39	>75% Grass cover, Good, HSG A
34,990	81	Weighted Average
10,265		29.34% Pervious Area
24,725		70.66% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
4.7	30	0.0100	0.11		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.9	70	0.0200	1.34		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
2.0	347	0.0200	2.87		Shallow Concentrated Flow, Paved Kv= 20.3 fps
7.6	447	Total			

Subcatchment PDA-200: Area Draining to Grove Street South



Summary for Subcatchment PDA-300: Area Draining to Grove Street North


Runoff = 1.16 cfs @ 12.04 hrs, Volume= 3,595 cf, Depth= 4.87"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 50-yr Rainfall=8.07"

Area (sf)	CN	Description
* 5,090	98	Impervious, HSG A
3,765	39	>75% Grass cover, Good, HSG A
8,855	73	Weighted Average
3,765		42.52% Pervious Area
5,090		57.48% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.7	66	0.0300	0.19		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.4	27	0.0200	1.11		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
6.1	93	Total			

Subcatchment PDA-300: Area Draining to Grove Street North



Summary for Subcatchment PDA-400: Area Draining to Brook Street South


Runoff = 1.03 cfs @ 12.03 hrs, Volume= 3,068 cf, Depth= 3.39"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 50-yr Rainfall=8.07"

Area (sf)	CN	Description
3,945	98	Impervious, HSG A
6,930	39	>75% Grass cover, Good, HSG A
10,875	60	Weighted Average
6,930		63.72% Pervious Area
3,945		36.28% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.6	37	0.0300	0.17		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.1	25	0.4000	3.62		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
3.7	62	Total, Increased to minimum Tc = 5.0 min			

Subcatchment PDA-400: Area Draining to Brook Street South



Summary for Subcatchment PDA-500: Area Draining to Brook Street North


Runoff = 0.10 cfs @ 12.04 hrs, Volume= 429 cf, Depth= 1.28"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 50-yr Rainfall=8.07"

Area (sf)	CN	Description
* 45	98	Impervious, HSG A
3,975	39	>75% Grass cover, Good, HSG A
4,020	40	Weighted Average
3,975		98.88% Pervious Area
45		1.12% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.4	35	0.0300	0.17		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.1	18	0.6000	3.99		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
3.5	53	Total, Increased to minimum Tc = 5.0 min			

Subcatchment PDA-500: Area Draining to Brook Street North



Summary for Pond 1P: Underground Detention System

Inflow Area = 44,335 sf, 85.76% Impervious, Inflow Depth = 6.82" for 50-yr event
 Inflow = 7.96 cfs @ 12.03 hrs, Volume= 25,206 cf
 Outflow = 7.47 cfs @ 12.05 hrs, Volume= 19,566 cf, Atten= 6%, Lag= 1.2 min
 Discarded = 0.03 cfs @ 2.49 hrs, Volume= 2,735 cf
 Primary = 7.45 cfs @ 12.05 hrs, Volume= 16,831 cf

Routing by Stor-Ind method, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 Peak Elev= 100.75' @ 12.05 hrs Surf.Area= 3,095 sf Storage= 6,986 cf

Plug-Flow detention time= 195.5 min calculated for 19,566 cf (78% of inflow)
 Center-of-Mass det. time= 90.2 min (871.4 - 781.2)

Volume	Invert	Avail.Storage	Storage Description
#1A	96.98'	3,408 cf	34.75"W x 89.06'L x 4.00'H Field A 12,379 cf Overall - 3,859 cf Embedded = 8,520 cf x 40.0% Voids
#2A	97.98'	3,859 cf	ADS_StormTech SC-740 +Cap x 84 Inside #1 Effective Size= 44.6"W x 30.0"H => 6.45 sf x 7.12'L = 45.9 cf Overall Size= 51.0"W x 30.0"H x 7.56'L with 0.44' Overlap 84 Chambers in 7 Rows
		7,267 cf	Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	98.40'	18.0" Round Culvert L= 20.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 98.40' / 98.30' S= 0.0050 '/' Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 1.77 sf
#2	Device 1	100.05'	4.0' long Sharp-Crested Rectangular Weir 2 End Contraction(s)
#3	Discarded	96.98'	0.400 in/hr Exfiltration over Surface area

Discarded OutFlow Max=0.03 cfs @ 2.49 hrs HW=97.02' (Free Discharge)
 ↑**3=Exfiltration** (Exfiltration Controls 0.03 cfs)

Primary OutFlow Max=7.42 cfs @ 12.05 hrs HW=100.75' (Free Discharge)
 ↑**1=Culvert** (Passes 7.42 cfs of 10.13 cfs potential flow)
 ↑**2=Sharp-Crested Rectangular Weir**(Weir Controls 7.42 cfs @ 2.74 fps)

Pond 1P: Underground Detention System - Chamber Wizard Field A

Chamber Model = ADS_StormTechSC-740 +Cap (ADS StormTech®SC-740 with cap length)

Effective Size= 44.6"W x 30.0"H => 6.45 sf x 7.12'L = 45.9 cf

Overall Size= 51.0"W x 30.0"H x 7.56'L with 0.44' Overlap

51.0" Wide + 6.0" Spacing = 57.0" C-C Row Spacing

12 Chambers/Row x 7.12' Long +0.81' Cap Length x 2 = 87.06' Row Length +12.0" End Stone x 2 = 89.06' Base Length

7 Rows x 51.0" Wide + 6.0" Spacing x 6 + 12.0" Side Stone x 2 = 34.75' Base Width

12.0" Base + 30.0" Chamber Height + 6.0" Cover = 4.00' Field Height

84 Chambers x 45.9 cf = 3,859.0 cf Chamber Storage


12,378.9 cf Field - 3,859.0 cf Chambers = 8,519.9 cf Stone x 40.0% Voids = 3,408.0 cf Stone Storage

Chamber Storage + Stone Storage = 7,266.9 cf = 0.167 af


Overall Storage Efficiency = 58.7%

Overall System Size = 89.06' x 34.75' x 4.00'

84 Chambers
458.5 cy Field
315.6 cy Stone



Pond 1P: Underground Detention System




Summary for Link DP-1: Offsite West

Inflow Area = 63,655 sf, 61.80% Impervious, Inflow Depth = 3.65" for 50-yr event
Inflow = 8.09 cfs @ 12.05 hrs, Volume= 19,363 cf
Primary = 8.09 cfs @ 12.05 hrs, Volume= 19,363 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-1: Offsite West




Summary for Link DP-2: Grove Street South

Inflow Area = 34,990 sf, 70.66% Impervious, Inflow Depth = 5.81" for 50-yr event
Inflow = 4.94 cfs @ 12.05 hrs, Volume= 16,936 cf
Primary = 4.94 cfs @ 12.05 hrs, Volume= 16,936 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-2: Grove Street South




Summary for Link DP-3: Grove Street North

Inflow Area = 8,855 sf, 57.48% Impervious, Inflow Depth = 4.87" for 50-yr event
Inflow = 1.16 cfs @ 12.04 hrs, Volume= 3,595 cf
Primary = 1.16 cfs @ 12.04 hrs, Volume= 3,595 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-3: Grove Street North




Summary for Link DP-4: Brook Street South

Inflow Area = 10,875 sf, 36.28% Impervious, Inflow Depth = 3.39" for 50-yr event
Inflow = 1.03 cfs @ 12.03 hrs, Volume= 3,068 cf
Primary = 1.03 cfs @ 12.03 hrs, Volume= 3,068 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-4: Brook Street South




Summary for Link DP-5: Brook Street North

Inflow Area = 4,020 sf, 1.12% Impervious, Inflow Depth = 1.28" for 50-yr event
 Inflow = 0.10 cfs @ 12.04 hrs, Volume= 429 cf
 Primary = 0.10 cfs @ 12.04 hrs, Volume= 429 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-5: Brook Street North

Hydrograph




Summary for Link DP-6: Total Offsite Flow

Inflow Area = 122,395 sf, 59.76% Impervious, Inflow Depth = 4.25" for 50-yr event
Inflow = 15.21 cfs @ 12.05 hrs, Volume= 43,392 cf
Primary = 15.21 cfs @ 12.05 hrs, Volume= 43,392 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-6: Total Offsite Flow



C-CALC-2202472-Proposed ConCT-Torrington-2202472-Depth 24-hr S1 100-yr Rainfall=9.18"

Prepared by BL Companies

Printed 4/14/2023

HydroCAD® 10.00-25 s/n 01334 © 2019 HydroCAD Software Solutions LLC

Page 122

Time span=0.00-28.00 hrs, dt=0.01 hrs, 2801 points
Runoff by SCS TR-20 method, UH=SCS, Weighted-CN
Reach routing by Stor-Ind+Trans method - Pond routing by Stor-Ind method

SubcatchmentPDA-100: Area Draining Runoff Area=19,320 sf 6.83% Impervious Runoff Depth=2.15"
Flow Length=50' Slope=0.0300 '/' Tc=5.0 min CN=43 Runoff=0.98 cfs 3,469 cf

SubcatchmentPDA-110: School Parking Runoff Area=14,030 sf 85.25% Impervious Runoff Depth=7.85"
Flow Length=181' Slope=0.0200 '/' Tc=5.5 min CN=89 Runoff=2.81 cfs 9,175 cf

SubcatchmentPDA-120: School Roof Runoff Area=10,425 sf 100.00% Impervious Runoff Depth=8.94"
Tc=5.0 min CN=98 Runoff=2.26 cfs 7,766 cf

SubcatchmentPDA-130: Church Parking Runoff Area=8,295 sf 84.63% Impervious Runoff Depth=7.85"
Flow Length=151' Tc=5.0 min CN=89 Runoff=1.71 cfs 5,424 cf

SubcatchmentPDA-140: Rectory Parking Runoff Area=11,585 sf 74.36% Impervious Runoff Depth=7.11"
Flow Length=64' Slope=0.0300 '/' Tc=5.0 min CN=83 Runoff=2.23 cfs 6,864 cf

SubcatchmentPDA-200: Area Draining to Runoff Area=34,990 sf 70.66% Impervious Runoff Depth=6.86"
Flow Length=447' Tc=7.6 min CN=81 Runoff=5.69 cfs 20,011 cf

SubcatchmentPDA-300: Area Draining to Runoff Area=8,855 sf 57.48% Impervious Runoff Depth=5.87"
Flow Length=93' Tc=6.1 min CN=73 Runoff=1.36 cfs 4,331 cf

SubcatchmentPDA-400: Area Draining to Runoff Area=10,875 sf 36.28% Impervious Runoff Depth=4.24"
Flow Length=62' Tc=5.0 min CN=60 Runoff=1.28 cfs 3,845 cf

SubcatchmentPDA-500: Area Draining to Runoff Area=4,020 sf 1.12% Impervious Runoff Depth=1.80"
Flow Length=53' Tc=5.0 min CN=40 Runoff=0.16 cfs 604 cf

Pond 1P: Underground Detention System Peak Elev=100.82' Storage=7,066 cf Inflow=9.00 cfs 29,229 cf
Discarded=0.03 cfs 2,760 cf Primary=8.46 cfs 20,827 cf Outflow=8.49 cfs 23,587 cf

Link DP-1: Offsite West Inflow=9.41 cfs 24,296 cf
Primary=9.41 cfs 24,296 cf

Link DP-2: Grove Street South Inflow=5.69 cfs 20,011 cf
Primary=5.69 cfs 20,011 cf

Link DP-3: Grove Street North Inflow=1.36 cfs 4,331 cf
Primary=1.36 cfs 4,331 cf

Link DP-4: Brook Street South Inflow=1.28 cfs 3,845 cf
Primary=1.28 cfs 3,845 cf

Link DP-5: Brook Street North Inflow=0.16 cfs 604 cf
Primary=0.16 cfs 604 cf

Link DP-6: Total Offsite Flow Inflow=17.77 cfs 53,086 cf
Primary=17.77 cfs 53,086 cf

Total Runoff Area = 122,395 sf Runoff Volume = 61,488 cf Average Runoff Depth = 6.03"
40.24% Pervious = 49,250 sf 59.76% Impervious = 73,145 sf

Summary for Subcatchment PDA-100: Area Draining Offsite to the West


Runoff = 0.98 cfs @ 12.03 hrs, Volume= 3,469 cf, Depth= 2.15"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 100-yr Rainfall=9.18"

Area (sf)	CN	Description
* 1,320	98	Impervious, HSG A
18,000	39	>75% Grass cover, Good, HSG A
19,320	43	Weighted Average
18,000		93.17% Pervious Area
1,320		6.83% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
4.6	50	0.0300	0.18		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
4.6	50	Total, Increased to minimum Tc = 5.0 min			

Subcatchment PDA-100: Area Draining Offsite to the West



Summary for Subcatchment PDA-110: School Parking Area to UDS

Runoff = 2.81 cfs @ 12.03 hrs, Volume= 9,175 cf, Depth= 7.85"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 100-yr Rainfall=9.18"

Area (sf)	CN	Description
* 11,960	98	Impervious, HSG A
2,070	39	>75% Grass cover, Good, HSG A
14,030	89	Weighted Average
2,070		14.75% Pervious Area
11,960		85.25% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
4.2	37	0.0200	0.15		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.8	63	0.0200	1.32		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
0.5	81	0.0200	2.87		Shallow Concentrated Flow, Paved Kv= 20.3 fps
5.5	181	Total			

Subcatchment PDA-110: School Parking Area to UDS

Hydrograph



Summary for Subcatchment PDA-120: School Roof Area to UDS


Runoff = 2.26 cfs @ 12.03 hrs, Volume= 7,766 cf, Depth= 8.94"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 100-yr Rainfall=9.18"

Area (sf)	CN	Description
* 10,425	98	Impervious, HSG A
10,425		100.00% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.0					Direct Entry,

Subcatchment PDA-120: School Roof Area to UDS



Summary for Subcatchment PDA-130: Church Parking Area to UDS

Runoff = 1.71 cfs @ 12.03 hrs, Volume= 5,424 cf, Depth= 7.85"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 100-yr Rainfall=9.18"

Area (sf)	CN	Description
* 7,020	98	Impervious, HSG A
1,275	39	>75% Grass cover, Good, HSG A
8,295	89	Weighted Average
1,275		15.37% Pervious Area
7,020		84.63% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.7	22	0.0100	0.10		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.8	78	0.0350	1.72		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
0.2	51	0.0350	3.80		Shallow Concentrated Flow, Paved Kv= 20.3 fps
4.7	151	Total, Increased to minimum Tc = 5.0 min			

Subcatchment PDA-130: Church Parking Area to UDS

Hydrograph



Summary for Subcatchment PDA-140: Rectory Parking Area to UDS


Runoff = 2.23 cfs @ 12.03 hrs, Volume= 6,864 cf, Depth= 7.11"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 100-yr Rainfall=9.18"

Area (sf)	CN	Description
* 8,615	98	Impervious, HSG A
2,970	39	>75% Grass cover, Good, HSG A
11,585	83	Weighted Average
2,970		25.64% Pervious Area
8,615		74.36% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
1.8	16	0.0300	0.15		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.5	48	0.0300	1.47		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
2.3	64	Total, Increased to minimum Tc = 5.0 min			

Subcatchment PDA-140: Rectory Parking Area to UDS



Summary for Subcatchment PDA-200: Area Draining to Grove Street South

Runoff = 5.69 cfs @ 12.05 hrs, Volume= 20,011 cf, Depth= 6.86"


Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 100-yr Rainfall=9.18"

Area (sf)	CN	Description
24,725	98	Impervious, HSG A
10,265	39	>75% Grass cover, Good, HSG A
34,990	81	Weighted Average
10,265		29.34% Pervious Area
24,725		70.66% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
4.7	30	0.0100	0.11		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.9	70	0.0200	1.34		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
2.0	347	0.0200	2.87		Shallow Concentrated Flow, Paved Kv= 20.3 fps
7.6	447	Total			

Subcatchment PDA-200: Area Draining to Grove Street South

Hydrograph



Summary for Subcatchment PDA-300: Area Draining to Grove Street North


Runoff = 1.36 cfs @ 12.04 hrs, Volume= 4,331 cf, Depth= 5.87"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 100-yr Rainfall=9.18"

Area (sf)	CN	Description
* 5,090	98	Impervious, HSG A
3,765	39	>75% Grass cover, Good, HSG A
8,855	73	Weighted Average
3,765		42.52% Pervious Area
5,090		57.48% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
5.7	66	0.0300	0.19		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.4	27	0.0200	1.11		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
6.1	93	Total			

Subcatchment PDA-300: Area Draining to Grove Street North



Summary for Subcatchment PDA-400: Area Draining to Brook Street South


Runoff = 1.28 cfs @ 12.03 hrs, Volume= 3,845 cf, Depth= 4.24"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 100-yr Rainfall=9.18"

Area (sf)	CN	Description
3,945	98	Impervious, HSG A
6,930	39	>75% Grass cover, Good, HSG A
10,875	60	Weighted Average
6,930		63.72% Pervious Area
3,945		36.28% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.6	37	0.0300	0.17		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.1	25	0.4000	3.62		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
3.7	62	Total, Increased to minimum Tc = 5.0 min			

Subcatchment PDA-400: Area Draining to Brook Street South



Summary for Subcatchment PDA-500: Area Draining to Brook Street North


Runoff = 0.16 cfs @ 12.04 hrs, Volume= 604 cf, Depth= 1.80"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 CT-Torrington-2202472-Depth 24-hr S1 100-yr Rainfall=9.18"

Area (sf)	CN	Description
* 45	98	Impervious, HSG A
3,975	39	>75% Grass cover, Good, HSG A
4,020	40	Weighted Average
3,975		98.88% Pervious Area
45		1.12% Impervious Area

Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description
3.4	35	0.0300	0.17		Sheet Flow, Grass: Short n= 0.150 P2= 3.52"
0.1	18	0.6000	3.99		Sheet Flow, Smooth surfaces n= 0.011 P2= 3.52"
3.5	53	Total, Increased to minimum Tc = 5.0 min			

Subcatchment PDA-500: Area Draining to Brook Street North



Summary for Pond 1P: Underground Detention System

Inflow Area = 44,335 sf, 85.76% Impervious, Inflow Depth = 7.91" for 100-yr event
 Inflow = 9.00 cfs @ 12.03 hrs, Volume= 29,229 cf
 Outflow = 8.49 cfs @ 12.05 hrs, Volume= 23,587 cf, Atten= 6%, Lag= 1.1 min
 Discarded = 0.03 cfs @ 2.06 hrs, Volume= 2,760 cf
 Primary = 8.46 cfs @ 12.05 hrs, Volume= 20,827 cf

Routing by Stor-Ind method, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs
 Peak Elev= 100.82' @ 12.05 hrs Surf.Area= 3,095 sf Storage= 7,066 cf

Plug-Flow detention time= 181.5 min calculated for 23,587 cf (81% of inflow)
 Center-of-Mass det. time= 85.4 min (862.7 - 777.2)

Volume	Invert	Avail.Storage	Storage Description
#1A	96.98'	3,408 cf	34.75"W x 89.06'L x 4.00'H Field A 12,379 cf Overall - 3,859 cf Embedded = 8,520 cf x 40.0% Voids
#2A	97.98'	3,859 cf	ADS_StormTech SC-740 +Cap x 84 Inside #1 Effective Size= 44.6"W x 30.0"H => 6.45 sf x 7.12'L = 45.9 cf Overall Size= 51.0"W x 30.0"H x 7.56'L with 0.44' Overlap 84 Chambers in 7 Rows
		7,267 cf	Total Available Storage

Storage Group A created with Chamber Wizard

Device	Routing	Invert	Outlet Devices
#1	Primary	98.40'	18.0" Round Culvert L= 20.0' CPP, square edge headwall, Ke= 0.500 Inlet / Outlet Invert= 98.40' / 98.30' S= 0.0050 '/ Cc= 0.900 n= 0.013 Corrugated PE, smooth interior, Flow Area= 1.77 sf
#2	Device 1	100.05'	4.0' long Sharp-Crested Rectangular Weir 2 End Contraction(s)
#3	Discarded	96.98'	0.400 in/hr Exfiltration over Surface area

Discarded OutFlow Max=0.03 cfs @ 2.06 hrs HW=97.02' (Free Discharge)
 ↑**3=Exfiltration** (Exfiltration Controls 0.03 cfs)

Primary OutFlow Max=8.43 cfs @ 12.05 hrs HW=100.82' (Free Discharge)
 ↑**1=Culvert** (Passes 8.43 cfs of 10.46 cfs potential flow)
 ↑**2=Sharp-Crested Rectangular Weir**(Weir Controls 8.43 cfs @ 2.86 fps)

Pond 1P: Underground Detention System - Chamber Wizard Field A

Chamber Model = ADS_StormTechSC-740 +Cap (ADS StormTech®SC-740 with cap length)

Effective Size= 44.6"W x 30.0"H => 6.45 sf x 7.12'L = 45.9 cf

Overall Size= 51.0"W x 30.0"H x 7.56'L with 0.44' Overlap

51.0" Wide + 6.0" Spacing = 57.0" C-C Row Spacing

12 Chambers/Row x 7.12' Long +0.81' Cap Length x 2 = 87.06' Row Length +12.0" End Stone x 2 = 89.06' Base Length

7 Rows x 51.0" Wide + 6.0" Spacing x 6 + 12.0" Side Stone x 2 = 34.75' Base Width

12.0" Base + 30.0" Chamber Height + 6.0" Cover = 4.00' Field Height

84 Chambers x 45.9 cf = 3,859.0 cf Chamber Storage


12,378.9 cf Field - 3,859.0 cf Chambers = 8,519.9 cf Stone x 40.0% Voids = 3,408.0 cf Stone Storage

Chamber Storage + Stone Storage = 7,266.9 cf = 0.167 af


Overall Storage Efficiency = 58.7%

Overall System Size = 89.06' x 34.75' x 4.00'

84 Chambers
458.5 cy Field
315.6 cy Stone



Pond 1P: Underground Detention System




Summary for Link DP-1: Offsite West

Inflow Area = 63,655 sf, 61.80% Impervious, Inflow Depth = 4.58" for 100-yr event
Inflow = 9.41 cfs @ 12.04 hrs, Volume= 24,296 cf
Primary = 9.41 cfs @ 12.04 hrs, Volume= 24,296 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-1: Offsite West




Summary for Link DP-2: Grove Street South

Inflow Area = 34,990 sf, 70.66% Impervious, Inflow Depth = 6.86" for 100-yr event
Inflow = 5.69 cfs @ 12.05 hrs, Volume= 20,011 cf
Primary = 5.69 cfs @ 12.05 hrs, Volume= 20,011 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-2: Grove Street South




Summary for Link DP-3: Grove Street North

Inflow Area = 8,855 sf, 57.48% Impervious, Inflow Depth = 5.87" for 100-yr event
Inflow = 1.36 cfs @ 12.04 hrs, Volume= 4,331 cf
Primary = 1.36 cfs @ 12.04 hrs, Volume= 4,331 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-3: Grove Street North




Summary for Link DP-4: Brook Street South

Inflow Area = 10,875 sf, 36.28% Impervious, Inflow Depth = 4.24" for 100-yr event
Inflow = 1.28 cfs @ 12.03 hrs, Volume= 3,845 cf
Primary = 1.28 cfs @ 12.03 hrs, Volume= 3,845 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-4: Brook Street South




Summary for Link DP-5: Brook Street North

Inflow Area = 4,020 sf, 1.12% Impervious, Inflow Depth = 1.80" for 100-yr event
Inflow = 0.16 cfs @ 12.04 hrs, Volume= 604 cf
Primary = 0.16 cfs @ 12.04 hrs, Volume= 604 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-5: Brook Street North




Summary for Link DP-6: Total Offsite Flow

Inflow Area = 122,395 sf, 59.76% Impervious, Inflow Depth = 5.20" for 100-yr event
Inflow = 17.77 cfs @ 12.04 hrs, Volume= 53,086 cf
Primary = 17.77 cfs @ 12.04 hrs, Volume= 53,086 cf, Atten= 0%, Lag= 0.0 min

Primary outflow = Inflow, Time Span= 0.00-28.00 hrs, dt= 0.01 hrs

Link DP-6: Total Offsite Flow



APPENDIX D

WATER QUALITY CALCULATIONS

CTDEEP Water Quality Volume Calculations

CTDEEP Water Quality Flow Calculations

CTDEEP Groundwater Recharge Calculations

HydroCAD WQV Stage Volume Table

CTDOT Hydrodynamic Separator Sizing

Treatment Train Efficiency Worksheet

Water Quality Calculations

Determine Water Quality Volume

From CT 2004 Stormwater Quality Manual, Section 7.4.1:

$$WQV = \frac{(1')(R)(A)}{12}$$

$$R = 0.05 + 0.009(I)$$

WQV = water quality volume (ac-ft)

R = volumetric runoff coefficient

I = percent impervious cover

A = site area in acres

Area	Total Area		Impervious Area		Impervious Cover	Volumetric Runoff Coefficient	Water Quality Volume (WQV)		Water Quality Volume Provided
	ac	ft ²	ac	ft ²			acre-feet	ft ³	
ID					%	R			ft ³
Site Area	2.323	101,208	1.223	53,280	52.65	0.524	0.101	4,400	6,011

Note: The provided Water Quality Volume for the Underground detention System was derived from the Stage Volume tables in HydroCAD as the volume below the first orifice elevation from Pond 1P: Underground Stormwater Detention System (100.05').

Water Quality Calculations

Determine Water Quality Flow

From CT 2004 Stormwater Quality Manual:

$$CN = \frac{1000}{\left[10 + 5P + 10Q - 10(Q^2 + 1.25QP)^{\frac{1}{2}} \right]}$$

$$Q = \frac{[WQV(acre - feet) \times [12(inches / foot)]]}{DrainageArea(acres)}$$

$$WQF = (q_u)(A)(Q)$$

CN = Runoff Curve Number

P = design precipitation, inches, (1" for water quality storm)

Q = runoff depth (in watershed inches)

T_c = time of concentration

I_a = Initial abstraction, inches, from Table 4-1, Chapter 4, TR-55

q_u = unit peak discharge,

WQF = water quality flow (cfs)

Structure		Total Area			Imp Area		Imp Cover	R	WQV	Q	P	CN	T _c		I _a	I _a /P	q _u *	WQF
		ft ²	ac	mi ²	ft ²	ac	%	-	acre-feet	in	in	-	mins	hours	in	-	cfs/mi ² /in	cfs
Isolator Row	Underground Detention System	25,830	0.593	0.0009	20,820	0.478	80.60	0.775	0.038	0.77	1.00	98	5.0	0.08	0.041	0.041	650	0.45
CB-10	Inlet Hydrodynamic separator	8,080	0.185	0.0003	6,775	0.156	83.85	0.805	0.012	0.78	1.00	98	5.0	0.08	0.041	0.041	650	0.15

* From Exhibit 4-III: Unit peak discharge (qu) for SCS type III rainfall distribution, Urban Hydrology for Small Watersheds (TR-55), USDS< SCS, June 1986.

Groundwater Recharge Volume Calculations

Groundwater Recharge Volume

From CT 2004 Stormwater Quality Manual:

$$GVR = \frac{(D)(A)(I)}{12}$$

GRV Groundwater Recharge Volume (ac-ft)
 D = Depth of Runoff to be Recharged (table 7-4)
 A = site area in acres
 I = impervious cover (decimal)

Total Site Area (AC)	Site Area by NRCS Hydrologic Soil Group				Impervious Cover by NRCS Hydrologic Soil Group				Site Imperviousness (Decimel) by NRCS Hydrologic Soil Group				GRV Required		Potential Recharge Pond Volumes Proposed	
	A	B	C	D	A	B	C	D	A	B	C	D	(ac-ft)	(cu ft)	(ac-ft)	(cu ft)
	2.32	2.323	0.000	0.000	0.000	1.223	0.000	0.000	0.000	0.53	0.00	0.00	0.00	0.061	2,664	0.138

Table from 2004 Connecticut Stormwater Quality Manual

NRCS Hydrologic Soil Group	Average Annual Recharge	Groundwater Recharge Depth (D)
A	18 inches/year	0.4 inches
B	12 inches/year	0.25 inches
C	6 inches/year	0.10 inches
D	3 inches/year	0 inches (waived)

Source: MADEP, 1997.
 NRCS – Natural Resources Conservation Service

More Conservative Groundwater Recharge Amounts used in Calculations

NRCS Hydrologic Soil	Groundwater Recharge
A	0.60
B	0.40
C	0.25
D	0.00

Stage-Area-Storage for Pond 1P: Underground Detention System

Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)	Elevation (feet)	Surface (sq-ft)	Storage (cubic-feet)
96.98	3,095	0	99.58	3,095	5,086
97.03	3,095	62	99.63	3,095	5,191
97.08	3,095	124	99.68	3,095	5,295
97.13	3,095	186	99.73	3,095	5,398
97.18	3,095	248	99.78	3,095	5,498
97.23	3,095	309	99.83	3,095	5,598
97.28	3,095	371	99.88	3,095	5,695
97.33	3,095	433	99.93	3,095	5,791
97.38	3,095	495	99.98	3,095	5,884
97.43	3,095	557	<u>100.03</u>	<u>3,095</u>	<u>5,976</u>
97.48	3,095	619	100.08	3,095	6,064
97.53	3,095	681	100.13	3,095	6,150
97.58	3,095	743	100.18	3,095	6,233
97.63	3,095	805	100.23	3,095	6,310
97.68	3,095	867	100.28	3,095	6,384
97.73	3,095	928	100.33	3,095	6,453
97.78	3,095	990	100.38	3,095	6,520
97.83	3,095	1,052	100.43	3,095	6,585
97.88	3,095	1,114	100.48	3,095	6,648
97.93	3,095	1,176	100.53	3,095	6,710
97.98	3,095	1,238	100.58	3,095	6,772
98.03	3,095	1,366	100.63	3,095	6,834
98.08	3,095	1,495	100.68	3,095	6,896
98.13	3,095	1,623	100.73	3,095	6,957
98.18	3,095	1,751	100.78	3,095	7,019
98.23	3,095	1,879	100.83	3,095	7,081
98.28	3,095	2,006	100.88	3,095	7,143
98.33	3,095	2,133	100.93	3,095	7,205
98.38	3,095	2,259	100.98	3,095	7,267
98.43	3,095	2,385			
98.48	3,095	2,511			
98.53	3,095	2,635			
98.58	3,095	2,760			
98.63	3,095	2,883			
98.68	3,095	3,006			
98.73	3,095	3,129			
98.78	3,095	3,250			
98.83	3,095	3,371			
98.88	3,095	3,492			
98.93	3,095	3,612			
98.98	3,095	3,731			
99.03	3,095	3,849			
99.08	3,095	3,966			
99.13	3,095	4,083			
99.18	3,095	4,198			
99.23	3,095	4,313			
99.28	3,095	4,426			
99.33	3,095	4,539			
99.38	3,095	4,650			
99.43	3,095	4,761			
99.48	3,095	4,870			
99.53	3,095	4,979			

WQV @ 100.05 =
6,011 CF

Exhibit 4-III Unit peak discharge (q_u) for NRCS (SCS) type III rainfall distribution




TABLE 2 - PERFORMANCE MATRIX FOR CONNDOT APPROVED HYDRODYNAMIC SEPARATORS

Maximum WQF (cfs)	Product Model								
	<i>Downstream Defender</i>	<i>Flogard</i>	<i>High Eff. CDS</i>	<i>Hydroguard</i>	<i>Stormceptor OSR</i>	<i>Stormceptor STC</i>	<i>Vortechs</i>	<i>Vortsentry</i>	<i>V2B1</i>
0.4	4-ft	DVS-36	2015-4G; 2015-4	HG 4	065	450	1000	VS30	2
0.5	4-ft	DVS-36	2015-4G; 2015-4	HG 4	065	900	1000	VS30	2
0.6	4-ft	DVS-36	2015-4G; 2015-4	HG 4	065	900	1000	VS40	2
0.7	4-ft	DVS-48	2015-4G; 2015-4	HG 4	140	900	1000	VS40	2
0.8	4-ft	DVS-48	2015-4G; 2015-4	HG 4	140	900	1000	VS40	2
0.9	4-ft	DVS-48	2015-4G; 2015-4	HG 4	140	1200	1000	VS40	3
1.0	4-ft	DVS-48	2015-4G; 2015-4	HG 4	140	1800	1000	VS40	3
1.1	4-ft	DVS-48	2015-4G; 2015-4	HG 4	140	1800	1000	VS40	4
1.2	6-ft	DVS-48	2015	HG 5	140	2400	1000	VS50	4
1.3	6-ft	DVS-60	2015	HG 5	140	2400	1000	VS50	4
1.4	6-ft	DVS-60	2015	HG 5	140	2400	2000	VS50	4
1.5	6-ft	DVS-60	2020	HG 5	140	2400	2000	VS50	6
1.6	6-ft	DVS-60	2020	HG 5	140	2400	2000	VS50	6
1.7	6-ft	DVS-60	2020	HG 5	250	2400	2000	VS50	6
1.8	6-ft	DVS-60	2020	HG 6	250	2400	2000	VS50	7
1.9	6-ft	DVS-60	2020	HG 6	250	3600	2000	VS60	7
2.0	6-ft	DVS-60	2020	HG 6	250	3600	2000	VS60	7
2.1	6-ft	DVS-60	2020	HG 6	250	3600	2000	VS60	9
2.2	6-ft	DVS-72	2025	HG 6	250	3600	2000	VS60	8
2.3	6-ft	DVS-72	3020, 3020-D	HG 6	250	3600	2000	VS60	8
2.4	6-ft	DVS-72	3035; 3035-D	HG 6	250	4800	2000	VS60	8
2.5	6-ft	DVS-72	3035; 3035-D	HG 6	250	4800	3000	VS60	10
2.6	6-ft	DVS-72	3035; 3035-D	HG 6	250	4800	3000	VS60	11
2.7	6-ft	DVS-72	3035; 3035-D	HG 7	250	4800	3000	VS60	11
2.8	6-ft	DVS-72	3035; 3035-D	HG 7	250	4800	3000	VS70	11
2.9	6-ft	DVS-72	3035; 3035-D	HG 7	250	4800	3000	VS70	12
3.0	6-ft	DVS-72	3035; 3035-D	HG 7	390	4800	3000	VS70	12

HDS
CB-10

Best Management Practice (BMP) Treatment Train Efficiency Worksheet

Prepared for:
 Sacred Heart EdAdvance
 95-104 Grove Street
 Torrington, Connecticut

Prepared by:
 BL Companies
 355 Research Parkway
 Meriden, CT

Date prepared:
 March 27, 2023

Overall Site Treatment Train Efficiency to Underground Detention System (Isolator Row)

Et=[1-(1-E1)(1-E2)(1-E3)(1-E4)(1-E?)]*100	BMP	BMP Description	Type of Treatment	Efficiency
				Rate %
	E1	Impervious Surface Sweeping***	secondary (conventional)	10
	E2	Deep Sump and Hooded Catch Basin	secondary (conventional)	25
	E3	Isolator Row**	Primary	80

Overall Treatment Train Efficiency (Et)= 87 % Total Suspended Solids (TSS) Removal

* 80% required per CT DEEP
 ** Manufacturer Claims 80% TSS Removal
 *** Schueler 1996 & EPA 1993

BMP	Type of Treatment	TSS Removal	Starting TSS	Amount	Remaining
		Rate	Load	Removed	Load
Impervious Surface Sweeping***	secondary (conventional)	0.10	1.00	0.10	0.90
Deep Sump and Hooded Catch Basin	secondary (conventional)	0.25	0.90	0.23	0.68
Isolator Row**	Primary	0.80	0.68	0.54	0.14

Overall Treatment Train Efficiency (%) 87

TSS Removal Rates (adapted from Schueler, 1996, & EPA, 1993)

BMP List	Design Rate	Range of Average TSS Removal Rates	Brief Design Requirements
Extended Detention Pond	70%	60-80%	Sediment forebay
Wet Pond (a)	70%	60-80%	Sediment forebay
Constructed Wetland (b)	80%	65-80%	Designed to infiltrate or retain
Water Quality Swale	70%	60-80%	Designed to infiltrate or retain
Infiltration Trench	80%	75-80%	Pretreatment critical
Infiltration Basin	80%	75-80% (predicted)	Pretreatment critical
Dry Well	80%	80% (predicted)	Roof-top runoff (uncontaminated only)
Sand Filter (c)	80%	80%	Pretreatment
Organic Filter (d)	80%	80%+	Pretreatment
Water Quality Inlet	25%	15-35% w/ cleanout	Off-line only; 0.1" minimum Water Quality Volume (WQV) storage
Sediment Trap (Forebay)	25%	25% w/ cleanout	Storm flows for 2-year event must not cause erosion; 0.1" minimum WQV storage
Drainage Channel	25%	25%	Check dams; non-erosive for 2-yr.
Deep Sump and Hooded Catch Basin	25%	25% w/ cleanout	Deep sump general rule = 4 x pipe diameter or 4.0' for pipes 18" or less
Street Sweeping	10%	10%	Discretionary non-structural credit, must be part of approved plan

Best Management Practice (BMP) Treatment Train Efficiency Worksheet

Prepared for:
 Sacred Heart EdAdvance
 95-104 Grove Street
 Torrington, Connecticut

Prepared by:
 BL Companies
 355 Research Parkway
 Meriden, CT

Date prepared:
 March 27, 2023

Overall Site Treatment Train Efficiency to Underground Detention System (HDS)

Et=[1-(1-E1)(1-E2)(1-E3)(1-E4)(1-E?)]*100	BMP	BMP Description	Type of Treatment	Efficiency
				Rate %
	E1	Impervious Surface Sweeping***	secondary (conventional)	10
	E2	Deep Sump and Hooded Catch Basin	secondary (conventional)	25
	E3	Hydrodynamic Separator**	Primary	80

Overall Treatment Train Efficiency (Et)= **87 % Total Suspended Solids (TSS) Removal**

* 80% required per CT DEEP
 ** Manufacturer Claims 80% TSS Removal
 *** Schueler 1996 & EPA 1993

BMP	Type of Treatment	TSS Removal	Starting TSS	Amount	Remaining
		Rate	Load	Removed	Load
Impervious Surface Sweeping***	secondary (conventional)	0.10	1.00	0.10	0.90
Deep Sump and Hooded Catch Basin	secondary (conventional)	0.25	0.90	0.23	0.68
Hydrodynamic Separator**	Primary	0.80	0.68	0.54	0.14

Overall Treatment Train Efficiency (%) **87**

TSS Removal Rates (adapted from Schueler, 1996, & EPA, 1993)

BMP List	Design Rate	Range of Average TSS Removal Rates	Brief Design Requirements
Extended Detention Pond	70%	60-80%	Sediment forebay
Wet Pond (a)	70%	60-80%	Sediment forebay
Constructed Wetland (b)	80%	65-80%	Designed to infiltrate or retain
Water Quality Swale	70%	60-80%	Designed to infiltrate or retain
Infiltration Trench	80%	75-80%	Pretreatment critical
Infiltration Basin	80%	75-80% (predicted)	Pretreatment critical
Dry Well	80%	80% (predicted)	Roof-top runoff (uncontaminated only)
Sand Filter (c)	80%	80%	Pretreatment
Organic Filter (d)	80%	80%+	Pretreatment
Water Quality Inlet	25%	15-35% w/ cleanout	Off-line only; 0.1" minimum Water Quality Volume (WQV) storage
Sediment Trap (Forebay)	25%	25% w/ cleanout	Storm flows for 2-year event must not cause erosion; 0.1" minimum WQV storage
Drainage Channel	25%	25%	Check dams; non-erosive for 2-yr.
Deep Sump and Hooded Catch Basin	25%	25% w/ cleanout	Deep sump general rule = 4 x pipe diameter or 4.0' for pipes 18" or less
Street Sweeping	10%	10%	Discretionary non-structural credit, must be part of approved plan

APPENDIX E






DRAINAGE MAPS



- ED-1 – Existing Drainage Map
- PD-1 – Proposed Drainage Map
- GD-1 – Grading and Drainage Plan

EXISTING HYDROLOGY INFORMATION

DRAINAGE AREA	TOTAL AREA (S.F.)	IMPERVIOUS AREA (S.F.)	PERVIOUS AREA (S.F.)	PERCENT IMPERVIOUS (%)	CN	TIME OF CONCENTRATION (MIN.)
EDA-10	12,270	1,575	10,695	12.8%	55	5.0
EDA-20	67,225	54,565	12,660	81.2%	89	7.1
EDA-30	9,035	4,980	4,055	55.1%	76	6.1
EDA-40	22,400	8,130	14,270	36.3%	67	5.0
EDA-50	11,465	1,985	9,480	17.3%	57	5.0

HYDROLOGY LEGEND

- PROPERTY LINE 
- DRAINAGE AREA BOUNDARY 
- TIME OF CONCENTRATION ROUTE 
- DESIGN POINT **DP-X** 
- HINCKLEY-URBAN LAND COMPLEX SOIL, 3 TO 15 PERCENT SLOPES **238C** 



PROPOSED EDADVANCE BUILDING
95-104 GROVE STREET
TORRINGTON, CONNECTICUT

Designed C.J.L.
Drawn C.J.L.
Reviewed R.M.R.
Scale 1"=50'
Project 2202472
Date 03/31/2023





EXISTING DRAINAGE MAPPING



ED-1

PROPOSED HYDROLOGY INFORMATION

DRAINAGE AREA	TOTAL AREA (S.F.)	IMPERVIOUS AREA (S.F.)	PERVIOUS AREA (S.F.)	PERCENT IMPERVIOUS (%)	CN	TIME OF CONCENTRATION (MIN.)
PDA-100	19,320	1,320	18,000	6.8%	43	5.0
PDA-110	14,030	11,960	2,070	85.2%	89	5.5
PDA-120	10,425	10,425	0	100.0%	98	5.0
PDA-130	8,295	7,020	1,275	84.6%	89	5.0
PDA-140	11,585	8,615	2,970	74.4%	83	5.0
PDA-200	34,990	24,725	10,265	70.7%	81	7.6
PDA-300	8,855	5,090	3,765	57.5%	73	6.1
PDA-400	10,875	3,945	6,930	36.3%	60	5.0
PDA-500	4,020	45	3,975	1.1%	40	5.0

HYDROLOGY LEGEND

- PROPERTY LINE 
- DRAINAGE AREA BOUNDARY 
- TIME OF CONCENTRATION ROUTE 
- DESIGN POINT **DP-X** 
- HINCKLEY-URBAN LAND COMPLEX SOIL, 3 TO 15 PERCENT SLOPES **238C** 
















PROPOSED EDADVANCE BUILDING
95-104 GROVE STREET
TORRINGTON, CONNECTICUT

Designed C.J.L.
Drawn C.J.L.
Reviewed R.M.R.
Scale 1"=50'
Project 2202472
Date 04/14/2023

PROPOSED DRAINAGE MAPPING

PD-1

GRADING AND DRAINAGE LEGEND

-  PROPERTY LINE
-  PROPOSED LIMIT OF DISTURBANCE LINE AND CONTRACT LIMIT LINE
-  PROPOSED SAWCUT LINE
-  PROVIDE AND INSTALL STORM PIPE
-  PROPOSED ELEVATION CONTOUR (1' INTERVAL)
-  EXISTING ELEVATION CONTOUR (2' INTERVAL)
-  PROVIDE AND INSTALL CURBLESS TYPE CATCH BASIN (TYPE C-L)
-  PROVIDE AND INSTALL CURB TYPE CATCH BASIN (TYPE C)
-  PROVIDE AND INSTALL YARD DRAIN
-  PROVIDE AND INSTALL DRAINAGE MANHOLE
-  PROPOSED SPOT GRADE
-  SPOT GRADE ABBREVIATIONS:
 BC BOTTOM OF CURB
 TC TOP OF CURB
 BS BOTTOM OF STEP
 TS TOP OF STEP
 BL BOTTOM OF LIP
 TL TOP OF LIP
 BW BOTTOM OF WALL
 TW TOP OF WALL
 MEX MEET EXISTING CONDITION
-  PROVIDE AND INSTALL RIPRAP OR CRUSHED STONE



PROPOSED EDADVANCE BUILDING
95-104 GROVE STREET
TORRINGTON, CONNECTICUT


Disc. REVISIONS PER CITY STAFF COMMENTS
REVISED PER CITY STAFF COMMENTS

No.	Date	By
1.	3/27/2023	
2.	4/14/2023	


Designed C.J.L.
Drawn C.J.L.
Reviewed
Scale 1"=30'
Project No. 2202472
Date 03/10/2023
CAD File: GD220247201

GRADING AND DRAINAGE PLAN

Sheet No.



FOR PERMITTING PURPOSES ONLY
NOT RELEASED FOR CONSTRUCTION



4/11/2023, C:\HEUR\A\C\108220247201\GD220247201.DWG (GD-1) (A) (30X)

Sheet No.: GD220247201; Project No.: 220247201; Date: 03/10/2023; Scale: 1"=30'; Drawn: C.J.L.; Designed: C.J.L.



An Employee-Owned Company
Stormwater Management Report

APPENDIX F
STORMWATER SYSTEM
OPERATION AND MAINTENANCE MANUAL

Appendix F:

**Stormwater System
Operations and Maintenance Plan**

For the Proposed:
EdAdvance Building

Located at:
95-104 Grove Street
Torrington, Connecticut

Prepared for Submission to:
City of Torrington, Connecticut

March 31, 2023

Prepared for:
A. Secondino & Son, Inc.
PO Box 622 / 21 Acorn Road
Branford, CT 06405

Prepared by:



BL Companies
100 Constitution Plaza, 10th Floor
Hartford, Connecticut 06103
Phone: (860) 249-2200
Fax: (860) 249-2400

BL Project Number: 2202472

Table of Contents

GENERAL OVERVIEW	2
PURPOSE & GOALS	2
RESPONSIBLE PARTIES	2
LIST OF PERMITS & SPECIAL CONDITIONS	3
MAINTENANCE LOGS AND CHECKLISTS.....	3
FORMS	3
EMPLOYEE TRAINING.....	3
SPILL CONTROL	3
STORM WATER MANAGEMENT	4
SYSTEM COMPONENTS.....	4
CATCH BASINS AND MANHOLES	4
ISOLATOR ROW AND UNDERGROUND DETENTION SYSTEM	5
HYDRODYNAMIC SEPARATOR (OR APPROVED EQUAL).....	5
LEVEL SPREADER.....	5
SITE MAINTENANCE	5
PARKING LOTS.....	5
LANDSCAPING.....	6
OUTDOOR STORAGE.....	6
DEICING AND SNOW REMOVAL & STORAGE.....	6

General Overview

The project parcel, located at 95-104 Grove Street, is approximately 1.29 acres in size and is currently developed with an existing convent building and was the previous location of a school building demolished within the past decade. The existing Lot 2 is approximately 0.97 acres in size and is currently developed with the Sacred Heart Church building and rectory. The proposed EdAdvance school development is to be constructed on Lot 1, while work on Lot 2 consists of reconfiguration of existing parking areas. The properties are situated with Lot 1 on the western side of Grove Street and Lot 2 on the eastern side. Lot 2 is also bordered by Brook Street to the east. The parcels are bordered by residential properties on all sides. The East Branch Naugatuck River runs from north to south off Lot 1's western boundary.

The project parcels are located at a high point in elevation of Grove Street. In general, the existing topography Grove Street slopes from high point down to the north and south from approximately elevation 591' at the high point to 519' at the northern extent and 583' in the southern extent. Slopes on Lot 1 vary from approximately 2-3% along Grove Street to approximately 25% at the embankment drop-off to the west. Slopes on Lot 2 vary from 2-6% along Grove Street to approximately 67% at the embankment drop-off to Brook Street in the east. Several retaining walls exist on Lot 2 along the boundary with Brook Street supporting Lot 2 above Brook Street elevation.

Proposed site improvements include a ±10,300 square foot school building with paved parking areas and driveways, landscaped areas, pedestrian sidewalks, site utilities and lighting, and stormwater management system upgrades. The proposed stormwater management system is designed to be in compliance with the 2002 State of Connecticut Guidelines for Soil Erosion and Sediment Control, and the 2004 State of Connecticut Stormwater Quality Manual.

The following Operations and Maintenance Plan was prepared specifically for this proposed development in the City of Torrington, Connecticut. The Plan was developed to satisfy the requirements of the Connecticut Department of Energy and Environmental Protection's 2002 Connecticut Guidelines for Soil Erosion and Sediment Control.

Purpose & Goals

The purpose of this Manual is to ensure that the stormwater management components are operated in accordance with all approvals and permits. The primary goal is to inform all the property managers about how the system operates and what maintenance items are necessary to protect downstream wetlands and watercourses. The secondary goal is to provide a practical, efficient means of maintenance planning and record keeping to verify permit compliance.

Responsible Parties

The Property Owner will be responsible for implementing the Plan on the property.

Maintenance inspections shall be performed by a qualified professional.

Some utilities located on the site will be owned and maintained by various utility companies in accordance with their standards. The property owner may maintain the service connections.

List of Permits & Special Conditions

The project will receive several permits, which may contain special conditions that require compliance by the property owner and maintenance contractors. This permit may include the following:

- City of Torrington – Wetlands Permit, Site Plan Permit, Demolition Permit, and Building Permit

Maintenance Logs and Checklists

The property owner will keep a record of all maintenance procedures performed, date of inspection/ cleanings, etc. Copies of inspection reports and maintenance records shall be kept on-site.

Forms

The following forms will be developed for annual maintenance. Copies of the forms will be kept on-site as part of the Storm Water Management Plan.

- Annual Checklist
- Quarterly Checklist
- Monthly Checklist

Employee Training

The property owner will have an employee-training program, with annual up-dates, to ensure that the qualified employees charged with maintaining the buildings and grounds do so in accordance with the approved permit conditions. All employees that have maintenance duties will be adequately informed of their responsibilities.

Spill Control

In addition to the good housekeeping and material management practices discussed in the previous sections of this plan, the following practices will be followed for spill prevention and clean-up:

- Manufacturer's recommended methods for spill clean-up will be clearly posted and site personnel will be made aware of the procedures and the location of the information and clean-up supplies.

- Materials and equipment necessary for spill clean-up will be kept in the material storage area on-site. Equipment and materials will include but not be limited to: absorbent booms or mats, brooms, dust pans, mops, rags, gloves, goggles, sand, and plastic and metal trash containers specifically for this purpose.
- All spills will be cleaned immediately after discovery.
- The spill area will be kept well-ventilated and personnel will wear appropriate protective clothing to prevent injury from contact with hazardous substance.
- Spills of toxic or hazardous material, regardless of size, will be reported to the appropriate State or local government agency.
- If a spill occurs, this plan will be adjusted to include measures to prevent this type of spill from reoccurring and how to clean the spill if there is another one. A description of the spill, the cause, and the remediation measures will also be included.

A spill report shall be prepared by the property owner following each occurrence. The spill report shall present a description of the release, including quantity and type of material, date of spill, circumstances leading to the release, location of spill, response actions and personnel, documentation of notifications and corrective measures implemented to prevent reoccurrence.

The property owner shall identify an appropriately qualified and trained site employee involved with day-to-day site operations to be the spill prevention and clean-up coordinator. The name(s) of responsible spill personnel shall be posted on-site. Each employee shall be instructed that all spills are to be reported to the spill prevention and clean-up coordinator.

Storm Water Management

System Components

The storm water management system has several components that are shown on the Grading and Drainage Plan (GD-1), that performs various functions in treating storm water runoff:

Catch Basins and Manholes

The property owner is responsible for cleaning the catch basins and manholes on the property. A Connecticut Licensed hauler shall clean the sumps and dispose of removed sand legally. The road sand may be reused for winter sanding but may not be stored on-site. As part of the hauling contract, the hauler shall notify the property owner in writing where the material is being disposed.

Each catch basin shall be inspected every four months, with one inspection occurring during the month of April. Any debris occurring within one foot from the bottom of each sump shall be removed by Vacuum "Vactor" type of maintenance equipment.

During the inspection of each of the catch basin sumps, the hoods (where provided) on each of the outlet pipes shall also be observed for trash accumulation as well as overall condition. In the event that a hood is damaged or off the hanger, it shall be reset or repaired.

Isolator Row and Underground Detention System

The underground detention system and Isolator Row shall be inspected every six months in the months of April and September. Each of the inspection ports provided shall be opened and visually checked from the surface. Observation of grit inside of the detention system shall be noted and any deposits found to be 2 inches or more, as measured from the invert of pipe, shall be cleaned and removed. The underground detention system qualifies as a Confined Space under OSHA regulations, and any maintenance involving entry into the pipes should comply with OSHA Confined Space Entry Regulations.

Hydrodynamic Separator (or Approved Equal)

The hydrodynamic separator shall be cleaned periodically during construction, with one cleaning and inspection occurring at the end of construction after landscaped areas are fully stabilized.

For the first year of operation following construction, inspect each structure once each month during January, February, March, and April, and once every four months thereafter. A graduated measuring device (stadia rod) shall be inserted into each grit chamber and measurements of any accumulations shall be recorded. Any debris, which has accumulated to within one foot of the water surface inside the grit chamber portion of each tank, shall be removed by vacuum "Vactor" type equipment.

After the first year of operation, each structure shall be inspected at a minimum, three times yearly with one inspection occurring in the month of April in the same manner as described above for the first season of operation. Any accumulations found to be occurring within one foot of the water surface shall be removed from the structure and properly disposed off-site. Also, any floating material discovered during inspections shall be removed from the tank.

Level Spreader

Catch basins draining to the level spreader, including the level spreader junction catch basin, level spreader stone trench and curbing, and the area downstream from the level spreader shall be inspected for clogging, density of vegetation, damage by foot or vehicular traffic, excessive accumulations, and channelization. Inspections shall be made on a quarterly basis for the first two years following installation, and then on a semiannual basis thereafter. Inspections shall be performed after every storm event greater than 1-inch.

Catch basins draining to level spreaders shall be cleaned when sediment accumulation reaches a depth of 1', or on a minimum annual basis. Sediment and debris shall be removed from downstream areas on a minimum semiannual basis or whenever buildup is observed. Regrading and reseeded may be necessary to perform the maintenance procedure.

Site Maintenance

Parking Lots

Parking lots and sidewalks shall be swept as necessary by the property owner, or at least once per year, to clean sediment, trash, and other debris. The property owner will sweep parking lots on the property in the spring to remove winter accumulations of road sand.

Landscaping

The management company retained by the property owner will maintain landscaped areas. Normally the landscaping maintenance will consist of pruning, mulching, planting, mowing lawns, raking leaves, etc. Use of fertilizers and pesticides will be controlled and limited to minimal amounts necessary for healthy landscape maintenance.

The lawn areas, once established, will be maintained at a typical height of 3 ½". This will allow the grass to be maintained with minimal impact from weeds and/or pests. The low-maintenance areas will be maintained as a meadow or allowed to revert back to natural conditions. Topsoil, brush, leaves, clippings, woodchips, mulch, equipment, and other material shall be stored off site.

Outdoor Storage

There will be no outdoor storage of hazardous chemicals, de-icing agents, fertilizer, pesticides, or herbicides anywhere around the buildings.

Deicing and Snow Removal & Storage

The use of clean sand may be used to aid traction in conjunction with salt and/or chemicals for deicing, snow melting and other related winter weather management. Snow shall be shoveled and plowed from sidewalk and parking areas as soon as practical during and after winter storms. Sand accumulation shall be removed from the site at the end of the winter season or appropriate time when seasonal snow has melted. Alternative deicing methods must be submitted prior to use onsite for review to the City of Torrington for approval.

MAINTENANCE SCHEDULE

During the First Year of Operation:		
Task:	Completion Date:	Manager's Initials:
JANUARY:		
Employee Training Program with Spill Program		
*Catch Basin Inspection		
*Isolator Row and Subsurface Stormwater Detention		
*Hydrodynamic Separator Inspection		
Level Spreader Inspection		
FEBRUARY:		
*Isolator Row and Subsurface Stormwater Detention		
*Hydrodynamic Separator Inspection		
MARCH:		
*Isolator Row and Subsurface Stormwater Detention		
*Hydrodynamic Separator Inspection		
APRIL:		
*Catch Basin Inspection		
*Isolator Row and Subsurface Stormwater Detention		
*Hydrodynamic Separator Inspection		
Level Spreader Inspection		
Sweeping of Paved Surfaces		
Shrub Fertilization		
Lawn Liming (if necessary)		
JUNE:		
*Catch Basin Inspection		
Sweeping of Paved Surfaces		
SEPTEMBER:		
*Isolator Row and Subsurface Stormwater Detention		
Level Spreader Inspection		
Sweeping of Paved Surfaces		
Tree and Lawn Fertilization		
DECEMBER:		
*Catch Basin Inspection		
*Isolator Row and Subsurface Stormwater Detention		
Level Spreader Inspection		
Sweeping of Paved Surfaces		

*NOTE: Use appropriate worksheet found in this plan to conduct the inspection.

After the First Year of Operation:

FOR YEAR _____

Task:		Completion Date:	Manager's Initials:
JANUARY:			
Employee Training Program with Spill Program			
APRIL:			
*Catch Basin Inspection			
*Isolator Row and Subsurface Stormwater Detention			
*Hydrodynamic Separator Inspection			
Level Spreader Inspection			
Sweeping of Paved Surfaces			
Shrub Fertilization			
Lawn Liming (if necessary)			
JUNE:			
*Catch Basin Inspection			
Sweeping of Paved Surfaces			
SEPTEMBER:			
*Isolator Row and Subsurface Stormwater Detention			
*Hydrodynamic Separator Inspection			
Level Spreader Inspection			
Sweeping of Paved Surfaces			
Tree and Lawn Fertilization			
DECEMBER:			
*Catch Basin Inspection			
*Hydrodynamic Separator Inspection			
Sweeping of Paved Surfaces			

*NOTE: Use appropriate worksheet found in this plan to conduct the inspection.

CATCH BASIN / CATCH BASIN INSERT / HDS INSPECTION LOG

Name of Inspector:

Date:

Catch Basin ID	Condition (circle one)		Debris above 1' within sump? (If yes then catch basin is to be cleaned)		Date of Catch Basin/Cleaning (if debris is greater than 1')		Condition of Hood (if applicable, remove trash/debris if necessary)	Comments:
	Excellent							
	Fair	Poor	Yes	No	Yes	No		
	Excellent							
	Fair	Poor	Yes	No	Yes	No		
	Excellent							
	Fair	Poor	Yes	No	Yes	No		
	Excellent							
	Fair	Poor	Yes	No	Yes	No		
	Excellent							
	Fair	Poor	Yes	No	Yes	No		
	Excellent							
	Fair	Poor	Yes	No	Yes	No		
	Excellent							
	Fair	Poor	Yes	No	Yes	No		
	Excellent							


On-site Procedures for Inspection and Maintenance of Catch Basin Inserts

- Secure traffic and pedestrian traffic with cones, barrels, etc.
- Clean surface area around each catch basin.
- Remove grates and set aside
- Clean grates, remove litter and debris that may be trapped within the grate
- Visually inspect condition of outlet hood and remove trash and debris from hood if necessary.
- Remove by vacator hose the debris that has been trapped in the trough area. Dispose of in accordance with local, state and federal regulatory agency requirements. Most debris that is captured in the trough or sump area will fall into the non-hazardous waste category.
- Visually inspect and check the condition of the trough area.
- Replace grate and lockdown as needed.
- Un-secure traffic control area.
- Complete service report and submit to facility owner.

StormTech and Stormwater Quality

StormTech's patented Isolator™ Row is a row of chambers wrapped in a geotextile which filters the stormwater trapping pollutants in the row. The Isolator Row provides a way to inspect and maintain the system.

Isolator Row Detail



Note: For many applications, the non-woven geotextile over the DC-780, MC-3500 and MC-4500 Isolator Row chambers can be eliminated or substituted with the AASHTO Class 1 woven geotextile. Contact your StormTech representative for assistance.

Isolator Row Field Verification Testing at the University of New Hampshire Stormwater Center

- Field testing (TARP tier II protocol) of the Isolator Row has been ongoing since December 2006.
- Removal efficiencies for TSS have improved as the filter cake has built up on the bottom fabric of the Isolator Row.
- Current data shows a TSS removal efficiency which exceeds 80%.

Removal Efficiency Results:

- Total Suspended Solids = 80%
- Phosphorous = 49%
- Total Petroleum Hydrocarbons = 90%
- Zinc = 53%

This system achieves a removal efficiency of 80% for TSS which meets most municipal recommended levels for water quality treatment.



Inspection and Maintenance

The Isolator Row can be inspected through the upstream manhole or optional inspection port.

Maintenance is easily accomplished with the JetVac process.

The frequency of inspection and maintenance varies by location. Contact StormTech for assistance with inspection and maintenance scheduling.



Isolator[®] Row O&M Manual



THE ISOLATOR[®] ROW

INTRODUCTION

An important component of any Stormwater Pollution Prevention Plan is inspection and maintenance. The StormTech Isolator Row is a technique to inexpensively enhance Total Suspended Solids (TSS) and Total Phosphorus (TP) removal with easy access for inspection and maintenance.

THE ISOLATOR ROW

The Isolator Row is a row of StormTech chambers, either SC-160, SC-310, SC-310-3, SC-740, DC-780, MC-3500 or MC-4500 models, that is surrounded with filter fabric and connected to a closely located manhole for easy access. The fabric-wrapped chambers provide for settling and filtration of sediment as storm water rises in the Isolator Row and ultimately passes through the filter fabric. The open bottom chambers and perforated sidewalls (SC-310, SC-310-3 and SC-740 models) allow storm water to flow both vertically and horizontally out of the chambers. Sediments are captured in the Isolator Row protecting the storage areas of the adjacent stone and chambers from sediment accumulation.

A woven geotextile fabric is placed between the stone and the Isolator Row chambers. The woven geotextile provides a media for stormwater filtration, a durable surface for maintenance, prevents scour of the underlying stone and remains intact during high pressure jetting. A non-woven fabric is placed over the chambers to provide a filter media for flows passing through the perforations in the sidewall of the chamber. The non-woven fabric is not required over the SC-160, DC-780, MC-3500 or MC-4500 models as these chambers do not have perforated side walls.

The Isolator Row is typically designed to capture the “first flush” and offers the versatility to be sized on a volume basis or flow rate basis. An upstream manhole provides access to the Isolator Row and typically includes a high flow weir. When flow rates or volumes exceed the Isolator Row weir capacity the water will flow over the weir and discharge through a manifold to the other chambers.

Another acceptable design uses one open grate inlet structure. Using a “high/low” design (low invert elevation on the Isolator Row and a higher invert elevation on the manifold) an open grate structure can provide the advantages of the Isolator Row by creating a differential between the Isolator Row and manifold thus allowing for settlement in the Isolator Row.

The Isolator Row may be part of a treatment train system. The design of the treatment train and selection of pretreatment devices by the design engineer is often driven by regulatory requirements. Whether pretreatment is used or not, the Isolator Row is recommended by StormTech as an effective means to minimize maintenance requirements and maintenance costs.


Note: See the StormTech Design Manual for detailed information on designing inlets for a StormTech system, including the Isolator Row.



Looking down the Isolator Row from the manhole opening, woven geotextile is shown between the chamber and stone base.



StormTech Isolator Row with Overflow Spillway (not to scale)





ISOLATOR ROW INSPECTION/MAINTENANCE

INSPECTION

The frequency of inspection and maintenance varies by location. A routine inspection schedule needs to be established for each individual location based upon site specific variables. The type of land use (i.e. industrial, commercial, residential), anticipated pollutant load, percent imperviousness, climate, etc. all play a critical role in determining the actual frequency of inspection and maintenance practices.

At a minimum, StormTech recommends annual inspections. Initially, the Isolator Row should be inspected every 6 months for the first year of operation. For subsequent years, the inspection should be adjusted based upon previous observation of sediment deposition.

The Isolator Row incorporates a combination of standard manhole(s) and strategically located inspection ports (as needed). The inspection ports allow for easy access to the system from the surface, eliminating the need to perform a confined space entry for inspection purposes.

If upon visual inspection it is found that sediment has accumulated, a stadia rod should be inserted to determine the depth of sediment. When the average depth of sediment exceeds 3 inches throughout the length of the Isolator Row, clean-out should be performed.


MAINTENANCE

The Isolator Row was designed to reduce the cost of periodic maintenance. By “isolating” sediments to just one row, costs are dramatically reduced by eliminating the need to clean out each row of the entire storage bed. If inspection indicates the potential need for maintenance, access is provided via a manhole(s) located on the end(s) of the row for cleanout. If entry into the manhole is required, please follow local and OSHA rules for a confined space entries.

Maintenance is accomplished with the JetVac process. The JetVac process utilizes a high pressure water nozzle to propel itself down the Isolator Row while scouring and suspending sediments. As the nozzle is retrieved, the captured pollutants are flushed back into the manhole for vacuuming. Most sewer and pipe maintenance companies have vacuum/JetVac combination vehicles. Selection of an appropriate JetVac nozzle will improve maintenance efficiency. Fixed nozzles designed for culverts or large diameter pipe cleaning are preferable. Rear facing jets with an effective spread of at least 45” are best. Most JetVac reels have 400 feet of hose allowing maintenance of an Isolator Row up to 50 chambers long. **The JetVac process shall only be performed on StormTech Isolator Rows that have AASHTO class 1 woven geotextile (as specified by StormTech) over their angular base stone.**

StormTech Isolator Row (not to scale)

Note: Non-woven fabric is only required over the inlet pipe connection into the end cap for SC-160LP, DC-780, MC-3500 and MC-4500 chamber models and is not required over the entire Isolator Row.



ISOLATOR ROW STEP BY STEP MAINTENANCE PROCEDURES

STEP 1

Inspect Isolator Row for sediment.

- A) Inspection ports (if present)
 - i. Remove lid from floor box frame
 - ii. Remove cap from inspection riser
 - iii. Using a flashlight and stadia rod, measure depth of sediment and record results on maintenance log.
 - iv. If sediment is at or above 3 inch depth, proceed to Step 2. If not, proceed to Step 3.
- B) All Isolator Rows
 - i. Remove cover from manhole at upstream end of Isolator Row
 - ii. Using a flashlight, inspect down Isolator Row through outlet pipe
 - 1. Mirrors on poles or cameras may be used to avoid a confined space entry
 - 2. Follow OSHA regulations for confined space entry if entering manhole
 - iii. If sediment is at or above the lower row of sidewall holes (approximately 3 inches), proceed to Step 2. If not, proceed to Step 3.

STEP 2

Clean out Isolator Row using the JetVac process.


- A) A fixed floor cleaning nozzle with rear facing nozzle spread of 45 inches or more is preferable
- B) Apply multiple passes of JetVac until backflush water is clean
- C) Vacuum manhole sump as required

STEP 3

Replace all caps, lids and covers, record observations and actions.

STEP 4

Inspect & clean catch basins and manholes upstream of the StormTech system.



SAMPLE MAINTENANCE LOG

Date	Stadia Rod Readings		Sediment Depth (1)-(2)	Observations/Actions	Inspector
	Fixed point to chamber bottom (1)	Fixed point to top of sediment (2)			
3/15/11	6.3 ft	none		New installation. Fixed point is CI frame at grade	DJM
9/24/11		6.2	0.1 ft	Some grit felt	SM
6/20/13		5.8	0.5 ft	Mucky feel, debris visible in manhole and in Isolator Row, maintenance due	NV
7/7/13	6.3 ft		0	System jetted and vacuumed	DJM

