


Total Impervious Surace area outline = 30,637 sf $\frac{634 \text{ sf}}{30,003 \text{ sf}}$ Total Interior Permeable Surface Areas = Total (Net) Impervious Surface Areas = Total Lot Size = 54,505 sf Total Impervious Lot Coverage = 30,003 / 54,505 =


PREVIOUS / EXISTING IMPERVIOUS SURFACE AREA (55.0%)




Proposed Impervious Surface Area:

Total Impervious Surace area outline = 38,554 sf 1,773 sf 36,781 sf Total Interior Permeable Surface Areas = Total (Net) Impervious Surface Areas = Total Lot Size = 54,505 sf 67.5% Total Impervious Lot Coverage = 36,781 / 54,505 =

PROPOSED IMPERVIOUS SURFACE AREA (67.1%)





Existing / Previous Building Coverage:

<u>6,046 sf</u> <u>54,505 sf</u> Total Building Coverage = Total Lot Size = Total Building Coverage = 6,046 / 54,505 = 11.1%

PREVIOUS / EXISTING BUILDING COVERAGE (11.1%) Proposed Building Area Including Walk-In Cooler = 7385 sf Existing / Proposed Lot Area = 54,505 sf

License No. 20338

Proposed Building Coverage:

7,385 sf 54,505 sf Total Building Coverage = Total Lot Size = Total Building Coverage = 7,385 / 54,505 = 13.5%

PROPOSED BUILDING COVERAGE (13.5%)

SITE / GRADING PLAN - BUILDING COVERAGE IMPERVIOUS SURFACE AREAS **MARINO'S RESTAURANT**

Prepared For

Cheryl and Christian Marino

LAUREL ENGINEERING, LLC

Submitted:

Civil, Seismic, Structural Consultants 48 Center Street - Winsted, Connecticut 06098

09/24/20

Phone (860) 379-6898 E-Mail laureleng@earthlink.net Drawing No. Project No.: 20-105 As Noted RCSite-Plan... .dwg File Name: Drawn By:

09/23/20

Revised Through:

1B



Approved by the City of Torrington Planning and Zoning Commission Sheets 1 through 5 Inclusive Final Approval: Chairperson Date: Expiration Date:

SITE OVERLAY

MARINO'S RESTAURANT

Prepared For Cheryl and Christian Marino

Torringtor

LAUREL ENGINEERING, LLC

Connecticut

License No. 20338 Civil, Seismic, Structural Consultants
48 Center Street - Winsted, Connecticut 06098

Phone (860) 379–6898

Scale:


NTS


Project No.: 20–105


Drawing No.

The Name: Site-Plan....dwg

Revised Through: 09/23/20 Submitted: 09/24/20








6' -0" SUPPORT POST (2' MIN. EMBEDMENT) PLANTING MEDIUM — 4" WOOD-CHIP MULCH FEARTH SAUCER 6" DEEP FINISHED GRADE \ ~4" WOOD-CHIP MULCH EXTENDED 18" BEYOND EARTH SAUCER TYP. VARIES TWICE ROOT BALL DIAMETER MIN SECTION / D

DOUBLE STRAND NO. 12 GAUGE — GALVANIZED WIRE TWIST TO TIGHTEN. PLASTIC OR RUBBER -TREE BALL OR HOSE TYP. ROOT SPREAD

MANCHOR STAKE TYP.

STAKING FOR MULTI-STEMMED DECIDUOUS TREES FROM 5'(1.5m) TO 10'(3.0m) HIGH



GALVANIZED WIRE TWIST —/
TO TIGHTEN TYP. (SEE NOTE 4)

STAKING PLAN

PLAN

GALVANIZED WIRE TWIST —/
TO TIGHTEN TYP. (SEE NOTE 3)


Approved by the City of Torrington Planning and Zoning Commission

Chairperson

Sheets 1 through 5 Inclusive

<u>Final Approval:</u>

Expiration Date:



*** UNLESS OTHERWISE DIRECTED, WOOD-CHIP MULCH SHALL BE PLACED TO A LIMIT OF 18" (457) BEYOND THE CENTER OF THE OUTERMOST SHRUBS IN SHRUB BED.

PLANTING FOR SHRUBS IN BEDS

PLANTINGS TABLE


COMMON NAME	BOTANICAL NAME	NO.	QTY.	SIZE
Flowering Crab Apple (prairie fire)	Malus (ionsis)	1	2	2" to 2.5"
Laurel	Kalmia Latifolia	2	7	15" — 18"
Red Maple	Acer Rubrum	3	1	2" TO 2.5"
Day Lily	Lillium	4	100	1 gal.
Arborvitae Dark American	Thuja occidentalis	5	10	8' (Height)
Rhododendron Azalea	P.J.M.	6	6	3 gal.
Eastern White Pine	Pinus Strobus	7	5	2" to 2 1/2"

All beds shall be covered with 3" of bark mulch


All other un-paved areas shall receive a 4" layer of loam, lime, grass seed and mulch.

GENERAL NOTES:

- 1. THE PLANTING PIT SIZE SHALL BE TWICE THE DIAMETER OF THE ROOT BALL IN WIDTH AND 2" LESS THAN THE HEIGHT OF THE ROOT BALL.
- 2. ALL EXTERIOR PACKAGING MATERIAL APPLIED TO PLANTS SHALL BE REMOVED AFTER THE PLANT IS LOCATED IN THE PLANTING PIT. CUT AND REMOVE TWINE, BURLAP OR WIRE BASKETS FROM THE TOP 2/3RDS OF THE ROOT BALL.
- 3. USE DOUBLE STRAND NO. 12 WIRE FOR DECIDUOUS TREES GREATER THAN OR EQUAL TO 3" CALIPER AND USE DOUBLE STRAND NO. 10 WIRE FOR EVERGREEN TREES GREATER THAN OR EQUAL TO 8"(203) CALIPER.
- 4. TREE TRUNK WRAPPING MATERIAL SHALL BE USED AS DIRECTED BY THE ENGINEER.
- 5. PLANTING PITS FOR INDIVIDUAL SHRUBS ON SLOPES SHALL BE THREE TIMES THE DIAMETER OF THE ROOT
- 6. CALIPER (SIZE) SHALL BE MEASURED AT 6" ABOVE FINISHED GRADE



SECTION PLANTING FOR SHRUBS IN INDIVIDUAL PITS ON SLOPES



NOTE: PLACE PLANTS AT THE SAME DEPTH THAT THE SEEDLING WAS GROWN IN THE NURSERY.

PLANTING FOR SEEDLINGS, VINES AND GROUND **COVER PLANTS IN PITS ON SLOPES**

LANDSCAPING DETAILS / NOTES

MARINO'S RESTAURANT

Prepared For Cheryl and Christian Marino

Torrington


License No. 20338


Connecticus LAUREL ENGINEERING, LLC


48 Center Street - Winsted, Connecticut 06098


Phone (860) 379-6898 E-Mail laureleng@earthlink.net Drawing No. *Project No.:* | 20-105 As Noted **2B** File Name: Drawn By: Landsc... .dwg Revised Through: 09/10/20 Submitted: | 09/24/20

Civil, Seismic, Structural Consultants












TYPE C-L CATCH BASIN




TYPICAL WATER SERVICE TRENCH DETAIL NTS




TYPICAL STORM SEWER TRENCH DETAIL NTS




TYPICAL SANITARY **SEWER TRENCH DETAIL** NTS






DUMPSTER SCREENING DETAIL NTS



UTILITY NOTES:

- 1. COORDINATE TEMPORARY AND PERMANENT ELECTRICAL SERVICE INSTALLATION WITH THE ELECTRICAL UTILITY SERVICE COMPANY. ALL TEMPORARY SERVICES SHALL BE PLACED TO ENSURE THEIR SAFETY DURING CONSTRUCTION AND SHALL BE COMPLETELY REMOVED WHEN USE IS DISCONTINUED.
- 2. COORDINATE SECURITY, TELEPHONE, CABLE TV AND INTERNET TECHNOLOGY SERVICES WITH HE INDIVIDUAL UTILITY SERVICE COMPANIES.
- 3. COORDINATE SANITARY SEWER CONNECTION TO CITY SERVICE LATERALS WITH THE DEPARTMENT OF PUBLIC WORKS. THE WATER POLLUTION CONTROL AUTHORITY AND THE CITY ENGINEER.
- 4. COORDINATE STORM SEWER CONNECTIONS TO CITY STORM WATER SYSTEMS WITH THE CITY'S DEPARTMENT OF PUBLIC WORKS AND CITY ENGINEER.
- 5. COORDINATE WATER SERVICE CONNECTIONS WITH THE TORRINGTON WATER COMPANY.
- 6. CONTACT AND IMPLEMENT CALL-BEFORE-YOU-DIG SERVICES PRIOR TO ANY SITE EXCAVATION. (1-800-922-4455)



File Name:

Submitted: 09/24/20

Utility-Plan.dwg

RC

Revised Through: 09/23/20

Drawn By:

SOIL EROSION AND SEDIMENT CONTROL PLAN NARRATIVE

PREPARED USING CURRENT CONNECTICUT GUIDELINES FOR SOIL EROSION AND SEDIMENT CONTROL

1. INTRODUCTION AND PERMIT COMPLIANCE

Pursuant to Connecticut P.A. 83—388, this project requires a Soil Erosion and Sediment Control Plan

This narrative describes the minimum measures required to control soil erosion during and after construction of the sitework shown on this plan. The soil erosion and sediment control measures shown on this plan are designed in accordance with a document entitled "Connecticut Guidelines for Soil Erosion and Sediment Control" as most recently published by the Connecticut Council on Soil and Water Conservation. The contractor may be required to implement additional measures to prevent site erosion

The contractor is required to obtain copies of, and comply with the conditions of all permits for this project, including but not limited to:

* Municipal Inland Wetlands Permit * Municipal Approval of the Erosion Control Plan

and sedimentation of downstream waterways.

The contractor's activities and operations include all site work and work incidental to the project including, but not limited to haul roads, waste and disposal areas, staging areas, and field offices. If any of his activities require approvals above and beyond those already accounted for by the Owner's permits, the contractor shall apply for and obtain such permits prior to conducting those operations.

2. PROJECT AND DESCRIPTION OF PROJECT

The project plans show the construction of a new 7385 sf restaurant and the clearing for, formation of subgrade and subsequent construction of a parking areas associated with the restaurants use. The subject property is located at 12 Pinewoods Road, Torrington, CT.

3. CONSTRUCTION SEQUENCING

Construction sequencing may be as follows:

- 1. Prepare site for activity
- Install construction entrance 3. Install erosion and sediment control measures (silt fencing is shown on plans — hay bales may be
- Remove vegetation within the clearing limits
- 5. Remove existing layer of topsoil where excavation is required and stockpile upgradient of all erosion control measures within project clearing limits.
- Excavate for and prepare driveway and parking area subgrade keep construction entrance in-place Excavate for and install storm sewer and appurtenances.
- Building erection shall be performed simultaneously with site work. 9. Install light standards as determined by contractor and approved by the Town of Winchester.
- 10. Remove construction entrance Install processed aggregate base throughout drive and parking areas and bituminous concrete binder course.

11. Install BCLC and bituminous concrete wearing surface. Install HC ramps. 12. Install landscape features, finish lighting and provide topsoil and turf establishment in all disturbed

13. Upon strong establishment of turf and vegetative features remove erosion control measures.

The Engineer estimates the single phase construction activities to be completed within 12—36 weeks of

Erosion control measures shall remain in-place until turf has been established in all disturbed areas.

4.1 RESPONSIBILITIES OF OWNER The Owner is: Marinos LLC 12 Pinewoods Road Torrington CT 06790 — Telephone number (860)

4. RESPONSIBILITY

- A. Provide the contractor / future owners with copies of land—use permits that owner has acquired. B. Inform all parties involved with the proposed site work of this plan's objectives and requirements.
- 4.2 RESPONSIBILITIES OF CONTRACTOR
- The contractor is responsible for preventing erosion of the site and for protecting adjacent waterways from sedimentation.
- The contractor shall:
- A. Install, monitor, and maintain all of the soil erosion and sediment control measures as shown on
- C. Provide the Owner, Engineer, and the municipality with 24 hour phone numbers in the event of an emergency at the site.

5. DESCRIPTION AND MAINTENANCE OF EROSION CONTROL MEASURES

5.1 TEMPORARY STABILIZATION MEASURES

Silt Fence / Straw Bales:

Install silt fence as shown on the plans and details. Embed the silt fence into the ground and firmly anchor it as shown in the details. Remove sediment once levels have reached 1/4 of the effective fence—height or straw bales. Repair and/or replace silt fence immediately if damaged or deteriorated. See straw bale detail for proper installation.

Stockpiling or Storage of Excavated Materials:

Expiration Date:

There shall be minimal stockpiling of topsoil from leaching area. No other materials may be stockpiled

5.2 PERMANENT STABILIZATION MEASURES

Implement stabilization measure within three days of final grading.

Immediately following rough grading activities, bring all disturbed areas to final grade with four inches of

Loam shall be free of large stones and roots and other deleterious materials such as wood, pieces of pavement, metals, trash, etc. and shall be of such quality as to readily promote germination of grass

Prior to seeding, lime and fertilize according to soil test or, at a minimum, apply lime at a rate of 100 lbs./1000 sq. ft. and 10—10—10 fertilizer at a rate of 6 lbs./1000 sq. ft. Work lime and fertilizer into

Unless specified otherwise by an expert, apply grass seed at the following rates:

MIXTURE 1 LBS./1000 SF

Kentucky Bluegrass Creeping Red Fescue Perennial Ryegrass

MIXTURE 2 LBS./1000 SF

Creeping Red Fescue Tall Fescue or Smooth Bromegrass

Immediately after seeding operations, cover the seedbed with hay or straw mulch at a rate of 100 lbs./1000 sq. ft. Mulch must be free of weeds and coarse matter. Spread mulch by hand or by mulch blower. Mulch anchoring is required by tractor drawn anchoring device along contour, or by tracking with a bulldozer (cleats parallel to contour) on slopes flatter than 3H:1V. If not specifically required herein, anchored jute mesh or equal is preferred by the engineer but not required on slopes steeper than

The contractor shall irrigate all seeded areas until a stand of grass, acceptable to the Owner, is

The contractor shall be responsible for all seeded areas. If topsoil, seed, and/or mulch is washed away by rainfall, the contractor shall restore the area.

Shady areas 5 5

5.3 OTHER CONTROLS

Place clean washed stone (CONNDOT No.3 stone) at the site entrance(s) to the length, width and depth indicated on the plans and details to help remove mud and/or clods of soil from construction vehicles exiting from the site. Add stone as necessary to maintain adequate serviceability.

Stone swales shall be installed as detailed on the project plans.

Where required on 2:1 slopes or steeper a jute mesh matting shall be provided and installed by the contractor upon request of the Construction Engineer or Town of Winchester.

Sediment Protection at Catch Basins:

All catch basins shall be protected from sediment during construction with the use of sand and or gravel filled bags. The bags shall be placed around the catch basin to minimize the migration of sediment into the storm sewer system during construction. the bags shall be placed to a depth of 18" high and sediment should be periodically removed from the sediment trap areas..

6. GENERAL CONDITIONS

6.1 If erosion control measures are damaged by construction vehicles, acts of vandalism, or severe weather conditions, the contractor shall immediately remove sediment in the vicinity of the erosion control measures and repair these measures to a functional condition.


6.2 If, during or after construction, it becomes apparent that existing erosion control measures are incapable of controlling erosion, the owner, the engineer, or the municipality may require additional control measures including, but not limited to; additional hay bales, silt fence, sediment basins, or

6.3 Refueling of equipment or machinery within 25 feet of any wetland or watercourse is prohibited.


6.4 No materials resulting from construction activities shall be placed in or allowed to contribute to the degradation of an adjacent wetland or watercourse. Disposal of any material shall be in accordance with Connecticut General Statutes, including, but not limited to, Sections 22a-207 through

6.5 Stabilize all temporary fill to prevent erosion and to prevent sediment or other particulate matter from reentering a wetland or watercourse. Restore and revegetate all areas affected by temporary fills to their original contours or as directed by the Owner. Confine the extent of temporary fill or excavation to that area necessary to perform the work, as approved by the Owner.


6.6 Dumping of oil, chemicals or other deleterious materials on the ground is forbidden. The contractor shall provide a means of catching, retaining, and properly disposing of drained oil, removed oil filters, or other deleterious material. All spills of such materials shall be reported immediately by




CONSTRUCTION ENTRANCE NTS



SEDIMENTATION AND EROSION CONTROL (FILTER FABRIC SYSTEM) NTS



PLAN VIEW



PROTECTION AT CATCH BASIN

NOTES:

than 0.5"


1. Place hay bales on contour and wing last hay bales upslope so that the top of last hay bales are higher than the line of straw bales. 2. Stake all hay bales. 3. Maintain and remove sediment deposits as required during

construction. 4. Regular maintenance shall include but not be limited to the following; a.) Removal of sediment build—up

b.) Replacement of damaged units c.) minimum inspection requirements include at least once per week or within 24hrs

of a precipitation event greater

SEDIMENTATION AND EROSION CONTROL (HAY-BALE SYSTEM) NTS



SOIL EROSION / SEDIMENTATION CONTROL **NARRATIVE AND DETAILS** MARINO'S RESTAURANT

Prepared For Cheryl and Christian Marino

Torrington

LAUREL ENGINEERING, LLC

Civil, Seismic, Structural Consultants 49 Center Street - Winsted, Connecticut 06098

Phone (860) 379-6898 As Noted 20-105 Project No.: SESC-Plan.dwg Drawn By: File Name: Revised Through: 09/23/20 Submitted: 09/24/20

E-Mail laureleng@earthlink.net Drawing No.

Connecticu

Sheets 1 through 5 Inclusive Final Approval: Chairperson

Approved by the City of Torrington Planning and Zoning Commission